### TRURO PLANNING BOARD AGENDA Wednesday, October 23, 2019 – 6:00 p.m. Truro Town Hall, 24 Town Hall Road, Truro

### **Public Comment Period**

The Commonwealth's Open Meeting Law limits any discussion by members of the Board of an issue raised to whether that issue should be placed on a future agenda. Speakers are limited to no more than 5 minutes.

### **Temporary Sign Permit Applications**

Erik Spencer – First Parish Thanksgiving Service, for one (1) sign, 36" x 24" to be located on the east side of Route 6, south of Union Field Road. The sign will be installed on October 28<sup>th</sup> and removed November 29<sup>th</sup> for an event on November 28<sup>th</sup>.

Erik Spencer – First Parish Candlelight Service, for one (1) sign, 36" x 24" to be located on the east side of Route 6, south of Union Field Road. The sign will be installed on November 29<sup>th</sup> and removed December 29<sup>th</sup> for an event on December 24<sup>th</sup>.

### **Informal Consultation**

Regan McCarthy – 35A Higgins Hollow Road (Map 47, Parcel 2), informal consultation with the Planning Board regarding potential development on the above listed property.

### **Board Action/Review**

Update on past Work Sessions.

Update on Planning Board/Select Board ADU Ad Hoc Subcommittee Work Sessions.

Discussion and approval of Commercial Site Plan Review packet.

Discussion for setting dates for future Board public workshops.

### **Next Meeting**

Wednesday, November 6, 2019, at 5:00 p.m.; please note time change

### Adjourn

Site visits: None





## **TOWN OF TRURO**



# PLANNING BOARD

Fee: \$25.00

Application for Temporary Sign Permit
Pursuant to Section 11 of the Truro Sign Code

Office of Town Cler Treasurer – Tax Colle 25.00 Pd OCT -8 2019 Received TOWING

Applicant Name: Erik Spencer	Date: _/0/7/19
Applicant Contact Information: Mailing Address	
	rencer10 O Jer; zon. n
Number of Signs Requested:	
Temporary Sign Dimensions: Height 36 Width 24	the proposed sign(s)
Location(s) of Proposed Temporary Sign(s): egst 5.de	e of RtG, south of
Map(s): Parcel(s): Please use ad	ditional sheet(s) for multiple locations
Date(s) of the Event in Which the Sign is Intended: 1/28	
Date When Sign(s) will be: Installed: 10/28/19	Removed: 11/2 9/19
Name and Address of Property Owner(s) Where Temporary S	
Name Mailing Address	
Phone Email	
Applicant Signature Oct 7 Date	2019
Owner Signature (which also authorizes the use of the property)  Date	
Planning Board Action: Approved Approved w/Condition	ons Denied
Conditions:	
	Oate:
CC: Building Commissioner, Board of Selectmen	

# FIRST PARISH TRURO, COM



T-GIVING MORNING

THANKSGIVING SERVICE

## **TOWN OF TRURO**

- CC: Building Commissioner, Board of Selectmen



## PLANNING BOARD

Application for Temporary Sign Permit
Pursuant to Section 11 of the Truro Sign Code

Fee: \$25.00

Applicant Name: ENK	Spencer	Date: 10/7/19	
Applicant Contact Information: Mailing	Dhidal Way	Wallfleet 02667	٠
508-214-0083 Phone			
Number of Signs Requested:			
Temporary Sign Dimensions: Height	6 6" Width 24"	Please attach a "to scale" copy of the proposed sign(s).	
Location(s) of Proposed Temporary Sign(		2 2	
Map(s): Parcel(s):			
Date(s) of the Event in Which the Sign is I	170		
Date When Sign(s) will be: Installed:			
Name and Address of Property Owner(s)	Where Temporary Sign(	s) to be located:	
Name	Mailing Address		
Phone	Email		
Ed Speur	Date Date	2019	
Owner Signature (which also authorizes the use of the proper	rty) Date		
Planning Board Action: Approved	Approved w/Conditions	Denied	
Conditions:		9	
Board Signature:	Date	: :	

Office of Town Clerk Treasurer - Tax Collector 25.00 Pd

# FIRST PARISH TRURO COM



SHRISTMAS

CANDLELIGHT SERVICE

# INFORMAL CONSULTATION

Regan McCarthy – 35A Higgins Hollow Road (Map 47, Parcel 2), informal consultation with the Planning Board regarding potential development on the above listed property

# **BOARD ACTION / REVIEW**



## **Town of Truro Planning Board**

P.O. Box 2030, Truro, MA 02666

# PROCEDURE FOR SUBMITTING APPLICATION FOR COMMERCIAL SITE PLAN REVIEW

A completed application consisting of each of the requirements of §70 will be filed as follows:

- fifteen (15) packets to be filed with the Town Clerk; AND
- a complete copy, including all plans and attachments, submitted electronically to the Town Planner at <a href="mailto:planner1@truro-ma.gov">planner1@truro-ma.gov</a>.

The following information and requirements must be filed with all applications for Commercial Site Plan Review consistent with the Rules, Regulations and Fee Schedule of the Truro Planning Board.

1 – Official Application Form – Original and Fourteen (14) Copies  Every application for action by the Board shall be made on an official form. Any communications purporting to be an application shall be treated as mere notice of intention until such time as it is made on an official application form accompanied by all requisite supporting data.
2 - Required Plan(s) and Other Information including Checklist (Fifteen (15) Copies) Every application and petition to the Board shall be accompanied by all the plans and other information required in the Zoning Bylaw. The application shall include each of the requirements of §70 as listed in the attached Checklist which is to be submitted as part of the official application.
3 – Criteria Review Applicant will briefly state how they meet each of the review criteria in §70 using the format provided in this packet.
4 – Certified Abutters List – Original and Fourteen (14) Copies  A Certified Abutters List shall be obtained by the Applicant from the Truro Assessors Office and filed as part of the complete application. A copy of the "Certified Abutters List Request Form" is included in this packet.
5 – Filing Fee All applications shall be filed with the Town Clerk and shall be accompanied by a check payable to the Town of Truro in the amount of \$250.00. The filing fee is non-refundable.

### ONCE A COMPLETED APPLICATION HAS BEEN RECEIVED

- Town Planner will determine if an Application is complete. Upon determination an Application is complete, the Planning Board will then proceed to post notice of a public hearing in accordance with Section 11 of Chapter 40A of the General Laws of Massachusetts.
- Either you or your agent/representative shall appear before the Board at the scheduled hearing. If you need to reschedule, you must submit a request in writing for a continuance, using Town of Truro Continuance Request Form.
- Additional information may be submitted prior to the scheduled public hearing provided it is received no less than ten (10) days prior to the hearing so that it can be included in the packet for Board Members to read and review. Submit fifteen (15) paper copies AND an electronic copy to the Town Planner (at planner1@truro-ma.gov). Plans must be submitted to the Town Clerk for filing. Information received less than ten (10) days before the scheduled hearing may result in a continuance of the hearing. New material brought to the meeting, that has not previously been filed/submitted, will not be reviewed at that meeting.

Please do not include a copy of these instructions with the application




# Town of Truro Planning Board P.O. Box 2030, Truro, MA 02666

### APPLICATION FOR COMMERCIAL SITE PLAN REVIEW

To the Town Clerk and the Planning Board of the	Town of Truro, MA Date
The undersigned hereby files an application with the	he Truro Planning Board for the following:
Site Plan Review pursuant to	§70 of the Truro Zoning Bylaw
	ursuant to §70.9 of the Truro Zoning Bylaw  Il not be waived in the Seashore District)
	Map(s) and Parcel(s)
Registry of Deeds title reference: Book	, Page, or Certificate of Title
	Lot # and Plan #
Applicant's Name	
Applicant's Phone(s), Fax and Email	
Applicant is one of the following: (please check appr	
Owner Prospective Buyer	required for submittal of this application.  *
requirements of §70.3.D, provided that in the opinion to the public interest, cause the Town any expense, request for a waiver by the applicant shall be acc	y, upon the request of the applicant, pursuant to §70.3.E, waive on of the Planning Board such a waiver would not be detrimental , or be inconsistent with the intent and purpose of this Bylaw. A companied by a reasonable explanation as to why the waiver is , the applicant shall explain why each waiver is requested.
The applicant is <i>advised</i> to consult with the Department, and/or Health Department prior to	Building Commissioner, Planning Department, Conservation submitting this application.
Signature(s)	
Applicant(s)/Representative Printed Name(s)	Owner(s) Printed Name(s) or written permission
Applicant(s)/Representative Signature(s)	Owner(s) Signature(s) or written permission

Your signature on this application authorizes the Members of the Planning Board and town staff to visit and enter upon the subject property.



Address:	Applicant Name:		Date:	
No.	Requirement	Included	Not Included	Explanation, if needed
D. Proc	Procedures and Plan Requirements			
1a.	An original and 14 copies of the Application for Site Plan Review			
1b.	15 copies of the required plans and other required information including this Checklist			
1c.	Completed Criteria Review			
1d.	Certified copy of the abutters list obtained from the Truro Assessors Office			
1e.	3 copies of drainage calculations stamped by a Professional Engineer			
1f.	Applicable filing fee			
1g.	Any other information that may be applicable or required by the Planning Board			
	Site Plans			
20	Site Plans shall be prepared, signed and stamped by a Registered Land Surveyor and			
7a.	Professional Engineer			
2b.	Site Plans shall be prepared at a scale of one inch equals forty feet (1"=40") or larger			
3a.	General - Submitted plans shall contain the following:			
	North Arrow/Location Map: A north arrow and a locus plan containing sufficient			
3a. 1	information to locate the subject property, such as streets bounding or providing access to the			
	property.			
	Zoning Information: All applicable Zoning Bylaw information regarding the site's development, both existing and proposed. This information shall be placed in a table formation.			
3a. 2	which must list all parking; setbacks; percent of lot coverage, broken down by parking,			
	walkways, building(s), etc.; number of dwelling units; total amount of square feet; size of			
	signs, and any other applicable zoning information necessary for the proper review of the site			
	plan.			
	Existing:			
	All parking			
	All setbacks			
	Percent (%) of lot coverage broken down by parking, walkways, building(s), etc.			
	Number of dwelling units			

Address:	Applicant Name:		Date:	
No.	Requirement	Included	Not Included	Explanation, if needed
	Total amount of square feet			
	Size of signs			
	Any other applicable zoning information necessary for the proper review of the			
	site plan			
	Proposed:			
	All parking			
	All setbacks			
	Percent (%) of lot coverage broken down by parking, walkways, building(s), etc.			
	Number of dwelling units			
	Total amount of square feet			
	Size of signs			
	Any other applicable zoning information necessary for the proper review of the			
	site plan			
3a. 3	Assessor and Deed Information: The Truro Assessors Atlas Map(s) and Parcel(s) numbers and all plan and deed references.			
3a. 4	Graphic Scale			
3a. 5	Title Block - Including:			
	Name and description of the project			
	Address of the property			
	Names of the record owner(s) and the applicant(s)			
	Date of the preparation of the plan(s) and subsequent revision dates			
3a. 6	Legend of all symbols			
3b.	Existing Conditions Plan - showing the following:			
3b. 1	Total area and dimensions of the lot shown on a surveyed plan conforming to the requirements of the Barnstable County Registry of Deeds.			
3b. 2	Location of existing buildings (including the number of stories, overall height in feet, and gross floor area in square feet of all existing buildings), parking, drives, walks, lighting service areas, all utilities, drainage facilities, easements, and other appurtenances, including setbacks from property lines.			

Address:	Applicant Name:		Date:	:
No.	Requirement	Included	Not Included	Explanation, if needed
	Location of existing buildings			
	Number of stories			
	Overall height in feet			
	Gross floor area in square feet			
	Parking			
	Drives			
	Walks			
	Lighting service areas			
	All utilities			
	Draining facilities			
	Easements			
	Other appurtenances			
	Setback from property lines			
3b. 3	Existing contours based on two foot (2) contour intervals.			
3b. 4	General location of trees having a caliper of ten (10) inches or more diameter at breast height (DBH), all resource areas as defined in M.G.L. Chapter 131, Section 40, landscaping and other significant natural features.			
3b. 5	Respective floor areas and/or square footage of existing uses of buildings and/or the property.			
3b. 6	Existing location(s) of any freestanding sign(s).			
3b. 7	National Flood Insurance Program flood hazard elevation.			
3b. 8	Massachusetts Natural Heritage Endangered Species Act jurisdiction.			
Зс.	Proposed Conditions Plan - showing the following:			
3c. 1	Building Location: Identification of all building(s) to be located on the site. The number of stories, overall height in feet and gross floor area in square feet of all buildings shall be indicated.			
3c. 2	Building Elevation: A drawing(s) of the exterior of all building(s), as viewed from all sides, including dimensions, at a scale of no smaller than 1/8" = 1'-0". This drawing must be at least 8" x 11" in size.			

Address	S: Applicant Name:		Date:	
No.	Requirement	Included	Not Included	Explanation, if needed
3c. 3	Location of Parking/Walkways: Identification of the location of all parking and walkways, including curb cuts that will be used for site access from adjacent roadways or access points. Parking shall be consistent with the requirements outlined in §30.9.			
3c. 4	Easements/Legal Conditions: Identification of legal encumbrances(s), including easements, that are related to the site's physical development, and a listing of any condition(s) placed upon the site by the Board of Appeals, Planning Board, Conservation Commission, Board of Health or any other public body or agency with the authority to place conditions on the site's development.			
3c. 5	Stormwater Drainage: All storm water drainage facilities utilized by the site shall be shown on the site plan. Storm water drainage calculations, which support the design of the control facilities shown on the plan, shall be calculated using a 2, 10, and 50-year storm events.			
3c. 6	Grades: Topography and a grading plan of the site.			
3c. 7	Location of Walls: Identification of the location, height and materials to be used for all retaining walls to be located on the site.			
3c. 8	Signs: Identification of the location, height and materials to be used for all signs to be located on the site. Signs will be reviewed using the Town of Truro Sign Code section of the zoning bylaw.			
3c. 9	Location of Streets/Drives: Identification of all streets and driveways including the type and dimensions of curbs and gutters. Distances to all the nearest streets and/or curb cuts shall be shown for both sides of any street which is adjacent to the site.			
3c. 10	Outdoor Storage/Display Areas: Identification of the location and type of outdoor storage and display areas on the site.			
3c. 11	Refuse Areas: Identification of the location of each outdoor refuse storage area, including the method of storage and screening. All refuse areas must be fully enclosed.			

	Address: Applicant Name:		Dat	Date:
No.	Requirement	Included	Not Included	Explanation, if needed
3c. 12	Lighting Facilities: Identification of all illumination, indicating the direction and the degree of illumination offered by the lighting facilities and including specifications of the light fixture(s) to be used.			
3c. 13	Location of Wetlands/Notice of Intent: All resource areas as defined in M.G.L. Chapter 131, Section 40. The applicant shall file a Notice of Intent with the Truro Conservation Commission concurrently with the application to the Planning Board for Site Plan Review.			
3c. 14	Location and Description of Utilities. Identification of all utilities, including sewer line locations and profiles and storm drainage systems.			
3c. 15	Parking and Driveway Cross Section: a cross section identifying the proposed construction of driveways and parking areas on the site.			
3c. 16	Limit of work area (area to be disturbed during construction, including parking and storage of vehicles and equipment) and work staging area(s).			
3d. P	Proposed Landscaping Plan – showing the following:			
A 1	A landscape schedule for, and identification of, the location of all perimeter and interior			
* **	stonewalls; and all planting materials to be placed on the site. In addition, all existing trees			
o si	over 10 inches diameter at breast height (DBH) to be saved or removed shall be shown on the site plan.			
	Proposed paving materials for walkways			
	Fences			
	Stonewalls			
	All planting materials to be placed on the site			
	All existing trees over 10 inches diameter at breast height (DBH) to be saved or removed shall be shown on the site plan			
3e. B	Building Plans – at a scale of no less than 1/8" = 1'-0" showing the following:			
3e. 1	Elevations showing exterior materials and features including but not limited to doors, windows, trim, roof, lighting and including the height of the building(s).			
3e. 2	Floor plans with dimensions.			

Address:	Applicant Name:		Date:	
No.	Requirement	Included	Not Included	Explanation, if needed
3f.	Project Estimate:			
	The estimated date of initiation and the time required to complete the proposed project and any			
	and all phases thereot; together with a written cost estimate with a breakdown of the			
	building(s) and all site improvements.			
	Estimated date of initiation			
	Time required to complete the proposed project and any and all phases thereof			
	Written cost estimate with a breakdown of the building(s) and all site improvements			

### ADDRESSING THE REVIEW CRITERIA

### § 70.1 PURPOSE

The purpose of Site Plan Review for Commercial Development and for Residential Development is to protect the health, safety, convenience and general welfare of the inhabitants of the Town. It provides for a review of plans for uses and structures which may have significant impacts, both within the site and in relation to adjacent properties and streets; including the potential impact on public services and infrastructure; pedestrian and vehicular traffic; significant environmental and historic resources; abutting properties; and community character and ambiance.

<u>Instructions</u>: Please provide the Planning Board with a short explanation of how your application meets each of the review criteria of §70.3F of the Truro Zoning Bylaw. If you require extra space for your answers, please attach the additional information to your application in no more than two pages. This is to provide the Planning Board with an overview of your rationale prior to the meeting.

### §70.3F – REVIEW CRITERIA/DESIGN GUIDELINES

The Planning Board will review applications and their supporting information based on the following:

1.	The proposal is in conformity with all applicable provisions of the Zoning Bylaw because:
2.	The proposal provides for the protection of abutting properties and the surrounding area from
	detrimental site characteristics and from adverse impact from excessive noise, dust, smoke, or vibration higher than levels previously experienced from permitted uses because:
3.	The proposal provides for the protection of adjacent properties and the night sky from intrusive
	lighting, including parking lot and building exterior lighting. Lighting must be consistent with Chapter IV, Section 6 of the General Bylaws of the Town of Truro because:

1.	The proposal provides for the protection of significant or important natural, historic, or scenic features because:
5.	The building sites shall minimize obstruction of scenic views from publicly accessible locations; minimize tree, vegetation, and soil removal and grade changes; and maximize open space retention because:
5.	The proposal adequately provides for refuse disposal because:
7.	The proposed sewage disposal and water supply systems within and adjacent to the site shall be adequate to serve the proposed use because:
3.	The proposed drainage system within the site shall be adequate to handle the runoff resulting from the development. Drainage run-off from the project shall not: damage any existing wellfield(s) or public water supply; damage adjoining property; overload, silt up or contaminate any marsh swamp, bog, pond, stream, or other body of water; or interfere with the functioning of any vernal pool because:

9.	A soil erosion plan shall adequately protect all steep slopes within the site and control runoff to adjacent properties and streets both during and after construction because:				
10.	The proposal shall provide for structural and/or landscaped screening or buffers for storage areas, loading docks, dumpsters, rooftop or other exposed equipment, parking areas, utility buildings and similar features viewed from street frontages and residentially used or zoned premises because:				
11.	Buildings and structures within the subject site shall relate harmoniously to each other in architectural style, site location, and building exits and entrances. Building scale, massing, materials, and detailing should be compatible with the surrounding area because:				
12.	Electric, telephone, cable, and other such utility lines and equipment shall be placed underground because:				
13.	The project shall not place excessive demands on Town services because:				

14.	The location and number of curb cuts shall be minimized to reduce turning movements and hazardous exits and entrances. Where appropriate and allowable, access to adjoining properties shall be provided. Joint access driveways between adjoining properties shall be encouraged because:				
15.	Convenience and safety of vehicular and pedestrian movement within the site and in relation to adjacent and other ways serving the project shall be maximized. Traffic patterns for vehicles and pedestrians must show safe and adequate circulation within and access to and from the site because:				
16.	A bicycle rack(s) shall be provided on the site and shall be located near the entrance to the building(s) because:				



# **TOWN OF TRURO**

## Assessors Office Certified Abutters List Request Form

		DAIE:			
NAME OF APPLICANT:					
NAME OF AGENT (if any):					
MAILING ADDRESS:					
CONTACT: HOME/CELL	EMAIL				
PROPERTY LOCATION:					
PROPERTY LOCATION:(street address)					
PROPERTY IDENTIFICATION	NUMBER: MAP	PARCEL	EXT.		
			(if condominium)		
ABUTTERS LIST NEEDED FOR (please check <u>all</u> applicable)			\$15.00 per checked item ther arrangements are made)		
Board of Health <sup>5</sup>	Planning Board (PB)	Zoning	g Board of Appeals (ZBA)		
Cape Cod Commission	Special Permit <sup>1</sup>		Special Permit <sup>1</sup>		
Conservation Commission <sup>4</sup>	Site Plan <sup>2</sup>		Variance <sup>1</sup>		
Licensing	Preliminary Subdivisi	ion <sup>3</sup>			
Type:	Definitive Subdivisio	$n^3$			
	Accessory Dwelling \				
Other	(Please Specify)		(Fee: Inquire with Assessors)		
<u>Note</u> : Per M.G.L., proce	ssing may take up to 10 calen	dar days. Please pla	n accordingly.		
THIS SEC	CTION FOR ASSESSORS O	OFFICE USE ONLY			
Date request received by Assessors:		Date completed:			
List completed by:					

<sup>&</sup>lt;sup>1</sup>Abutters, owners of land directly opposite on any public or private street or way, and abutters to the abutters within 300 feet of the property line.

<sup>&</sup>lt;sup>2</sup>Abutters to the subject property, abutters to the abutters, and owners of properties across the street from the subject property.

<sup>&</sup>lt;sup>3</sup>Landowners immediately bordering the proposed subdivision, landowners immediately bordering the immediate abutters, and landowners located across the streets and ways bordering the proposed subdivision. <u>Note</u>: For Definitive Subdivision only, responsibility of applicant to notify abutters and produce evidence as required.

<sup>&</sup>lt;sup>4</sup>All abutters within 300 feet of parcel, except Beach Point between Knowles Heights Road and Provincetown border, in which case it is all abutters within 100 feet. Note: Responsibility of applicant to notify abutters and produce evidence as required.

<sup>&</sup>lt;sup>5</sup>Abutters sharing any boundary or corner in any direction – including land across a street, river or stream. <u>Note</u>: Responsibility of applicant to notify abutters and produce evidence as required.