

Truro Zoning Board of Appeals Agenda

Remote Meeting

Monday, December 18, 2023 – 5:30 pm www.truro-ma.gov

Join the meeting from your computer, tablet or smartphone: https://us02web.zoom.us/j/86729752759

Dial in: +1-646-931-3860 or +1-305-224-1968

Meeting ID: 867 2975 2759 Passcode: 434136

Open Meeting

This will be a remote public meeting. Citizens can view the meeting on Channel 8 in Truro and on the web on the "Truro TV Channel 8" button under "Helpful Links" on the homepage of the Town of Truro website (www.truroma.gov). Click on the green "Watch" button in the upper right corner of the page. Please note that there may be a slight delay (approx. 15-30 seconds) between the meeting and the television broadcast/live stream.

Citizens can join the meeting to listen and provide public comment by entering the meeting link; clicking on the agenda's highlighted link; clicking on the meeting date in the Event Calendar; or by calling in toll free. Citizens will be muted upon entering the meeting until the public comment portion of the hearing. If you are joining the meeting while watching the television broadcast/live stream, please lower or mute the volume on your computer or television during public comment so that you may be heard clearly. Citizens may also provide written comment via postal mail or by emailing Liz Sturdy, Planning Department Administrator, at <u>esturdy@truro-ma.gov</u>.

Public Comment Period

The Commonwealth's Open Meeting Law limits any discussion by members of the Board of an issue raised to whether that issue should be placed on a future agenda. Speakers are limited to no more than 5 minutes.

Minutes November 6, 2023

Public Hearing – Continued

2022-017/ZBA (VAR/SP) – Ebb Tide on the Bay Condominiums for property located at 538 Shore Road (Atlas Map 7, Parcel 7, Registry of Deeds title reference: Book 5671, Page 232). Applicant seeks an <u>Amended Variance</u> under M.G.L. Ch. 40A §10 and §40.3.B.2/§30.9.C of the Truro Zoning Bylaw for a reduction in number of parking spaces (from 12 spaces to <u>8</u>); a <u>Special Permit</u> under M.G.L. Ch. 40A §6 and §30.7.A of the Truro Zoning Bylaw for the relocation of three non-conforming structures on a lot in the Beach Point Limited Business District. [*Original material in 9/26/2022*, 10/24/2022, 2/27/2023, 5/22/2023, 10/23/2023, and November 20, 2023 packets]

♦ Request to continue to January 22, 2024 meeting

Public Hearing - New

2023-011/ZBA SBA Communications for DISH Wireless – 5 Town Dump Road (Atlas Map 55, Parcel 2A). Applicant seeks a Special Permit to modify a telecommunication structure of nonconforming height.

Topics of Discussion:

- ♦ Report from Ad Hoc Housing Committee
- Deadline for submission of documents

Next Meetings Monday, January 22, 2024 at 5:30 p.m.

Adjourn



STAFF MEMORANDUM

To: Truro Zoning Board of Appeals

From: Barbara Carboni, Town Planner and Land Use Counsel

Date: December 14, 2023

Re: Meeting December 18, 2023

Continued public hearing:

202-017/ZBA (VAR/SP) **Ebb Tide on the Bay Condominiums for property located at 538 Shore Road** (Map 7, Parcel 7).

Applicant's counsel has requested a continuance to the Board's next meeting on January 22, 2023. The special permit remains pending.

Note: the Board's decision granting a variance with respect to Bylaw parking requirements was filed with the Town Clerk on December 4, 2023. There is a 20-day appeal period.

New public hearing:

2023-11/ZBA SBA Communications for DISH Wireless for property located at 5 Town Dump Road (Map 55, Parcel 2A) Applicant seeks a special permit to modify a telecommunication structure of nonconforming height.

Existing Conditions and Proposed Project

The telecommunications tower at the Town Dump is 190 feet in height, which exceeds the Zoning Bylaw limit of 150 feet. See s. 40.5.B.4. The telecommunications tower is therefore a nonconforming structure. Existing panel antennas are located at heights of 187' 3"; 175'; 165' and 138'. This is best seen on Sheet A-2 of the plan set.

The applicant (SBA Communications, on behalf of DISH Wireless), seeks to add three antennas to the existing tower at a height of 155'. (The applicant also seeks to install some additional equipment at the base of the tower. This will be reviewed by the Planning Board in its consideration of a special permit application pursuant to s. 40.5.B.1. The Planning Board's process is more akin to site plan review).

As the addition of antennas to the existing tower is an alteration to a nonconforming structure, the project requires a special permit pursuant to G.L. c. 40A, s. 6 and Bylaw s. 30.7 (as well as the special permit from the Planning Board).

As with any other special permit application, the Board may grant a special permit under G.L.c.40A, s.6 if it finds that the proposed alternation "shall not be substantially more

detrimental than the existing nonconforming [structure and] use to the neighborhood."

Likewise, the Board may grant a special permit under Section 30.7.A if it finds that:

"the alteration or extension will not be substantially more detrimental to the neighborhood than the existing nonconforming use or structure and that the alternation or extension will exist in harmony with the general purpose and intent of this bylaw."

In previous decisions of the Planning Board with respect to equipment installation, several standard conditions (e.g., requiring communication with the DPW director and Police/Fire Chief as needed prior to commencing work; removal of the equipment from the tower and site when no longer in use) have been included. The inclusion of these conditions is recommended.



TOWN OF TRURO

ZONING BOARD OF APPEALS

Meeting Minutes
November 6, 2023 – 5:30 pm
REMOTE ZONING BOARD OF APPEALS MEETING

<u>Members Present (Quorum)</u>: Chris Lucy (Chair); Darrell Shedd (Vice Chair); Art Hultin; Nancy Medoff; Dave Crocker (Alt.)

Members Absent: Joseph McKinnon (Alt.)

<u>Other Participants:</u> Barbara Carboni – Town Planner/Land Use Counsel; Bob Weinstein – Select Board Liaison; William Henchy (Attorney for Robert Martin – Applicant); Robert Martin (Applicant); Andrew Aiken (Owner); Alison Aiken (Owner); Lauren McKean (Planner at the Cape Cod National Seashore); Stephen Williams (Former Truro Building Inspector and Truro Resident); Shirley Smith (Truro Voter)

Remote meeting convened at 5:30 pm, Monday, November 6, 2023, by Town Planner/Land Use Counsel Carboni who announced that this was a remote meeting which is being broadcast live on Truro TV Channel 8 and is being recorded. Chair Lucy introduced the Members of the ZBA.

Public Comment Period

Chair Lucy invited the members of the public to offer public comments and there were none.

Public Hearings (Continued)

2023-006/ZBA Robert J. Martin II and 100 Route 6 LLC for property located at 100 Route 6 (Atlas Map 55, Parcel 12). Applicant appeals a cease-and-desist order issued by Building Commissioner on May 3, 2023, with respect to property located in the Seashore District.

Chair Lucy recognized Attorney Henchy who introduced Mr. Martin and Mr. Aiken. Attorney Henchy then presented a detailed update since the last meeting. Attorney Henchy reviewed a memorandum, dated November 6, 2023, that he sent to the ZBA with a list of removed materials from the site as well as a staff supplemental memorandum, dated November 3, 2023, that he and the Members had received from Town Planner/Land Use Counsel Carboni.

The following highlighted comments and topics were discussed by the Members, Town Planner/Land Use Counsel Carboni, Attorney Henchy, Mr. Martin, and Mr. Aiken: the continued sale of firewood as a pre-existing nonconforming use; Mr. Martin's comments which recently appeared in an article in The Independent if the ZBA decision did not favor his appeal of the cease-and-desist order, the cost of the site reporting and water testing over the next ten years, and the aspects of the Special Permit granted in 2004 for a period of 30 years.

Chair Lucy then recognized the following members of the public to comment on this topic: Mr. Williams and Ms. Smith.

Member Hultin made a motion to close the public input in this hearing and move into deliberations. Member Medoff seconded the motion.

ROLL CALL VOTE:
Vice Chair Shedd – Aye
Member Hultin – Aye
Member Crocker
Member Medoff - Aye
Chair Lucy - Aye
So voted, 5-0-0, motion carries.

Chair Lucy then led the deliberations with the Members and with input from Town Planner/Land Use Counsel Carboni. Members reviewed the draft findings of the appeal of the cease-and-desist and provided input on the draft findings. The draft findings discussion also included findings #1-#38, the removal of the original #14, the application of the Town of Bridgewater vs. Chuckran test to make a motion, and findings #42-#47.

Town Planner/Land Use Counsel Carboni provided additional guidance as to how the Members would apply the Chuckran test to this matter. The three questions were answered by the Members, by roll call vote, in the following three motions.

Chair Lucy made a motion that the Board finds that the current nonconforming use does not reflect the nature and purpose of the original lawful pre-existing nonconforming use.

Member Hultin seconded the motion.

ROLL CALL VOTE:

Vice Chair Shedd – Aye

Member Hultin – Aye

Member Crocker - Aye

Member Medoff - Aye

Chair Lucy - Aye

So voted, 5-0-0, motion carries.

Chair Lucy made a motion that the Board finds that there is a difference in the quality, character, or degree of use between the current nonconforming use and the original nonconforming use.

Vice Chair Shedd seconded the motion.

ROLL CALL VOTE:

Vice Chair Shedd – Aye

Member Hultin – Aye

Member Crocker - Aye

Member Medoff - Aye

Chair Lucy - Aye

So voted, 5-0-0, motion carries.

Chair Lucy made a motion that the Board finds that the current nonconforming use is different in kind in its effect on the neighborhood than the original nonconforming use was.

Vice Chair Shedd seconded the motion.

ROLL CALL VOTE:

Vice Chair Shedd – Aye

Member Hultin – Aye

Member Crocker - Aye

Member Medoff - Aye

Chair Lucy - Aye

So voted, 5-0-0, motion carries.

Vice Chair Shedd made a motion that in the matter of 2023-006/ZBA Robert J. Martin II and 100 Route 6 LLC for property located at 100 Route 6 that the Zoning Board of Appeals upholds the cease-and-desist order by the Building Commissioner on May 3, 2023, and attach the findings, dated November 1, 2023, the previous #1-#38 and the removal of previous #14 and including the aforementioned Chuckran questions, and the findings of continuous storage of materials or equipment under Zoning Bylaw section 30.3(C)(7) with respect to property located in the Seashore District.

Member Hultin seconded the motion.

ROLL CALL VOTE:

Vice Chair Shedd - Aye

Member Hultin – Aye

Member Crocker - Aye

Member Medoff - Aye

Chair Lucy - Aye

So voted, 5-0-0, motion carries.

Town Planner/Land Use Counsel Carboni advised Chair Lucy that the Members can direct the Building Commissioner as to the enforcement in order to carry out the Planning Board's decision. Chair Lucy led the discussion with the Members on this topic. Highlighted topics included: allowing the Building Commissioner to decide how to enforce the Planning Board's decision and direct the zoning enforcement officer to oversee the removal of all nonconforming materials and uses from the property by January 15, 2024.

Member Hultin made a motion to direct the zoning enforcement officer to direct the removal of all nonconforming materials and uses from the property by January 15, 2024.

Vice Chair Shedd seconded the motion.

ROLL CALL VOTE:

Vice Chair Shedd – Ave

Member Hultin - Aye

Member Crocker - Aye

Member Medoff - Aye

Chair Lucy - Aye

So voted, 5-0-0, motion carries.

Following the vote, Chair Lucy recognized Attorney Henchy who stated for the record that he did not believe that the Planning Board had the authority to take any enforcement action pursuant to Chapter 40A §14 which defines the power of the board. Attorney Henchy thanked the board and left the meeting.

Vice Chair Shedd made a motion to adjourn at 7:01 pm.

Member Medoff seconded the motion.

ROLL CALL VOTE:

Vice Chair Shedd – Aye

Member Hultin – Aye

Member Crocker – Aye

Member Medoff - Aye

Chair Lucy - Aye

So voted, 5-0-0, motion carries.

Respectfully submitted,

Alexander O. Powers

Board/Committee/Commission Support Staff



TOWN OF TRURO

Planning Department

24 Town Hall Road, P.O. Box 2030, Truro, MA 02666 Tel: (508) 349-7004, Ext. 127 Fax: (508) 349-5505

EXTENSION AGREEMENT FOR CASE NO. 2022-017/ZBA

I, Christopher J. Snow, Esq., as authorized agent of Ebb Tide on the Bay Condominiums, with

respect to property located at 538 Shore Road, agree to an extension of time through January 22.

2024 for action by the Zoning Board of Appeals on the above Application filed with the Town

Clerk pursuant to M.G.L. Ch. 40A §6 and §30.7 of the Truro Zoning Bylaw.

Signature of Applicant/Agent

12/12/23

Date

Filed with the Planning Department:

Name

Date



Town of Truro Planning Board 24 Town Hall Road Truro, MA 02666

RE: Dish NSD Project No. BOBOS00593A SBA Project No. MA12227-A 5 Town Dump Road, Truro, MA 02666

Good afternoon:

SBA Communications will be collocating the Dish Network on our existing cell tower located at 5 Town Dump Road, Truro, MA.* Scope of work will include but not be limited to the installation of (3) new antennas & (6) Radios on (3) new sector frame mounts.

Enclosed please see:

- (1) Original and (9) copies of:
 - This Cover Letter
 - Planning Board Application for Modification to Existing Telecommunications Structures by Special Permit Under 40.5 Procedures.
 - Zoning Board of Appeals Application for Hearing
 - Certified Abutters List Request Form
 - Building Permit Application
 - MA State Insurance Information
 - Eligible Facilities Request (EFR)
 - Structural Analysis
 - Appurtenance Mount Analysis Report
 - Construction Drawings
 - Electromagnetic Emissions Report

Please let this letter additionally serve as formal request for a waiver for compliance with §40.5.B.(19) of the Truro Zoning Bylaws, as this is a new colocation on an existing in service telecom tower.

Thank you,

Catherine Ware
Site Development Specialist
SBA Communications
134 Flanders Road
Westborough, MA 01581
(917)868-8365
CWare@sbasite.com

^{*} This application is eligible for relief under the parameters of the Eligible Facilities Request ("EFR"); Section 6409 of the Spectrum Act (Pub. Law No. 112-96, 126 Stat 156) (codified at 47 U.S.C. § 1455), as well as the FCC's subsequent Report and Order of October 17, 2014, and Declaratory Ruling of June 9, 2020. Therefore, the proposed upgrades are not subject to discretionary review and are admissible per Federal Law.



Town of Truro Zoning Board of Appeals P.O. Box 2030, Truro, MA 02666

APPLICATION FOR HEARING

To the Town Clerk of the Town of Truro, MA	Date <u>09/19/2023</u>
The undersigned hereby files with specific grounds for the	nis application: (check all that apply)
Commissioner on (date) Applicant is aggrieved by order or decision or	of the Building Commissioner on (date)
	e Truro Zoning Bylaw or the <i>Massachusetts Zoning Act</i> . quests a variance from the terms Section of the
concerning (describe) Nonconforming h Applicant seeks approval for a continuation,	of uses under Section <u>40.5</u> of the Truro Zoning Bylaw eight of existing telecom structure change, or extension of a nonconforming structure or use Bylaw and M.G.L. Ch. 40A, §6 concerning (describe)
Property Address <u>5 Town Dump Rd</u>	255 222 222
Registry of Deeds title reference: Book and Land Ct. Lot #	and Plan # 002-00A
Applicant's Name Catherine ware - SBA Communication Applicant's Legal Mailing Address 134 Flanders Road, Applicant's Phone(s), Fax and Email 917-868-8365 cv Applicant is one of the following: (please check appropriate Owner Prospective Buyer*	Westborough, Ma 01581 Suite 125 vare@SBASite.com
Owner's Name and Address SBA Towers II LLC Representative's Name and Address 8051 Congress Ave Representative's Phone(s), Fax and Email 917-868-8365	
2. The completed application shall also be suplanner 1@truro-ma.gov in its entirety (including all	· · · · · · · · · · · · · · · · · · ·
	ling Commissioner, Planning Department, Conservation Commission, as applicable, prior to submitting this
Catherine Ware - SBA Communications Applicant(s)/Representative <i>Printed</i> Name(s)	John Morrison - SBA Jovers 11 LVC Owner(s) Printed Name(s) or written permission
Applicant(s)/Representative Signature	Owner(s) Signature or written permission



TOWN OF TRURO

Assessors Office Certified Abutters List Request Form



	DATE: 10-23-23
NAME OF APPLICANT: DISH WIRELESS	
NAME OF AGENT (if any): CATLERINE WARE - 5	BA Communications
MAILING ADDRESS: 134 Flanacis RD Suite 125	Westbar Dugh MA 01581
CONTACT: HOME/CELL 917 868 8365 EMAIL	
PROPERTY LOCATION: 5 Town Dung Rd Trure, (stree[address)	MA 02666
PROPERTY IDENTIFICATION NUMBER: MAP 5'5 PARCEL	EXT. A (if condominium)
ABUTTERS LIST NEEDED FOR: (please check all applicable) (Fee must accompany the application un	FEE: \$15.00 per checked item
(ree must accompany the application an	ness other arrangements are made)
Board of Health ^s Planning Board (PB)	Zoning Board of Appeals (ZBA)
Cape Cod Commission Special Permit ¹	Special Permit
Conservation Commission ⁴ Site Plan ²	Variance ¹
Licensing Preliminary Subdivision ³	
Type: Definitive Subdivision ³	
Accessory Dwelling Unit (ADU) ²	
Other	(Fee: Inquire with Assessors)
(Please Spacify)	
Note: Per M.G.L., processing may take up to 10 calendar days. Pleas	se plan accordingly.
THIS SECTION FOR ASSESSORS OFFICE USE O	NLY /
Date request received by Assessors: Nov 14, 2023 Date complete	
List completed by: Laura Geiges Date paid: 11	/14/23 Cash/Check 2179510

¹Abutters, owners of land directly opposite on any public or private street or way, and abutters to the abutters within 300 feet of the property line.

²Abutters to the subject property, abutters to the abutters, and owners of properties across the street from the subject property.

³Landowners immediately bordering the proposed subdivision, landowners immediately bordering the immediate abutters, and landowners located across the streets and ways bordering the proposed subdivision. <u>Note:</u> For Definitive Subdivision only, responsibility of applicant to notify abutters and produce evidence as required.

⁴All abutters within 300 feet of parcel, except Beach Point between Knowles Heights Road and Provincetown border, in which case it is all abutters within 100 feet. Note: Responsibility of applicant to notify abutters and produce evidence as required.

⁵Abutters sharing any boundary or corner in any direction – including land across a street, river or stream. <u>Note:</u> Responsibility of applicant to notify abutters and produce evidence as required.



TRURO ASSESSORS OFFICE

PO Box 2012 Truro, MA 02666 Telephone: (508) 214-0921

Fax: (508) 349-5506

Date: November 15, 2023

To: Catherine Ware, SBA Communications

From: Assessors Department

Certified Abutters List: 5 Town Dump Road (Map 55 Parcel 2 Ext A)

Zoning Board of Appeals – Special Permit

Attached is a combined list of abutters for 5 Town Dump Road (Map 55 Parcel 2 Ext A).

The current owners are SBA Towers II LLC.

The names and addresses of the abutters are as of November 10, 2023 according to the most recent documents received from the Barnstable County Registry of Deeds.

Certified by:

Laura Geiges

Assistant Assessor / Data Collector

TOWN OF TRURO, MA BOARD OF ASSESSORS P.O. BOX 2012, TRURO MA 02666

Abutters List Within 300 feet of Parcel 55/2/A



Key	Parcel ID	Owner	Location	Mailing Street	Mailing City	ST	ZipCd/Country
7292	40-999-0-E	USA-DEPT OF INTERIOR Cape Cod National Seashore	0 CAPE COD NATIONAL SEASHORE	99 Marconi Site Rd	Wellfleet	MA	02667
3341	55-2-0-E	TOWN OF TRURO	5 TOWN DUMP RD	PO BOX 2030	TRURO	MA	02666-2030
5944	55-2-A-R	S B A TOWERS II LLC	5 TOWN DUMP RD	TAX DEPT MA12227-A 8051 CONGRESS AVE	BOCA RATON	FL	33487
3342	55-3-0-E	TOWN OF TRURO	5-A TOWN DUMP RD	PO BOX 2030	TRURO	MA	02666-2030

USA-DEPT OF INTERIOR Cape Cod National Seashore 99 Marconi Site Rd Wellfleet, MA 02667

TOWN OF TRURO PO BOX 2030 TRURO, MA 02666-2030 S B A TOWERS II LLC TAX DEPT MA12227-A 8051 CONGRESS AVE BOCA RATON, FL 33487

55-3-0-E

TOWN OF TRURO PO BOX 2030 TRURO, MA 02666-2030

Building Permit ApplicationMassachusetts State Building Code, 780 CMR, 9th Edition

- (16	1		1
- 3	18		新	
	1	PP0	PAT	10)
	((* B	* 1800	* DPADRAT

TOWN OF TRURO

Building Department

24 Town Hall Rd. PO Box 2030 Truro, MA 02666 Tel (508) 349-7004 x131 Fax (508) 349-5508

Permit #:	Fee: \$50 Application Fee
	Fee:

SITE INFORMATION						
Project Site: 5 Town Dump Road, Truro MA 02666						
Assessors Map & Parcel: 55-2-A	\	Zoning Dis	trict: SFO			
Outside Flood Zone		Inside Fl	ood Zone – Specif	īy:		
Setbacks: Front:	Left Side	::	Right Side:		Rear:	
Lot Area (sq. ft.)			Frontage:			
Water Supply: Private	Public		Subject to Policy If Yes, please a this application	attach a cop	? Y N y of the approval to	
SUBJECT TO NHESP/MESA REVIEW	/? 🗆 Y 🗀 !	N *	IF YES, PLEASE A	ттасн а сор	Y OF THE APPROVAL.	
	P	PROPERTY O	WNERSHIP			
Owner of Record: Town of Tr	uro, MA	\				
Mailing Address: P.O. Box 20)30 Trui	ro, MA C)2666 - Attn	: Landlor	d	
Phone: (917)868-8365	E-	mail:cwar	e@sbasite.	com		
Property Owner Authorization						
Signature:		Date:				
PROJECT INFORMATION						
1 & 2 Family Home Commercial / Other than 1 & 2 Family Home*			Change of Use	of DEMO - Subject to Chapter VI: Historic Properties Bylaw? Y		
* BUILDINGS IN EXCESS OF 35,000 CU. FT. MUST MEET CONTROL CONSTRUCTION REGULATIONS (780 CMR 116). ADDENDUM TO PERMIT APPLICATION AVAILABLE IN BUILDING DEPARTMENT.						
New Dwelling: # of units			Commercial B	uilding		
Addition		Alteratio	n	Mechan	ical	
Accessory Structure: (type) <u>Ce</u>	llular tower		Other:			
Detailed Description of Proposed Work: DISH Wireless - Adding 3 antennas and 6 RRU's and 1 OVP						
to the existing telecommunications facility located at 5 Town Dump Road in Truro.						
Construction drawings and Structural Analysis attached						
**We are filing this application with an eligible facilities request to modify an existing support structure						
pursuant to Section 6409(a) of the Middle-Class Tax Relief and Job Creation Act of 2012						
(" Spectrum Act ") and the rules of the	e Federal Coi	mmunications				
(" FCC "). See Pub. Law No. 112-96	, 126 Stat. 15	66 (2012); 47 (C.F.R. §1.6100.			

Estimated Construction Cost:40,000			Debris Disposal: (Landfill or Company Name)		
Floor Area: (Proposed Work Only) Basement: unfinis			ished N/A finished N/A		
1st flr: N/A 2nd flr: N/A			Porch/Deck: N/A Other:		
#fireplaces:	#chimne	ys:	#bathrooms: existing proposed		
#bedrooms: existing	pı	roposed			
Type of Heating System:	N/A		Type of Cooling System: N/A		
HOMEOWNER'S AFFI	DAVIT REQ	CONTRACTOR I QUIRED IF OWNERS ARE D	NFORMATION OING THEIR OWN WORK (RESIDENTIAL PROJECTS ONLY)		
Contractor Name: Tim k	perline	Construction C	Company		
Address: 300 Pine	e Stre	eet, Canton,	MA 02021		
Phone: (339)502-500	00		Email: borlandi@timberlinecommunications		
CSL#:		HIC #			
		OFFIC	E USE		
HEALTH/CONSERVATIO	N AGENT	Review			
Signature:			Date:		
Other Comments:					
BUILDING COMMISSIONER Review & Approval:					
Signature:			Issuance Date:		

BUILDING PERMIT APPLICATION DOCUMENT CHECKLIST

This checklist is part of the permit application and must be completed. If not completed the application may be considered incomplete and cause the permit to be denied.

TO PAORATE DIS

Town of Truro Building Department

24 Town Hall Rd. PO Box 2030 Truro, MA 02666 Tel (508) 349-7004 x131 Fax (508) 349-5508

Please note that marked-up archival drawings do not constitute acceptable documents for permitting purposes.

One and/or Two Family Home
Completed application form
1 copy original site plan showing building setbacks and grades.
2 (min.) copies building plans – One can be full size if greater than 11 x 17. One must be no greater than 11 x 17 for department filing. Electronic version is acceptable, in addition.
Drawings indicating all relevant information including but not limited to:
 Fully dimensioned foundation, floor and structural plans; Building elevations showing finish materials and critical dimensions; Building/wall sections describing building construction, energy related details and showing critical vertical dimensions. Smoke, CO and heat detectors must be shown.
 Door and window information demonstrating conformance with minimum room and dwelling egress and emergency escape.
 Exterior window and door information demonstrating conformance with light, ventilation and energy requirements.
 Location and design of any required fire separation assemblies.
All structural conditions noted on plans – braced wall lines indicated and analysis shown and/or engineered solution with registered design professional's certification and/or other prescriptive solution allowed by Code.
1 copy Energy Code compliance documents (check only one below)
☐ HERS/performance rating document – new construction
ResCheck (2015 MA) – additions/alterations- per 2015 IECC R502 & 503 Prescriptive – values shown on plans – see 2015 IECC table R402.1.2 and other req's.
Photocopy of CSL and HIC (if applicable) shown on application form
Worker's Compensation Insurance Affidavit and copy of current certificate of insurance
Homeowner's License Exemption (if qualified and there is no CSL)
Copy of recorded approvals from local regulatory boards
If street access is required and property is on a Town road, copy of Curb Cut approval from the Board of Selectmen

For applications for Modular and other than 1&2 Family Structures see Checklist on next page.

Modular Home (Homeowner license exemption not allowed)
 2 copies of foundation plan Approved plans by MA Board of Building Regulations & Standards with evidence of 3rd party inspection Manufacturer's certification of installer/set crew.
Structures Other than 1 & 2 Family Home
Completed Application form
Stamp and signature of registered design professional
2 (min.) copies building plans – One can be full size if greater than 11 x 17. One must be no greater than 11 x 17 for filing. Electronic version is acceptable, in addition. Drawings must indicate all relevant information including but not limited to: Fully dimensioned foundation, floor and structural plans; fire separation assemblies; door, window and room finish schedules; building elevations with critical dimensions; building/wall sections describing building construction and energy related details and showing critical vertical dimensions.
COMcheck Envelope, Lighting and Mechanical Compliance Certificates and Plan Review Inspection Checklist for the purposes of demonstrating compliance with the energy code.
Construction Control Document(s)
Tier 1 Fire Protection System document per section 902.2.1
Code analysis indicating (but not limited to) all use groups, construction types, allowable areas, fire separations, egress paths and distances. This analysis can be part of drawing set.
Contractor credentials
Worker's Compensation Insurance Affidavit and copy of current certificate of insurance
Recorded copy of any local regulatory board approvals
If modular construction see items above

Notes:



SBACOMM-01

HJSESERKO

15,000,000

1,000,000

5,000,000

DATE (MM/DD/YYYY) 4/10/2023

CERTIFICATE OF LIABILITY INSURANCE

THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AFFIRMATIVELY OR NEGATIVELY AMEND, EXTEND OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW. THIS CERTIFICATE OF INSURANCE DOES NOT CONSTITUTE A CONTRACT BETWEEN THE ISSUING INSURER(S), AUTHORIZED

R	EPRESENTATIVE OR PRODUCER, A	ND TH	IE C	ERTIFICATE HOLDER.					, ,,	
lf	PORTANT: If the certificate holde SUBROGATION IS WAIVED, subje is certificate does not confer rights	ct to	the	terms and conditions of	the po	licy, certain	oolicies may			
PRO	DUCER				CONTA NAME:	СТ				
	enderson Brothers Inc					o, Ext): (412) 2	61-1842	FAX (A/C No):	412) 2	261-4149
020 Ft. Duquesne Blvd. Pittsburgh, PA 15222						sonbrothers.com	, , -			
					INSURER(S) AFFORDING COVERAGE					NAIC #
					INSURE	R A : Traveler	s Property C	asualty Company of Am	erica	25674
INSU	RED				INSURE	RB:The Cha	arter Oak F	ire Ins. Co.		25615
	SBA Communications Corp	oratio	n		INSURE	R C : The Har	tford Com	oany Payable		29424
	8051 Congress Ave.				INSURE	RD:				
	Boca Raton, FL 33487				INSURER E :					
					INSURE	RF:				
CO	/ERAGES CEF	RTIFIC	ATE	NUMBER:				REVISION NUMBER:		
IN CI	IIS IS TO CERTIFY THAT THE POLICI DICATED. NOTWITHSTANDING ANY F ERTIFICATE MAY BE ISSUED OR MAY ICLUSIONS AND CONDITIONS OF SUCH	REQUIF PERT	REME AIN,	ENT, TERM OR CONDITION THE INSURANCE AFFORD	OF A	ANY CONTRAC	CT OR OTHER ES DESCRIB	DOCUMENT WITH RESPE	CT TO	WHICH THIS
NSR LTR	TYPE OF INSURANCE	ADDL S	SUBR	POLICY NUMBER		POLICY EFF (MM/DD/YYYY)	POLICY EXP	LIMIT	s	
Α	X COMMERCIAL GENERAL LIABILITY					<u> </u>	·······	EACH OCCURRENCE	\$	1,000,000
	CLAIMS-MADE X OCCUR			TC2J-GLSA-9P530142-TII	L-23	3/15/2023	3/15/2024	DAMAGE TO RENTED PREMISES (Ea occurrence)	\$	1,000,000
								MED EXP (Any one person)	\$	
								PERSONAL & ADV INJURY	\$	1,000,000
	GEN'L AGGREGATE LIMIT APPLIES PER:							GENERAL AGGREGATE	\$	2,000,000
	POLICY X PRO-							PRODUCTS - COMP/OP AGG	\$	2,000,000
	OTHER:								\$	
Α	AUTOMOBILE LIABILITY							COMBINED SINGLE LIMIT (Ea accident)	\$	1,000,000
	X ANY AUTO			TC2J-CAP-474M814A-TIL	-23	3/15/2023	3/15/2024	BODILY INJURY (Per person)	\$	
	OWNED SCHEDULED AUTOS ONLY							BODILY INJURY (Per accident)	\$	
	HIRED AUTOS ONLY NON-OWNED AUTOS ONLY							PROPERTY DAMAGE (Per accident)	\$	

15,000,000 CUP-1T38674A-23-NF 3/15/2023 3/15/2024 **EXCESS LIAB** CLAIMS-MADE AGGREGATE 10,000 DED | X | RETENTION \$ X PER STATUTE OTH-ER WORKERS COMPENSATION AND EMPLOYERS' LIABILITY 1,000,000 UB-4L099102-23-51-K 3/15/2023 3/15/2024 ANY PROPRIETOR/PARTNER/EXECUTIVE OFFICER/MEMBER EXCLUDED? (Mandatory in NH) E.L. EACH ACCIDENT 1,000,000 E.L. DISEASE - EA EMPLOYEE \$ If yes, describe under DESCRIPTION OF OPERATIONS below 1,000,000

3/15/2023

3/15/2023

3/15/2024

3/15/2024

DESCRIPTION OF OPERATIONS / LOCATIONS / VEHICLES (ACORD 101, Additional Remarks Schedule, may be attached if more space is required) For Informational Purpose Only

UB-3L884966

40 CPI HA6405

CERTIFICATE HOLDER	CANCELLATION
Evidence of Coverage	SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, NOTICE WILL BE DELIVERED IN ACCORDANCE WITH THE POLICY PROVISIONS.
	authorized representative On Warndian

X

UMBRELLA LIAB

Worker's Comp Prof/Poll

Χ

OCCUR

EACH OCCURRENCE

E.L. DISEASE - POLICY LIMIT

Each Acc/Policy Lmt

Claim/Agg

1 of 1

Page

SBA Torres Argentina SRL f/k/a Southern

T.A. Investment Holdings Inc.

Torres Andinas Holdco, Inc.

Tower Funding, LLC

Tower Funding II, LLC

TV6 Holdings LLC

Tower Funding III, L.P.

Tower Funding GP, Inc.

SBA Towers VII, LLC

Minara Tanzania Limited

RTGF Holdings Limited

Minara Zanzibar Limited

RTGF Midco Limited

SBA Edge, LLC

SBA Towers Philippines Holdings, Inc.

SBA Towers VI, LLC

SBA Towers XI, LLC

SBA South Africa Equityholder, LLC

Golden State Licensing, LLC.

DC Matrix Internet Ltda

SBA Towers Philippines, Inc

DC Matrix Telecomuncacoes Ltda

LOC #: 0

SBA Towers South Africa Proprietary, Limithed F/K/A Atlas Tower Proprietary,



ADDITIONAL REMARKS SCHEDULE

AGENCY		NAMED INSURED			
		SBA Communications Corporation 8051 Congress Ave. Boca Raton, FL 33487			
POLICY NUMBER		Boca Raton, FL 33487			
SEE PAGE 1					
CARRIER	NAIC CODE				
SEE PAGE 1	SEE P 1	EFFECTIVE DATE: SEE PAGE 1			

ADDITIONAL REMARKS

THIS ADDITIONAL REMARKS FORM IS A SCHEDULE TO ACORD FORM, FORM NUMBER: ACORD 25 FORM TITLE: Certificate of Liability Insurance

Named Insureds Continued SBA GC Holdings, LLC

Limited SBA Edge (JAX), LLC

Towers SRL

SBA UK Holdings Limited SBA GC Towers, LLC **SBA Guarantor LLC** Brazil Shareholder I, LLC Brazil Shareholder II, LLC

Central America Equityholder, LLC

Chile Shareholder, LLC Colombia Shareholder, LLC Costa Rica Quotaholder, LLC SBA Monarch Steel, LLC

Desarrollos Inmobiliarios Inmoavilies S.A.

Ecuador Shareholder, LLC Ecuador Shareholder II, LLC **SBA Network Management, Inc.** El Salvador Shareholder I, LLC El Salvador Shareholder II. LLC Guatemala Shareholder I, LLC Guatemala Shareholder II. LLC **SBA Senior Finance II LLC**

SBA Senior Finance, LLC SBA Site Management, LLC

Memphis Towers, LLC SBA Steel LLC

SBA Steel II, LLC

Nicaragua Shareholder I, LLC Nicaragua Shareholder III, LLC

OFO LLC

Panama Shareholder, LLC Peru Shareholder I, LLC Peru Shareholder II, LLC **Quality Tower Developers, LLC**

SBA Torres Costa Rica, Limitada SBA 2012 TC Assets, LLC SBA 2012 TC Assets Land, LLC SBA 2012 TC Assets PR, LLC SBA 2012 TC Holdings, LLC

SBA 2012 TC Land II, LLC

SBA 2014 PR, Inc. f/k/a Soluwise, Inc.

SBA BTS, LLC

SBA Canada Holdings, Inc. SBA Canada, ULC (fka Jade Tower ULC)

SBA Canada II. ULC SBA DAS & Small Cells, LLC

SBA Depositor LLC

SBA GC Parent I, LLC

SBA GC Parent II. LLC SBA Towers USVI, Inc. SBA Towers X, LLC **SBA Holdings LLC** SBA Holdings e Participações Ltds.

SBA HQ, LLC SBA Infrastructure, LLC

SBA Inmuebles Peru, S.A.C. fka MAA SBA Land, LLC fka TCO Land LLC

Desarrollos Inmobiliarios Inmo Aplicanet SA SBA Monarch Towers I. LLC

SBA Monarch Towers III, LLC SBA Negocios Imobiliarios Ltda

SBA Connect, LLC SBA New Builds, LLC SBA Properties, LLC SBA Puerto Rico, LLC

SBA RSA Holdings, LLC SBA TRS Holdco, LLC

SBA Ventures, LLC

SBA Network Services, LLC

SBA Sites, LLC

SBA Worth Telecom LLC

fka Atlas Tower South Africa Equityholder, LLC **Torreaviles S.A**

SBA Structures. LLC SBA Telecommunications, LLC.

SBA Telecomunicaciones Colombia S.A.S. f/k/a/ Torres Andinas S.A.S.

SBA Towers, LLC

SBA Torres Brasil, Limitada SBA Torres Chile, Spa **SBA Torres Colombia S.A.S**

SBA Towers VIII, LLC

SBA Torres Ecuador SBAEC, S.A. SBA Torres El Salvador, S.A. De C.V. SBA Torres Guatemala, Limitada SBA Torres Nicaragua, S.A.

SBA Torres Nicaragua II, LLC SBA Torres Panama, S.A.

SBA 2016 TC USVI, LLC f/k/a TowerCo 2013 USVI LLC SBA Torres Peru, S.A. fka Torres Andinas, S.A. **SBA Towers II LLC**

SBA Towers III LLC SBA Towers IV. LLC SBA Towers IX. LLC **SBA Towers V, LLC**

Desarrollos Inmobiliarios Ecuador SBAINMO-EC S.A.



The Commonwealth of Massachusetts Department of Industrial Accidents 1 Congress Street, Suite 100 Boston, MA 02114-2017

www.mass.gov/dia

Workers' Compensation Insurance Affidavit: General Businesses. TO BE FILED WITH THE PERMITTING AUTHORITY.

Applicant Information	Please Print Legibly
Business/Organization Name:	
Address:	
City/State/Zip:	Phone #:
Are you an employer? Check the appropriate box: 1.	Business Type (required): 5.
Policy # or Self-ins. Lic. #	Expiration Date: tion page (showing the policy number and expiration date).
Failure to secure coverage as required under Section 25A of M fine up to \$1,500.00 and/or one-year imprisonment, as well as of up to \$250.00 a day against the violator. Be advised that a d Investigations of the DIA for insurance coverage verification.	IGL c. 152 can lead to the imposition of criminal penalties of a civil penalties in the form of a STOP WORK ORDER and a fine copy of this statement may be forwarded to the Office of
I do hereby certify, under the pains and penalties of perjury t	
Signature:	Date:
Phone #: Official use only. Do not write in this area, to be complete	d by city or town official.
City or Town:	
Issuing Authority (circle one): 1. Board of Health 2. Building Department 3. City/Tow 6. Other	
Contact Person	Phone #•



ELIGIBLE FACILITIES REQUEST (EFR) APPLICATION FORM

Orig. Date of Submittal: 9/19/23

Submitted by:

Name: Catherine Ware

Title: Site Development Specialist on behalf of SBA Network Services and DISH Wireless

Contact Information: cware@sbasite.com

(917)868-8365

Name of Jurisdiction: Town of Truro

Address of Jurisdiction: 24 Town Hall Road

Contact Name for Jurisdiction: Elizabeth Sturdy

Name of Local Government Permit Application: Planning Application for Special Permit

Local Government File #: Click here to enter text.

Street Address of Site: 5 Town Dump Rd

Tax Parcel # of Site: 55-2-A

Latitude/Longitude of Site: 41.98578; -70.04133

List Each Piece of Transmission Equipment that will be Collocated or Added:

(3) JMA Wireless Antenas, (6) RRU/RRH Fujitsu, (1) Raycap OVP

List Each Piece of Transmission Equipment that will be Removed:

N/A

List Cabinets that will be Collocated or Added at the Site:

None

List Cabinets that will be Removed at the Site:

None

Permit Application Amount: \$350

Municipal Consultant Review Fee Deposit: Click here to enter text.



ELIGIBLE FACILITIES REQUEST (EFR) CERTIFICATION OF NON-SUBSTANTIAL CHANGES TO A WIRELESS TOWER NOT LOCATED WITHIN A PUBLIC RIGHT OF WAY

1)	Address of the Wireless Tower: 5 Town Dump Road, Truro MA. 02666					
2)	The height (measured in feet above ground level) of the existing Tower as originally approved, including any modifications approved prior to February 22, 2012: 190					
3)	What is the height (measured in feet above ground level) at which the modifications to the Transmission Equipment will occur on the Tower? 155'					
4)	What will be the height (measured in feet above ground level) of the existing Tower after the modifications to the Transmission Equipment are installed? 190'					
5)	Effect of modifications of Transmission Equipment on Tower height:					
	 a. Will the modifications in Transmission Equipment (addition, removal or replacement of Transmission Equipment) result in increasing the height above ground level of the existing Tower? ☐ Yes ☒ No 					
	 b. Will the modifications in Transmission Equipment result in increasing the height above ground level of the existing Tower by more than: (i) 10% of the height of the existing Tower as originally approved, including any modifications approved prior to February 22, 2012; or (ii) twenty feet above the height of the existing Tower, as originally approved, including any modifications approved prior to February 22, 2012, whichever height increase is greater? □ Yes ⋈ No 					
6)	Will the modifications in Transmission Equipment (measured at the height above ground level where the Transmission Equipment will be attached to the tower) result in any Transmission Equipment protruding horizontally from the edge of tower by more than twenty (20) feet or by more than the existing width of the tower at that height, whichever of these dimensions is greater? \square Yes \square No					
7)	Will the proposed changes in Transmission Equipment involve excavation or placement of new equipment outside the existing Tower site or outside any access or utility easements currently related to the site? \square Yes \square No					



8)	Will the proposed modification in Transmission Equipment involve installation of more than the standard number of new equipment cabinets for the technology involved, but not to exceed four? \square Yes \square No						
9)		e proposed modification in Transmission Equipment defeat the existing concealment nts of the Tower? No					
10)	Prior C	onditions of Approval					
	a.	Will the proposed modification in Transmission Equipment comply with conditions of approval imposed on the Tower prior to February 22, 2012? $\ \ \ \ \ \ \ \ \ \ \ \ \ $					
	b.	If the answer to 10(a) is "No," is the non-compliance due solely to any of the conditions addressed in questions 5-9 above? \Box Yes \Box No					
the	answe	ver to either question 5(a) or 5(b) is "No," and the answers to questions 6-9 are "No," and it to either 10(a) or 10(b) is "Yes," then the proposed modifications do not substantially ephysical dimensions of the existing Tower. Click here to enter text.					
Thi	s certifi	cation is dated this 9/19/ 2023					
Sig	nature	Catherine Ware					
Cat	herine '	Ware / Site Development Specialist on behalf of SBA Network Services LLC and DISH Wireless					
Naı	me & Ti	tle					



Eligible Facilities Request to Modify Transmission Equipment at an Existing Communications Tower

Location: 5 Town Dump Rd, Truro Ma

DISH Site No: BOBOS00593A

SBA Communications: Agent for SBA Network Services LLC and DISH Wireless

DISH Wireless is Filing an Eligible Facilities Request

SBA Properties, LLC, on behalf of DISH Wireless and SBA Network Services, LLC as General Contractor, is submitting an Eligible Facilities Request to add (collocate) Transmission Equipment on an existing SBA Telecommunications Tower located at 5 Town Dump Rd.

The existing Tower is a structure that is 190' high and presently contains wireless facilities. The existing Tower meets the Federal Communications Commission ("FCC") definition of a Tower and DISH Wireless is an FCC licensed wireless carrier.

The list of equipment identified in this Eligible Facilities Request application is Transmission Equipment as determined by the FCC, and as defined as follows: "any equipment that facilitates transmission for any Commission-licensed or authorized wireless communication service, including, but not limited to, radio transceivers, antennas and other relevant equipment associated with and necessary to their operation, including coaxial or fiber-optic cable, and regular and back-up power supply. This definition includes equipment used in any technological configuration associated with any Commission-authorized wireless transmission, licensed or unlicensed, terrestrial or satellite, including commercial mobile, private mobile, broadcast and public safety services, as well as fixed wireless services such as microwave backhaul or fixed broadband."

Administrative Review and Approval

While local jurisdictions retain discretionary zoning review over the construction of new towers, collocations and/or equipment upgrades such as reflected in this application must now be approved administratively. The new law provides, in part, that:

"a State or local government may not deny, and shall approve, any eligible facilities request for a modification of an existing wireless tower or base station that does not substantially change the physical dimensions of such tower or base station." (Emphasis added.)

The FCC, in a Report and Order adopted on October 17, 2014, determined that any modification to an existing telecommunications Tower that meets the following six criteria does not substantially change the physical dimensions of the existing Tower and therefore is an Eligible Facilities Request which must be granted:

1. The modifications to the Transmission Equipment do not increase the height of the Tower by twenty feet or ten percent, whichever is greater;



- 2. The modifications to the Transmission Equipment do not protrude from the edge of the Tower by twenty feet or more than the width of the Tower (whichever of these two dimensions is greater) at the level where the transmission equipment modifications are made:
- 3. The modifications to the Transmission Equipment do not involve the installation of more than the standard number of equipment cabinets for the technology involved, not to exceed four;
- 4. The modifications to the Transmission Equipment do not entail any excavation or deployment outside of the Tower site;
- 5. The modifications to the Transmission Equipment do not defeat any existing concealment elements of the Tower;
- 6. The modifications to the Transmission Equipment comply with prior conditions of approval of the Tower, unless the non-compliance is due to an increase in height, increase in width, addition of equipment cabinets, or new excavation that does not exceed the corresponding "substantial change" thresholds in numbers 1-4.

We are providing certification that each of the six review criteria identified by the FCC will be met, and that the proposed collocation fully conforms to Section 6409(a) as enacted by Congress and as interpreted by the FCC.

Expedited Permit Processing and Deemed Granted Designation

Under federal law, an Eligible Facilities Request is deemed granted sixty (60) days after a complete application is filed with a local jurisdiction. Accordingly, this Eligible Facilities Request must be approved within 60 days, as required by federal law and FCC regulations. If sixty days pass after the submission of DISH's application and the Truro Planning Board has not acted to grant or deny the request, it will be deemed granted.



Tower Engineering Solutions

Phone (972) 483-0607, Fax (972) 975-9615 1320 Greenway Drive, Suite 600, Irving, Texas 75038

Structural Analysis Report

Existing 190 ft Cellxion Self Supporting Tower

Customer Name: SBA Communications Corp

Customer Site Number: MA12227-A

Customer Site Name: Truro

Carrier Name: Dish Wireless (App#: 163468, V1)

Carrier Site ID / Name: BOBOS00593A / 0

Site Location: 5 Town Dump Road

Truro, Massachusetts

Barnstable County

Latitude: 41.985783

Longitude: -70.041333

Exp.06/30/2024



10/26/2023

Analysis Result:

Max Structural Usage: 104.8% [Pass]
Max Foundation Usage: 68.0% [Pass]

Additional Usage Caused by New Mount/Mount Modification: N/A

Report Prepared By: Sital Shrestha



Tower Engineering Solutions

Phone (972) 483-0607, Fax (972) 975-9615 1320 Greenway Drive, Suite 600, Irving, Texas 75038

Structural Analysis Report

Existing 190 ft Cellxion Self Supporting Tower

Customer Name: SBA Communications Corp

Customer Site Number: MA12227-A

Customer Site Name: Truro

Carrier Name: Dish Wireless (App#: 163468, V1)

Carrier Site ID / Name: BOBOS00593A / 0

Site Location: 5 Town Dump Road

Truro, Massachusetts

Barnstable County

Latitude: 41.985783

Longitude: -70.041333

Analysis Result:

Max Structural Usage: 104.8% [Pass]

Max Foundation Usage: 68.0% [Pass]

Additional Usage Caused by New Mount/Mount Modification: N/A

Report Prepared By: Sital Shrestha

Introduction

The purpose of this report is to summarize the analysis results on the 190 ft Cellxion Self Supporting Tower to support the proposed antennas and transmission lines in addition to those currently installed. Any modification listed under Sources of Information was assumed completed and was included in this analysis.

Sources of Information

Tower Drawings Cellxion Drawing # TBAY01793, dated 01/13/2004	
Foundation Drawing Cellxion Drawing #TBAY01793, dated 01/13/2004	
Geotechnical Report Paul B. Aldinger & Associates Project # 03135, dated 11/19/2003	

Analysis Criteria

The rigorous analysis was performed in accordance with the requirements and stipulations of the TIA-222-G-2. In accordance with this standard, the structure was analyzed using **TESTowers**, a proprietary analysis software. The program considers the structure as an elastic 3-D model with second-order effects and temperature effects incorporated in the analysis. The analysis was performed using multiple wind directions.

Wind Speed Used in the Analysis: Ultimate Design Wind Speed Vult =149.0 mph (3-Sec. Gust)/

Nominal Design Wind Speed $V_{asd} = 115.0 \text{ mph}$ (3-Sec. Gust)

Wind Speed with Ice: 50 mph (3-Sec. Gust) with 3/4" radial ice concurrent

Operational Wind Speed: 60 mph + 0" Radial ice

Standard/Codes: TIA-222-G-2 /2015 IBC/ Massachusetts State Building Code,

Ninth Edition

Exposure Category: B
Structure Class: III
Topographic Category: 1
Crest Height: 0 ft

Seismic Parameters: $S_S = 0.164, S_1 = 0.057$

This structural analysis is based upon the tower being classified as a Structure Class III; however, if a different classification is required subsequent to the date hereof, the tower classification will be changed to meet such requirement and a new structural analysis will be run.

Existing Antennas, Mounts and Transmission Lines

The table below summarizes the antennas, mounts and transmission lines that were considered in the analysis as existing on the tower.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
1		3	KMW - AM-X-CD-16-65-00T-RET - Panel	- AM-X-CD-16-65-00T-RET - Panel		
2		3	Cci - DMP5R-BU4DA - Panel			
3		3	Css - DUO1417-8686-0 - Panel		(12) 1 5/8"	
4		3	Kathrein - 800-10121 - Panel	(3) Sector Frames (Site	[(4) 3/4" DC &	AT&T
5	187.3	6	Powerwave - LGP17201 - TMA	Pro USF12-XX-U) + (3)	(2) 7/16" Fiber	
6		3	Ericsson - RRUS 12 B4 - RRU	Pipe Mounts	(Inside (2) 3"	
7		3	Ericsson - RRUS 4478 B14 - RRU		Conduits)]	
8		3	Ericsson - RRUS 4449 B5/B12 - RRU			
9		2	Raycap - DC6-48-60-18-8F - OVP			
10		3	Ericsson - AIR 21 B2A/B4P - Panel		(4) 4 5 (0)	
11		3	Ericsson - AIR 21 B4A/B2P - Panel		(4) 1 5/8" (1) 1-1/4" Fiber	
12	175.0	3	Ericsson - 840590966 - Panel	(3) VFA12-HD	(1) 1-1/4 Fiber (1) 1.9" Fiber	T-Mobile
13		3	Ericsson KRY 112 144/1		(3) 7/8" Hybrid	
14		3	Ericsson 4480 B71 + B85		(3) 7/8 1198114	
13		3	Swedcom - SWCP 2X7014 - Panel	(3) Modified		
14		6	CommScope - NHH-65B-R2B - Panel	Sector Frames with (3)		
15		3	Samsung - MT6407-77A - Panel	BSAMNT-SBS-1-2, (3)	(1) 1 5/8"	
16	165.0	3	B2/B66A RRH-BR049 (RFV01U-D1A)	VZWSMART-P40-	Hybrid	Verizon
17	200.0	3	B5/B13 RRH-BR04C (RFV01U-D2A)	238X150, (12)	(1) W/G Ladder	7 61.12011
18		1	Raycap RVZDC-6627-PF-48 - OVP	VZWSMART-MSK1, (3) VZWSMART-SFK1 and (3) VZWSMART-SFK3		
23		3	RFS - APXVTM14-C-I20 - Panel			
24		3	RFS - APXVSPP18 - Panel			
25		3	ALU - 2500 MHz - RRU		(2) 1 1 /4"	Cariat
26	138.0	3	ALU - 1900 MHz - RRU	(3) T-Frame	(3) 1 1/4" (1) 5/8" Fiber	Sprint Nextel
27		3	ALU - 800 MHz - RRU		(±) 3/6 FIDE	INEXLEI
28		3	ALU - 800MHz Filter			
29		4	RFS - ACU-A20-N - RET			

Proposed Carrier's Final Configuration of Antennas, Mounts and Transmission Lines

Information pertaining to the proposed carrier's final configuration of antennas and transmission lines was provided by SBA Communications Corp. The proposed antennas and lines are listed below.

Items	Elevation (ft)	Qty.	Antenna Descriptions	Mount Type & Qty.	Transmission Lines	Owner
19	3 JMA Wireless MX08FRO665-21 Panel		(2) 6			
20	155.0	3	Fujitsu TA08025-B605 RRU	(3) Commscope MTC3975083	(1) 1.75"	Dish
21	155.0	3	Fujitsu TA08025-B604 RRU	(Sector frames)	Hybrid	Wireless
22		1	Raycap RDIDC-9181-PF-48 OVP	(Sector frames)		

See the attached coax layout for the line placement considered in the analysis.

Analysis Results

The results of the structural analysis, performed for the wind and ice loading and antenna equipment as defined above, are summarized as the following:

Tower Component	Legs	Diagonals	Horizontals
Max. Usage:	70.1%	104.8%	4.8%
Pass/Fail	Pass	Pass	Pass

Foundations

	Compression (Kips)	Uplift (Kips)	Shear (Kips)
Analysis Reactions	528.2	453.0	51.1

The foundation has been investigated using the supplied documents and soils report and was found adequate. Therefore, no modification to the foundation will be required.

Operational Condition (Rigidity):

Operational characteristics of the tower are found to be within the limits prescribed by TIA-222 for the installed antennas. The maximum twist/sway at the elevation of the proposed equipment is 0.0785 degrees under the operational wind speed as specified in the Analysis Criteria.

Conclusions

Based on the analysis results, the existing structure and its foundation were found to be adequate to safely support the existing and proposed equipment and meet the minimum requirements per the TIA-222 Standard under the design basic wind speed as specified in the Analysis Criteria.

Standard Conditions

- 1. This analysis was performed based on the information supplied to (TES) Tower Engineering Solutions, LLC. Verification of the information provided was not included in the Scope of Work for TES. The accuracy of the analysis is dependent on the accuracy of the information provided.
- 2. The structural analysis was performance based upon the evidence available at the time of this report. All information provided by the client is considered to be accurate.
- 3. The analyses will be performed based on the codes as specified by the client or based on the best knowledge of the engineering staff of TES. In the absence of information to the contrary, all work will be performed in accordance with the latest relevant revision of ANSI/TIA-222. If wind speed and/or ice loads are different from the minimum values recommended by the ANSI/TIA-222 standard or other codes, TES should be notified in writing and the applicable minimum values provided by the client.
- 4. The configuration of the existing mounts, antennas, coax and other appurtenances were supplied by the customer for the current structural analysis. TES has not visited the tower site to verify the adequacy of the information provided. If there is any discrepancy found in the report regarding the existing conditions, TES should be notified immediately to evaluate the effect of the discrepancy on the analysis results.
- 5. The client will assume responsibility for rework associated with the differences in initially provided information, including tower and foundation information, existing and/or proposed equipment and transmission lines.
- 6. If a feasibility analysis was performed, final acceptance of changed conditions shall be based upon a rigorous structural analysis.

Structure: MA12227-A-SBA

Site Name: Truro

SOL 3 1/2" S0LID

SOL 3" SOLID

10

138.00

138.00

138.00

138.00

Code: TIA-222-G

Type:

Base Elev:

Self Support Base Shape: Basic WS:

10/26/2023

Height:

190.00 (ft)

0.00(ft)

Triangle **Base Width:** 22.50

5.41

SAE 2X2X0.1875

Top Width:

Basic Ice WS:

Operational WS:

115.00

60.00

50.00

Page: 1

Section Properties Sect Leg Members **Diagonal Members Horizontal Members** 1-2 SOL 5 1/4" SOLID SAE 4X4X0.25 SOL 5" SOLID SAE 4X4X0.25 3 SOL 5" SOLID SAE 3.5X3.5X0.25 4 SOL 4 3/4" SOLID SAE 3.5X3.5X0.25 SOL 4 1/4" SOLID SAE 3X3X0.1875 6 SOL 4" SOLID SAE 2.5X2.5X0.25 8 SOL 3 3/4" SOLID SAE 2.5X2.5X0.1875


SAE 2.5X2.5X0.1875

SAE 2X2X0.1875

	Discrete Appurtenances				
Attach	Force				
Elev (ft)	Elev (ft)	Qty	Description		
190.00	190.00	1	Lightning Rod		
187.30	187.30	1	(3) USF12-496-U		
187.30	187.30	3	AM-X-CD-16-65-00T-RET		
187.30	187.30	3	Cci - DMP5R-BU4DA		
187.30	187.30	3	DUO1417-8686-0		
187.30	187.30	3	800 10121		
187.30	187.30	6	LGP17201		
187.30	187.30	3	RRUS 12		
187.30	187.30	3	RRUS 4478 B14		
187.30	187.30	3	4449 B5/B12		
187.30	187.30	2	DC6-48-60-18-8F		
175.00	175.00	3	AIR 21 B2A/B4P		
175.00	175.00	3	AIR 21 B4A/B2P		
175.00	175.00	3	840590966		
175.00	175.00	3	Ericsson KRY 112 144/1		
175.00	175.00	3	Ericsson 4480 B71 + B85		
175.00	175.00	3	VFA12-HD		
165.00	165.00	3	Sector Frame		
165.00	165.00	3	SWCP 2X7014		
165.00	165.00	6	NHH-65B-R2B		
165.00	165.00	3	MT6407-77A		
165.00	165.00	3	B2/B66A RRH-BR049 (RFV01U-D1A)		
165.00	165.00	3	B5/B13 RRH-BR04C (RFV01U-D2A)		
165.00	165.00	1	Raycap RVZDC-6627-PF-48		
165.00	165.00	1	(3) V-Braces		
165.00	165.00	1	(3) Stabilizer Kit		
165.00	165.00	1	Handrail Kit		
155.00	155.00	3	MX08FRO665-21		
155.00	155.00	1	(3) MTC3975083		
155.00	155.00	3	TA08025-B605		
155.00	155.00	3	TA08025-B604		
155.00	155.00	1	RDIDC-9181-PF-48		
138.00	138.00	3	T-Arm (Flat)		
138.00	138.00	3	APXVTM14-C-I20		
138.00	138.00	3	APXVSPP18-C		
138.00	138.00	3	1900MHz RRH		
138.00	138.00	3	1900MHz RRH		
138.00	138.00	3	800 MHz RRH		

3 ALU 800MHz External Notch Filt

4 ACU-A20-N



Structure: MA12227-A-SBA

Site Name: Truro Code: TIA-222-G

Type:Self SupportBase Shape:TriangleBasic WS:115.00Height:190.00 (ft)Base Width:22.50Basic Ice WS:50.00

Base Elev: 0.00 (ft) Top Width: 5.41 Operational WS: 60.00 Page: 2



10/26/2023

Linear Appurtenances				
Elev	Elev			
From (ft)	To (ft)	Qty	Description	
0.00	187.30	12	1 5/8" Coax	
0.00	187.30	2	3" Conduit	
0.00	187.30	4	3/4" DC	
0.00	187.30	2	7/16" Fiber	
0.00	187.30	1	Climbing Ladder	
0.00	187.30	1	Safety Cable	
0.00	187.30	1	W/G Ladder	
0.00	175.00	4	1 5/8" Coax	
0.00	175.00	1	1-1/4" Fiber	
0.00	175.00	1	1.9" Fiber	
0.00	175.00	3	7/8" Hybrid	
0.00	175.00	1	W/G Ladder	
0.00	165.00	1	1 5/8" Hybrid	
0.00	165.00	1	W/G Ladder	
0.00	155.00	1	1.75" Hybrid	
0.00	138.00	3	1 1/4" Coax	
0.00	138.00	1	5/8" Fiber	
0.00	138.00	1	W/G Ladder	

Base Reactions

Leg Overturning

Max Uplift: -452.93 (kips Moment: 9745.70 (ft-kips)

 Max Down:
 528.19 (kips
 Total Down:
 84.12 (kips)

 Max Shear:
 51.05 (kips
 Total Shear:
 87.35 (kips)


Structure: MA12227-A-SBA

Site Name:TruroCode:TIA-222-G10/26/2023Type:Self SupportBase Shape:TriangleBasic WS:115.00

 Height:
 190.00 (ft)
 Base Width:
 22.50
 Basic Ice WS:
 50.00

 Base Elev:
 0.00 (ft)
 Top Width:
 5.41
 Operational WS:
 60.00
 Page: 3





Structure: MA12227-A-SBA - Coax Line Placement


Type: Self Support

Site Name: Truro

Height: 190.00 (ft) 10/26/2023

Page: 4





Loading Summary

Structure: MA12227-A-SBA **Code:** TIA-222-G 10/26/2023

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III



Page: 5

Discrete Appurtenances Properties

			N	o Ice	lce	Э						
Attach Elev (ft)	Description	Qty	Weight (lb)	CaAa (sf)	Weight (lb)	CaAa (sf)	Len (in)	Width (in)	Depth (in)	Ka	Orientation Factor	Vert Ecc (ft)
	Lightning Rod	1	5.00	0.500	31.73	2.728	72.000	1.000	1.000	1.00	1.00	0.000
187.30	(3) USF12-496-U	1	1598.0	34.800	4445.96	81.316	0.000	0.000	0.000	0.75	1.00	0.000
187.30	AM-X-CD-16-65-00T-RET	3	48.50	7.080	255.65	10.228	72.000	11.800	5.900	0.80	0.75	0.000
187.30	Cci - DMP5R-BU4DA	3	20.30	8.280	280.17	9.844	48.000	20.700	7.700	0.80	0.85	0.000
187.30	DUO1417-8686-0	3	20.30	5.640	222.59	6.912	48.400	14.000	9.000	0.80	0.82	0.000
187.30	800 10121	3	46.30	4.680	192.93	7.124	54.500	10.300	5.900	0.80	0.79	0.000
187.30	LGP17201	6	31.00	1.950	79.78	3.222	13.900	14.400	3.700	0.80	0.50	0.000
187.30	RRUS 12	3	60.00	2.700	145.55	3.542	18.200	17.800	8.000	0.80	0.50	0.000
187.30	RRUS 4478 B14	3	59.40	1.650	112.33	2.312	15.000	13.200	7.300	0.80	0.50	0.000
187.30	4449 B5/B12	3	71.00	1.970	139.14	2.669	17.900	13.200	9.400	0.80	0.50	0.000
187.30	DC6-48-60-18-8F	2	31.80	0.920	110.72	1.479	24.000	11.000	11.000	1.00	1.00	0.000
175.00	AIR 21 B2A/B4P	3	91.50	5.650	316.41	7.503	56.000	12.100	7.900	0.80	0.86	0.000
175.00	AIR 21 B4A/B2P	3	90.30	5.650	315.21	7.503	56.000	12.100	7.900	0.80	0.86	0.000
175.00	840590966	3	101.40	18.780	628.26	22.292	95.900	23.500	7.100	0.80	0.69	0.000
175.00	Ericsson KRY 112 144/1	3	11.00	0.410	24.65	1.011	6.900	6.100	2.700	0.80	0.67	0.000
175.00	Ericsson 4480 B71 + B85	3	93.00	2.850	184.05	3.704	21.800	15.700	7.500	0.80	0.50	0.000
175.00	VFA12-HD	3	774.00	18.400	1731.47	47.665	0.000	0.000	0.000	0.75	0.75	0.000
165.00	Sector Frame	3	500.00	15.500	1383.60	31.113	0.000	0.000	0.000	0.75	0.75	0.000
165.00	SWCP 2X7014	3	30.00	9.940	397.80	11.746	76.700	14.000	11.300	0.80	0.93	0.000
165.00	NHH-65B-R2B	6	43.70	7.140	312.02	9.745	72.000	11.900	7.100	0.80	0.83	0.000
165.00	MT6407-77A	3	79.40	4.690	239.29	5.904	35.100	16.100	5.500	0.80	0.70	0.000
165.00	B2/B66A RRH-BR049	3	84.40	1.880	149.28	2.578	15.000	15.000	10.000	0.80	0.50	0.000
165.00	B5/B13 RRH-BR04C (RFV01U-D2A)	3	70.30	1.880	131.86	2.578	15.000	15.000	8.100	0.80	0.50	0.000
165.00	Raycap RVZDC-6627-PF-48	1	32.00	4.060	176.20	5.100	29.500	16.500	12.600	0.80	0.67	0.000
165.00	(3) V-Braces	1	230.00	6.700	636.46	15.580	0.000	0.000	0.000	0.75	1.00	0.000
165.00	(3) Stabilizer Kit	1	180.00	6.100	466.29	14.185	0.000	0.000	0.000	0.75	1.00	0.000
165.00	Handrail Kit	1	261.72	6.750	654.85	15.100	0.000	0.000	0.000	0.75	1.00	0.000
155.00	MX08FRO665-21	3	64.50	12.100	428.09	13.874	72.000	20.000	8.000	0.80	0.74	0.000
155.00	(3) MTC3975083	1	1056.4	29.450	2346.97	75.707	0.000	0.000	0.000	0.75	1.00	0.000
155.00	TA08025-B605	3	75.00	1.960	140.38	2.661	15.800	15.000	9.100	0.80	0.50	0.000
155.00	TA08025-B604	3	63.90	1.960	127.19	2.661	15.800	15.000	7.900	0.80	0.50	0.000
155.00	RDIDC-9181-PF-48	1	21.85	2.010	88.26	2.720	16.570	14.570	8.460	1.00	1.00	0.000
138.00	T-Arm (Flat)	3	400.00	10.000	744.08	20.753	0.000	0.000	0.000	0.75	0.75	0.000
138.00	APXVTM14-C-I20	3	56.20	5.910	251.17	7.186	56.300	12.600	6.300	0.80	0.77	0.000
138.00	APXVSPP18-C	3	57.00	7.080	269.99	10.119	72.000	11.800	7.000	0.80	0.83	0.000
138.00	1900MHz RRH	3	44.00	2.500	178.52	3.627	23.000	13.000	17.000	0.80	0.50	0.000
138.00	1900MHz RRH	3	44.00	2.500	178.52	3.627	23.000	13.000	17.000	0.80	0.50	0.000
138.00	800 MHz RRH	3	53.00	2.130	144.14	3.336	19.700	13.000	10.800	0.80	0.50	0.000
138.00	ALU 800MHz External Notch Filt	3	8.80	0.780	30.54	1.577	10.000	8.000	3.000	0.80	0.50	0.000
138.00	ACU-A20-N	4	1.00	0.140	6.29	0.506	4.000	2.000	3.500	0.80	0.50	0.000

Totals: 110 13,253.28 39,472.65 Number of Appurtenances : 40

Loading Summary

Structure: MA12227-A-SBA **Code**: TIA-222-G 10/26/2023

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III Page: 6



Linear Appurtenances Properties

Elev. From	Elev. To	-	•		Weight	Pct In	Spread On	Bundling	Cluster Dia	of	-	Orientation	Ka
(ft)	(ft)	Description	Qty	(in)	(lb/ft)	Block	races	Arrangement	(in)	Zone	(in)	Factor	Override
0.00	187.30	1 5/8" Coax	12	1.98	1.04	100.00	3	Individual IR		N	1.00	1.00	
0.00	187.30	3" Conduit	2	3.02	1.78	100.00	3	Individual IR		N	1.00	1.00	
0.00	187.30	3/4" DC	4	0.75	0.40	100.00	3	Individual NR		N	1.00	1.00	0
0.00	187.30	7/16" Fiber	2	0.44	0.16	100.00	3	Individual NR		Ν	1.00	1.00	0
0.00	187.30	Climbing Ladder	1	3.00	6.90	100.00	1	Individual NR		Ν	1.00	1.00	
0.00	187.30	Safety Cable	1	0.38	0.27	100.00	1	Individual NR		N	1.00	1.00	
0.00	187.30	W/G Ladder	1	1.50	6.00	100.00	3	Individual NR		N	1.00	1.00	
0.00	175.00	1 5/8" Coax	4	1.98	1.04	50.00	1	Block		Ν	0.25	0.78	
0.00	175.00	1-1/4" Fiber	1	1.25	0.95	100.00	1	Individual NR		N	1.00	1.00	
0.00	175.00	1.9" Fiber	1	1.90	0.95	100.00	1	Individual NR		Ν	1.00	1.00	
0.00	175.00	7/8" Hybrid	3	0.88	0.65	100.00	1	Individual IR		Ν	1.00	0.67	
0.00	175.00	W/G Ladder	1	2.00	6.00	100.00	1	Individual NR		N	1.00	1.00	
0.00	165.00	1 5/8" Hybrid	1	1.98	1.04	100.00	2	Individual IR		N	1.00	0.67	
0.00	165.00	W/G Ladder	1	2.00	6.00	100.00	2	Individual NR		Ν	1.00	1.00	
0.00	155.00	1.75" Hybrid	1	1.75	1.99	100.00	2	Individual NR		N	1.00	1.00	
0.00	138.00	1 1/4" Coax	3	1.55	0.66	100.00	2	Individual IR		Ν	1.00	0.65	
0.00	138.00	5/8" Fiber	1	0.63	0.15	100.00	2	Individual NR		N	1.00	1.00	
0.00	138.00	W/G Ladder	1	2.00	6.00	100.00	1	Individual NR		Ν	1.00	1.00	

MA12227-A-SBA Code: 10/26/2023 Structure: TIA-222-G

Site Name: Truro **Exposure:** В 190.00 (ft) Crest Height: 0.00 Height:

D - Stiff Soil Base Elev: 0.000 (ft) Site Class:

Gh: 0.85 Topography: 1 Struct Class: III





Load Case: 1.2D + 1.6W Normal Wind 1.2D + 1.6W 115 mph Wind at Normal To Face

1 60 Wind Load Factor: Wind Importance Factor: 1.15

Dead Load Factor: 1.20 0.00 Ice Dead Load Factor:

Ice Importance Factor: 1.25

Sect Seq	Wind Height (ft)	Tota Flat qz Area (psf) (sqft	Round Area	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	23.17 44.3	36 17.52	0.00	0.14	2.81	1.00	1.00	0.00	53.17	105.94	0.00	10,028.	0.0	4702.34	2519.62	7,221.95
2	30.0	23.19 40.9	11 17.52	0.00	0.14	2.79	1.00	1.00	0.00	49.76	105.94	0.00	9,784.7	0.0	4381.05	2521.74	6,902.79
3	50.0	26.83 37.5	16.69	0.00	0.15	2.78	1.00	1.00	0.00	45.90	105.94	0.00	9,049.0	0.0	4658.98	2918.01	7,576.99
4	70.0	29.54 29.9	16.69	0.00	0.14	2.81	1.00	1.00	0.00	38.07	105.94	0.00	8,507.3	0.0	4293.46	3212.46	7,505.92
5	90.0	31.73 27.0	76 15.85	0.00	0.15	2.79	1.00	1.00	0.00	34.89	105.94	0.00	7,831.3	0.0	4200.37	3451.61	7,651.98
6	110.0	33.61 26.3	95 14.19	0.00	0.16	2.75	1.00	1.00	0.00	33.68	105.94	0.00	6,424.1	0.0	4228.70	3655.29	7,883.99
7	130.0	35.25 19.2	79 13.35	0.00	0.15	2.78	1.00	1.00	0.00	26.20	106.39	0.00	5,964.4	0.0	3496.91	3943.21	7,440.12
8	150.0	36.72 16.6	10 12.52	0.00	0.16	2.75	1.00	1.00	0.00	23.26	94.75	0.00	4,908.5	0.0	3191.86	3616.98	6,808.84
9	170.0	38.06 14.12	29 11.68	0.00	0.17	2.69	1.00	1.00	0.00	20.45	82.58	0.00	4,177.8	0.0	2849.36	3214.22	6,063.58
10	185.0	38.99 7.3	11 5.01	0.00	0.20	2.59	1.00	1.00	0.00	10.19	24.06	0.00	1,542.3	0.0	1398.52	940.61	2,339.13
													68,218.1	0.0	<u> </u>		67,395.30

Load Case: 1.2D + 1.6W 60° Wind 1.2D + 1.6W 115 mph Wind at 60° From Face

1.60 Wind Load Factor: **Dead Load Factor:** 1.20 Ice Dead Load Factor: 0.00

Wind Importance Factor: 1.15 1.25

Ice Importance Factor:

Total Ice Total Ice Wind Flat Round Round Ice Eff Linear Linear Total Struct Linear **Total** Sect Height gz Area Area Area Sol Thick Area **Area** Area Weight Weight Force Force Force Ratio Cf Df Dr Ice (lb) (lb) Seq (ft) (psf) (sqft) (sqft) (sqft) (in) (sqft) (sqft) (sqft) (lb) (lb) (lb) 10.0 23.17 44.336 17.52 0.00 0.14 2.81 0.80 1.00 0.00 44.30 105.94 0.00 10,028. 0.0 3918.07 2519.62 6,437.68 2 30.0 23.19 40.911 17.52 0.00 0.14 2.79 0.80 1.00 0.00 41.58 105.94 0.00 9,784.7 0.0 3660.62 2521.74 6,182.37 3 50.0 26.83 37.553 16.69 0.00 0.15 2.78 0.80 38.39 105.94 9,049.0 0.0 3896.71 2918.01 6,814.72 1.00 0.00 0.00 70.0 29.54 29.932 16 69 0.00 0 14 2.81 0.80 1.00 0.00 32.08 105.94 0.00 8,507.3 0.0 3618.33 3212.46 6,830.78 5 90.0 31.73 27.076 15.85 0.00 0.15 2.79 0.80 1.00 0.00 29.47 105.94 0.00 7,831.3 0.0 3548.36 3451.61 6,999.96 6 110.0 33.61 26.395 14.19 0.00 0.16 2.75 0.80 1.00 0.00 28.40 105.94 0.00 6,424.1 0.0 3565.85 3655.29 7,221.14 7 130.0 35.25 19.279 13.35 0.00 0.15 2.78 0.80 1.00 0.00 22.34 106.39 0.00 0.0 2982.24 3943.21 6.925.45 5,964.4 150.0 36.72 16.640 12 52 0.00 0.16 2.75 0.80 1.00 0.00 19.93 94 75 0.00 4,908.5 0.0 2735.20 3616.98 6,352.17 8 9 170.0 11.68 0.00 0.80 1.00 0.00 82.58 5,669.94 38.06 14.129 0.17 2.69 17.63 0.00 4,177.8 0.0 2455.71 3214.22 0.20 2.59 10 185.0 38.99 7.341 5.01 0.00 0.80 1.00 0.00 8 72 24.06 0.00 0.0 1197.02 940.61 1,542.3 2,137.63 68,218.1 0.0 61,571.85

Structure: MA12227-A-SBA **Code**: TIA-222-G 10/26/2023

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III





Load Case: 1.2D + 1.6W 90° Wind 1.2D + 1.6W 115 mph Wind at 90° From Face

Wind Load Factor: 1.60 Wind Importance Factor: 1.15

Dead Load Factor: 1.20 Ice Dead Load Factor: 0.00

Ice Importance Factor: 1.25

Sect Seq	Wind Height (ft)	Total Flat qz Area (psf) (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	23.17 44.336	17.52	0.00	0.14	2.81	0.85	1.00	0.00	46.52	105.94	0.00	10,028.	0.0	4114.13	2519.62	6,633.75
2	30.0	23.19 40.911	17.52	0.00	0.14	2.79	0.85	1.00	0.00	43.62	105.94	0.00	9,784.7	0.0	3840.73	2521.74	6,362.47
3	50.0	26.83 37.553	16.69	0.00	0.15	2.78	0.85	1.00	0.00	40.27	105.94	0.00	9,049.0	0.0	4087.28	2918.01	7,005.28
4	70.0	29.54 29.932	16.69	0.00	0.14	2.81	0.85	1.00	0.00	33.58	105.94	0.00	8,507.3	0.0	3787.11	3212.46	6,999.57
5	90.0	31.73 27.076	15.85	0.00	0.15	2.79	0.85	1.00	0.00	30.82	105.94	0.00	7,831.3	0.0	3711.36	3451.61	7,162.97
6	110.0	33.61 26.395	14.19	0.00	0.16	2.75	0.85	1.00	0.00	29.72	105.94	0.00	6,424.1	0.0	3731.56	3655.29	7,386.85
7	130.0	35.25 19.279	13.35	0.00	0.15	2.78	0.85	1.00	0.00	23.31	106.39	0.00	5,964.4	0.0	3110.91	3943.21	7,054.12
8	150.0	36.72 16.640	12.52	0.00	0.16	2.75	0.85	1.00	0.00	20.77	94.75	0.00	4,908.5	0.0	2849.36	3616.98	6,466.34
9	170.0	38.06 14.129	11.68	0.00	0.17	2.69	0.85	1.00	0.00	18.34	82.58	0.00	4,177.8	0.0	2554.12	3214.22	5,768.35
10	185.0	38.99 7.341	5.01	0.00	0.20	2.59	0.85	1.00	0.00	9.09	24.06	0.00	1,542.3	0.0	1247.40	940.61	2,188.01
													68,218.1	0.	<u></u>		63,027.71

Load Case: 0.9D + 1.6W Normal Wind 0.9D + 1.6W 115 mph Wind at Normal To Face

Wind Load Factor: 1.60
Dead Load Factor: 0.90
Ice Dead Load Factor: 0.00
Wind Importance Factor: 1.25

		Total	Total	Ice								Ice					
	Wind	Flat	Round	Round					Ice	Eff	Linear	Linear	Total		Struct	Linear	Total
Sect Seq	Height (ft)	qz Area (psf) (sqft)	Area (sqft)	Area (sqft)	Sol Ratio	Cf	Df	Dr	Thick (in)	Area (sqft)	Area (sqft)	Area (sqft)	Weight (lb)	Weight Ice (lb)	Force (lb)	Force (lb)	Force (lb)
1	10.0	23.17 44.336	17.52	0.00	0.14	2.81	1.00	1.00	0.00	53.17	105.94	0.00	7,521.6	0.0	4702.34	2519.62	7,221.95
2	30.0	23.19 40.911	17.52	0.00	0.14	2.79	1.00	1.00	0.00	49.76	105.94	0.00	7,338.5	0.0	4381.05	2521.74	6,902.79
3	50.0	26.83 37.553	16.69	0.00	0.15	2.78	1.00	1.00	0.00	45.90	105.94	0.00	6,786.7	0.0	4658.98	2918.01	7,576.99
4	70.0	29.54 29.932	16.69	0.00	0.14	2.81	1.00	1.00	0.00	38.07	105.94	0.00	6,380.4	0.0	4293.46	3212.46	7,505.92
5	90.0	31.73 27.076	15.85	0.00	0.15	2.79	1.00	1.00	0.00	34.89	105.94	0.00	5,873.5	0.0	4200.37	3451.61	7,651.98
6	110.0	33.61 26.395	14.19	0.00	0.16	2.75	1.00	1.00	0.00	33.68	105.94	0.00	4,818.1	0.0	4228.70	3655.29	7,883.99
7	130.0	35.25 19.279	13.35	0.00	0.15	2.78	1.00	1.00	0.00	26.20	106.39	0.00	4,473.3	0.0	3496.91	3943.21	7,440.12
8	150.0	36.72 16.640	12.52	0.00	0.16	2.75	1.00	1.00	0.00	23.26	94.75	0.00	3,681.4	0.0	3191.86	3616.98	6,808.84
9	170.0	38.06 14.129	11.68	0.00	0.17	2.69	1.00	1.00	0.00	20.45	82.58	0.00	3,133.3	0.0	2849.36	3214.22	6,063.58
10	185.0	38.99 7.341	5.01	0.00	0.20	2.59	1.00	1.00	0.00	10.19	24.06	0.00	1,156.7	0.0	1398.52	940.61	2,339.13
													51.163.6	0.	0		67.395.30

Structure: MA12227-A-SBA **Code**: TIA-222-G 10/26/2023

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III



Load Case: 0.9D + 1.6W 60° Wind 0.9D + 1.6W 115 mph Wind at 60° From Face

Wind Load Factor: 1.60 Wind Importance Factor: 1.15

Dead Load Factor: 0.90 lce Dead Load Factor: 0.00

Ice Importance Factor: 1.25

1.15

1.25

		Total	Total	Ice								Ice					
Se Se		Flat qz Area (psf) (sqft)	Round Area (sqft)	Round Area (sqft)	Sol Ratio	Cf	Df	Dr	lce Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	23.17 44.336	17.52	0.00	0.14	2.81	0.80	1.00	0.00	44.30	105.94	0.00	7,521.6	0.0	3918.07	2519.62	6,437.68
2	30.0	23.19 40.911	17.52	0.00	0.14	2.79	0.80	1.00	0.00	41.58	105.94	0.00	7,338.5	0.0	3660.62	2521.74	6,182.37
3	50.0	26.83 37.553	16.69	0.00	0.15	2.78	0.80	1.00	0.00	38.39	105.94	0.00	6,786.7	0.0	3896.71	2918.01	6,814.72
4	70.0	29.54 29.932	16.69	0.00	0.14	2.81	0.80	1.00	0.00	32.08	105.94	0.00	6,380.4	0.0	3618.33	3212.46	6,830.78
5	90.0	31.73 27.076	15.85	0.00	0.15	2.79	0.80	1.00	0.00	29.47	105.94	0.00	5,873.5	0.0	3548.36	3451.61	6,999.96
6	110.0	33.61 26.395	14.19	0.00	0.16	2.75	0.80	1.00	0.00	28.40	105.94	0.00	4,818.1	0.0	3565.85	3655.29	7,221.14
7	130.0	35.25 19.279	13.35	0.00	0.15	2.78	0.80	1.00	0.00	22.34	106.39	0.00	4,473.3	0.0	2982.24	3943.21	6,925.45
8	150.0	36.72 16.640	12.52	0.00	0.16	2.75	0.80	1.00	0.00	19.93	94.75	0.00	3,681.4	0.0	2735.20	3616.98	6,352.17
9	170.0	38.06 14.129	11.68	0.00	0.17	2.69	0.80	1.00	0.00	17.63	82.58	0.00	3,133.3	0.0	2455.71	3214.22	5,669.94
10	185.0	38.99 7.341	5.01	0.00	0.20	2.59	0.80	1.00	0.00	8.72	24.06	0.00	1,156.7	0.0	1197.02	940.61	2,137.63
													51,163.6	0.0	0		61,571.85

Load Case: 0.9D + 1.6W 90° Wind 0.9D + 1.6W 115 mph Wind at 90° From Face

Wind Load Factor: 1.60
Dead Load Factor: 0.90
Ice Dead Load Factor: 0.00
Wind Importance Factor: lice Importance Factor:

		Total	Total	Ice								Ice					
	Wind	Flat	Round	Round					Ice	Eff	Linear	Linear	Total		Struct	Linear	Total
Sect			Area	Area	Sol	0.5	D.		Thick	Area	Area	Area	Weight		Force	Force	Force
Seq	(ft)	(psf) (sqft)	(sqft)	(sqft)	Ratio	Cī	Df	Dr	(in)	(sqft)	(sqft)	(sqft)	(lb)	Ice (lb)	(lb)	(lb)	(lb)
1	10.0	23.17 44.336	17.52	0.00	0.14	2.81	0.85	1.00	0.00	46.52	105.94	0.00	7,521.6	0.0	4114.13	2519.62	6,633.75
2	30.0	23.19 40.911	17.52	0.00	0.14	2.79	0.85	1.00	0.00	43.62	105.94	0.00	7,338.5	0.0	3840.73	2521.74	6,362.47
3	50.0	26.83 37.553	16.69	0.00	0.15	2.78	0.85	1.00	0.00	40.27	105.94	0.00	6,786.7	0.0	4087.28	2918.01	7,005.28
4	70.0	29.54 29.932	16.69	0.00	0.14	2.81	0.85	1.00	0.00	33.58	105.94	0.00	6,380.4	0.0	3787.11	3212.46	6,999.57
5	90.0	31.73 27.076	15.85	0.00	0.15	2.79	0.85	1.00	0.00	30.82	105.94	0.00	5,873.5	0.0	3711.36	3451.61	7,162.97
6	110.0	33.61 26.395	14.19	0.00	0.16	2.75	0.85	1.00	0.00	29.72	105.94	0.00	4,818.1	0.0	3731.56	3655.29	7,386.85
7	130.0	35.25 19.279	13.35	0.00	0.15	2.78	0.85	1.00	0.00	23.31	106.39	0.00	4,473.3	0.0	3110.91	3943.21	7,054.12
8	150.0	36.72 16.640	12.52	0.00	0.16	2.75	0.85	1.00	0.00	20.77	94.75	0.00	3,681.4	0.0	2849.36	3616.98	6,466.34
9	170.0	38.06 14.129	11.68	0.00	0.17	2.69	0.85	1.00	0.00	18.34	82.58	0.00	3,133.3	0.0	2554.12	3214.22	5,768.35
10	185.0	38.99 7.341	5.01	0.00	0.20	2.59	0.85	1.00	0.00	9.09	24.06	0.00	1,156.7	0.0	1247.40	940.61	2,188.01
													51.163.6	0.	0		63.027.71

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III

1.00





Load Case: 1.2D + 1.0Di + 1.0Wi Normal Wind

Wind Load Factor:

1.2D + 1.0Di + 1.0Wi 50 mph Wind at Normal From Face

Wind Importance Factor: 1.00

Dead Load Factor: 1.20
Ice Dead Load Factor: 1.00
Ice Importance Factor: 1.25

		Total	Total	Ice								Ice					_
	Wind	Flat	Round	Round					lce	Eff	Linear	Linear			Struct	Linear	Total
Sect		qz Area	Area	Area	Sol	C.f	Df		Thick	Area	Area	Area		Weight	Force	Force	Force
Seq	(ft)	(psf) (sqft)	(sqft)	(sqft)	Ratio	CI	Df	Dr	(in)	(sqft)	(sqft)	(sqft)	(lb)	Ice (lb)	(lb)	(lb)	(lb)
1	10.0	3.81 44.336	66.25	48.72	0.25	2.44	1.00	1.00	1.66	83.06	193.62	61.01	20,663.	10634.3	657.07	625.50	1,282.57
2	30.0	3.81 40.911	68.72	51.20	0.27	2.39	1.00	1.00	1.86	81.41	194.52	74.29	21,516.	11731.5	629.81	662.57	1,292.39
3	50.0	4.41 37.553	67.26	50.57	0.28	2.35	1.00	1.00	1.95	77.43	197.76	78.18	21,056.	12007.1	682.54	781.97	1,464.52
4	70.0	4.86 29.932	65.60	48.91	0.28	2.35	1.00	1.00	2.02	68.86	199.99	80.86	20,064.	11557.6	666.62	874.07	1,540.69
5	90.0	5.22 27.076	62.59	46.74	0.30	2.31	1.00	1.00	2.07	64.49	201.70	82.92	19,296.	11465.0	659.53	946.33	1,605.85
6	110.0	5.52 26.395	66.53	52.35	0.35	2.17	1.00	1.00	2.11	67.36	203.10	84.60	18,173.	11749.0	687.47	995.33	1,682.80
7	130.0	5.79 19.279	61.84	48.49	0.35	2.16	1.00	1.00	2.15	57.44	201.31	85.30	16,833.	10869.4	612.45	1036.58	1,649.03
8	150.0	6.04 16.640	57.04	44.52	0.38	2.10	1.00	1.00	2.18	52.47	174.59	78.17	14,674.	9765.7	566.24	931.17	1,497.41
9	170.0	6.26 14.129	52.26	40.58	0.42	2.02	1.00	1.00	2.21	47.90	151.28	64.43	12,696.	8518.8	514.92	762.57	1,277.50
10	185.0	6.41 7.341	29.46	24.45	0.57	1.83	1.00	1.00	2.23	28.67	41.60	18.97	4,840.7	3298.4	285.40	156.70	442.10
													169,814.9	101596.7			13,734.86

Load Case: 1.2D + 1.0Di + 1.0Wi 60° Wind 1.2D + 1.0Di + 1.0Wi 50 mph Wind at 60° From Face

Wind Load Factor: 1.00
Dead Load Factor: 1.20
Ice Dead Load Factor: 1.00
Ice Importance Factor: 1.25

Sect Seq	Wind Height (ft)	Total Flat qz Area (psf) (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	3.81 44.336	66.25	48.72	0.25	2.44	0.80	1.00	1.66	74.19	193.62	61.01	20,663.	10634.3	586.92	625.50	1,212.42
2	30.0	3.81 40.911	68.72	51.20	0.27	2.39	0.80	1.00	1.86	73.23	194.52	74.29	21,516.	11731.5	566.51	662.57	1,229.09
3	50.0	4.41 37.553	67.26	50.57	0.28	2.35	0.80	1.00	1.95	69.92	197.76	78.18	21,056.	12007.1	616.34	781.97	1,398.31
4	70.0	4.86 29.932	65.60	48.91	0.28	2.35	0.80	1.00	2.02	62.88	199.99	80.86	20,064.	11557.6	608.67	874.07	1,482.74
5	90.0	5.22 27.076	62.59	46.74	0.30	2.31	0.80	1.00	2.07	59.07	201.70	82.92	19,296.	11465.0	604.14	946.33	1,550.47
6	110.0	5.52 26.395	66.53	52.35	0.35	2.17	0.80	1.00	2.11	62.08	203.10	84.60	18,173.	11749.0	633.60	995.33	1,628.93
7	130.0	5.79 19.279	61.84	48.49	0.35	2.16	0.80	1.00	2.15	53.59	201.31	85.30	16,833.	10869.4	571.34	1036.58	1,607.92
8	150.0	6.04 16.640	57.04	44.52	0.38	2.10	0.80	1.00	2.18	49.14	174.59	78.17	14,674.	9765.7	530.32	931.17	1,461.49
9	170.0	6.26 14.129	52.26	40.58	0.42	2.02	0.80	1.00	2.21	45.08	151.28	64.43	12,696.	8518.8	484.55	762.57	1,247.12
10	185.0	6.41 7.341	29.46	24.45	0.57	1.83	0.80	1.00	2.23	27.21	41.60	18.97	4,840.7	3298.4	270.79	156.70	427.49
													69.814.9	101596.7	,		13.245.98

Structure: MA12227-A-SBA **Code**: TIA-222-G 10/26/2023

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III



Load Case: 1.2D + 1.0Di + 1.0Wi 90° Wind 1.2D + 1.0Di + 1.0Wi 50 mph Wind at 90° From Face

Wind Load Factor: 1.00 Wind Importance Factor: 1.00

Dead Load Factor: 1.20 Ice Dead Load Factor: 1.00

Ice Importance Factor: 1.25

Sect Seq		Total Flat qz Area (psf) (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	3.81 44.336	66.25	48.72	0.25	2.44	0.85	1.00	1.66	76.40	193.62	61.01	20,663.	10634.3	604.45	625.50	1,229.96
2	30.0	3.81 40.911	68.72	51.20	0.27	2.39	0.85	1.00	1.86	75.27	194.52	74.29	21,516.	11731.5	582.34	662.57	1,244.91
3	50.0	4.41 37.553	67.26	50.57	0.28	2.35	0.85	1.00	1.95	71.79	197.76	78.18	21,056.	12007.1	632.89	781.97	1,414.86
4	70.0	4.86 29.932	65.60	48.91	0.28	2.35	0.85	1.00	2.02	64.37	199.99	80.86	20,064.	11557.6	623.15	874.07	1,497.22
5	90.0	5.22 27.076	62.59	46.74	0.30	2.31	0.85	1.00	2.07	60.43	201.70	82.92	19,296.	11465.0	617.99	946.33	1,564.32
6	110.0	5.52 26.395	66.53	52.35	0.35	2.17	0.85	1.00	2.11	63.40	203.10	84.60	18,173.	11749.0	647.07	995.33	1,642.40
7	130.0	5.79 19.279	61.84	48.49	0.35	2.16	0.85	1.00	2.15	54.55	201.31	85.30	16,833.	10869.4	581.62	1036.58	1,618.20
8	150.0	6.04 16.640	57.04	44.52	0.38	2.10	0.85	1.00	2.18	49.97	174.59	78.17	14,674.	9765.7	539.30	931.17	1,470.47
9	170.0	6.26 14.129	52.26	40.58	0.42	2.02	0.85	1.00	2.21	45.78	151.28	64.43	12,696.	8518.8	492.14	762.57	1,254.72
10	185.0	6.41 7.341	29.46	24.45	0.57	1.83	0.85	1.00	2.23	27.57	41.60	18.97	4,840.7	3298.4	274.44	156.70	431.14
													69,814.9	101596.7	-		13,368.20

Load Case: 1.0D + 1.0W Normal Wind 1.0D + 1.0W 60 mph Wind at Normal To Face

Wind Load Factor: 1.00
Dead Load Factor: 1.00
Ice Dead Load Factor: 0.00

Note the property of the property of

		Total	Total	Ice								Ice					
	Wind	Flat	Round	Round					Ice	Eff	Linear	Linear	Total		Struct	Linear	Total
Sect Seq	Height (ft)	qz Area (psf) (sqft)	Area (sqft)	Area (sqft)	Sol Ratio	Cf	Df	Dr	Thick (in)	Area (sqft)	Area (sqft)	Area (sqft)	Weight (lb)	Weight Ice (lb)	Force (lb)	Force (lb)	Force (lb)
004	(11)	(pai) (aqit)	(Sqit)	(Sqit)	itatio	01	<u> </u>	<u> </u>	(1117)	(3qit)	(Sqit)	(3qit)	(ID)	ice (ib)	(ID)	(ID)	(ID)
1	10.0	5.48 44.336	17.52	0.00	0.14	2.81	1.00	1.00	0.00	54.27	105.94	0.00	8,357.4	0.0	710.05	372.75	1,082.81
2	30.0	5.49 40.911	17.52	0.00	0.14	2.79	1.00	1.00	0.00	50.85	105.94	0.00	8,153.9	0.0	662.32	373.07	1,035.39
3	50.0	6.35 37.553	16.69	0.00	0.15	2.78	1.00	1.00	0.00	47.02	105.94	0.00	7,540.8	0.0	706.01	431.69	1,137.70
4	70.0	6.99 29.932	16.69	0.00	0.14	2.81	1.00	1.00	0.00	39.39	105.94	0.00	7,089.4	0.0	657.18	475.25	1,132.43
5	90.0	7.51 27.076	15.85	0.00	0.15	2.79	1.00	1.00	0.00	36.07	105.94	0.00	6,526.1	0.0	642.45	510.63	1,153.08
6	110.0	7.96 26.395	14.19	0.00	0.16	2.75	1.00	1.00	0.00	34.46	105.94	0.00	5,353.5	0.0	640.06	540.77	1,180.83
7	130.0	8.34 19.279	13.35	0.00	0.15	2.78	1.00	1.00	0.00	26.85	104.73	0.00	4,970.3	0.0	530.24	559.87	1,090.12
8	150.0	8.69 16.640	12.52	0.00	0.16	2.75	1.00	1.00	0.00	23.75	93.08	0.00	4,090.4	0.0	482.19	510.63	992.82
9	170.0	9.01 14.129	11.68	0.00	0.17	2.69	1.00	1.00	0.00	20.79	80.92	0.00	3,481.5	0.0	428.45	450.15	878.61
10	185.0	9.23 7.341	5.01	0.00	0.20	2.59	1.00	1.00	0.00	10.22	23.45	0.00	1,285.2	0.0	207.49	129.67	337.17
													56.848.4	0.0	-		10.020.94

Structure: MA12227-A-SBA **Code**: TIA-222-G 10/26/2023

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III





1.00

1.25

Load Case: 1.0D + 1.0W 60° Wind 1.0D + 1.0W 60 mph Wind at 60° From Face

Wind Load Factor: 1.00 Wind Importance Factor: 1.00

Dead Load Factor: 1.00
Ice Dead Load Factor: 0.00

Ice Importance Factor: 1.25

Sect Seq	Wind Height (ft)	Total Flat qz Area (psf) (sqft)	Total Round Area (sqft)	Ice Round Area (sqft)	Sol Ratio	Cf	Df	Dr	Ice Thick (in)	Eff Area (sqft)	Linear Area (sqft)	Ice Linear Area (sqft)	Total Weight (lb)	Weight Ice (lb)	Struct Force (lb)	Linear Force (lb)	Total Force (lb)
1	10.0	5.48 44.336	17.52	0.00	0.14	2.81	0.80	1.00	0.00	45.40	105.94	0.00	8,357.4	0.0	594.03	372.75	966.78
2	30.0	5.49 40.911	17.52	0.00	0.14	2.79	0.80	1.00	0.00	42.66	105.94	0.00	8,153.9	0.0	555.74	373.07	928.81
3	50.0	6.35 37.553	16.69	0.00	0.15	2.78	0.80	1.00	0.00	39.51	105.94	0.00	7,540.8	0.0	593.24	431.69	1,024.93
4	70.0	6.99 29.932	16.69	0.00	0.14	2.81	0.80	1.00	0.00	33.40	105.94	0.00	7,089.4	0.0	557.30	475.25	1,032.55
5	90.0	7.51 27.076	15.85	0.00	0.15	2.79	0.80	1.00	0.00	30.65	105.94	0.00	6,526.1	0.0	545.99	510.63	1,056.62
6	110.0	7.96 26.395	14.19	0.00	0.16	2.75	0.80	1.00	0.00	29.18	105.94	0.00	5,353.5	0.0	542.00	540.77	1,082.76
7	130.0	8.34 19.279	13.35	0.00	0.15	2.78	0.80	1.00	0.00	23.00	104.73	0.00	4,970.3	0.0	454.10	559.87	1,013.98
8	150.0	8.69 16.640	12.52	0.00	0.16	2.75	0.80	1.00	0.00	20.42	93.08	0.00	4,090.4	0.0	414.63	510.63	925.26
9	170.0	9.01 14.129	11.68	0.00	0.17	2.69	0.80	1.00	0.00	17.96	80.92	0.00	3,481.5	0.0	370.22	450.15	820.37
10	185.0	9.23 7.341	5.01	0.00	0.20	2.59	0.80	1.00	0.00	8.75	23.45	0.00	1,285.2	0.0	177.68	129.67	307.36
													56,848.4	0.0	<u></u>	•	9,159.42

Load Case: 1.0D + 1.0W 90° Wind 1.0D + 1.0W 60 mph Wind at 90° From Face

Wind Load Factor: 1.00
Dead Load Factor: 1.00
Ice Dead Load Factor: 0.00
Wind Importance Factor: lce Importance Factor:

		Total	Total	Ice								Ice					
	Wind	Flat	Round	Round					Ice	Eff	Linear	Linear	Total		Struct	Linear	Total
Sect Seq	Height (ft)	qz Area (psf) (sqft)	Area (sqft)	Area (sqft)	Sol Ratio	Cf	Df	Dr	Thick (in)	Area (sqft)	Area (sqft)	Area (sqft)	Weight (lb)	Weight Ice (lb)	Force (lb)	Force (lb)	Force (lb)
1	10.0	5.48 44.336	17.52	0.00	0.14	2.81	0.85	1.00	0.00	47.62	105.94	0.00	8,357.4	0.0	623.03	372.75	995.79
2	30.0	5.49 40.911	17.52	0.00	0.14	2.79	0.85	1.00	0.00	44.71	105.94	0.00	8,153.9	0.0	582.39	373.07	955.46
3	50.0	6.35 37.553	16.69	0.00	0.15	2.78	0.85	1.00	0.00	41.39	105.94	0.00	7,540.8	0.0	621.43	431.69	1,053.12
4	70.0	6.99 29.932	16.69	0.00	0.14	2.81	0.85	1.00	0.00	34.90	105.94	0.00	7,089.4	0.0	582.27	475.25	1,057.52
5	90.0	7.51 27.076	15.85	0.00	0.15	2.79	0.85	1.00	0.00	32.01	105.94	0.00	6,526.1	0.0	570.10	510.63	1,080.74
6	110.0	7.96 26.395	14.19	0.00	0.16	2.75	0.85	1.00	0.00	30.50	105.94	0.00	5,353.5	0.0	566.51	540.77	1,107.28
7	130.0	8.34 19.279	13.35	0.00	0.15	2.78	0.85	1.00	0.00	23.96	104.73	0.00	4,970.3	0.0	473.14	559.87	1,033.01
8	150.0	8.69 16.640	12.52	0.00	0.16	2.75	0.85	1.00	0.00	21.26	93.08	0.00	4,090.4	0.0	431.52	510.63	942.15
9	170.0	9.01 14.129	11.68	0.00	0.17	2.69	0.85	1.00	0.00	18.67	80.92	0.00	3,481.5	0.0	384.77	450.15	834.93
10	185.0	9.23 7.341	5.01	0.00	0.20	2.59	0.85	1.00	0.00	9.12	23.45	0.00	1,285.2	0.0	185.14	129.67	314.81
													56.848.4	0.0	<u> </u>	-	9.374.80

Force/Stress Compression Summary

Structure: MA12227-A-SBA Code: TIA-222-G 10/26/2023

Site Name: Truro Exposure: В Crest Height: 0.00 Height: 190.00 (ft)

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III





Page: 13

			LEG MEMBERS									
Sect	Top Elev Member	Force (kips)	Load Case	Len (ft)	Bı X	acino	у % Z	KL/R	Fy (ksi)	Mem Cap (kips)	Leg Use %	Controls
1	20 SOL - 5 1/4" SOLID	-520.02	1.2D + 1.6W Normal Wind	6.68	100	100	100	61.03	50.00	741.89	70.1	Member X
2	40 SOL - 5 1/4" SOLID	-467.24	1.2D + 1.6W Normal Wind	6.68	100	100	100	61.03	50.00	741.89	63.0	Member X
3	60 SOL - 5" SOLID	-411.12	1.2D + 1.6W Normal Wind	6.68	100	100	100	64.09	50.00	654.37	62.8	Member X
4	80 SOL - 5" SOLID	-353.98	1.2D + 1.6W Normal Wind	6.68	100	100	100	64.09	50.00	654.38	54.1	Member X
5	100 SOL - 4 3/4" SOLID	-295.54	1.2D + 1.6W Normal Wind	6.68	100	100	100	67.46	50.00	571.73	51.7	Member X
6	120 SOL - 4 1/4" SOLID	-238.15	1.2D + 1.6W Normal Wind	5.01	100	100	100	56.55	50.00	505.28	47.1	Member X
7	140 SOL - 4" SOLID	-177.11	1.2D + 1.6W Normal Wind	5.01	100	100	100	60.08	50.00	434.30	40.8	Member X
8	160 SOL - 3 3/4" SOLID	-112.36	1.2D + 1.6W Normal Wind	5.01	100	100	100	64.09	50.00	368.10	30.5	Member X
9	180 SOL - 3 1/2" S0LID	-50.17	1.2D + 1.6W Normal Wind	5.01	100	100	100	68.66	50.00	306.70	16.4	Member X
10	190 SOL - 3" SOLID	-8.50	1.2D + 1.6W Normal Wind	3.34	100	100	100	53.40	50.00	258.23	3.3	Member X

Splices

			Top Splic	е					Bottom Sp	lice			
Sect	Top Elev	Load Case	Force (kips)	Cap (kips)	Use %	Bolt Type	Num Bolts	Load Case	Force (kips)	Cap (kips)	Use %	Bolt Type	Num Bolts
1	20	1.2D + 1.6W Normal Wind	475.69	0.00	0.0			1.2D + 1.6W Normal Wind	529.26	0.00			
2	40	1.2D + 1.6W Normal Wind	420.17	0.00	0.0			1.2D + 1.6W Normal Wind	475.69	0.00		1/2 A325	6
3	60	1.2D + 1.6W Normal Wind	363.22	0.00	0.0			1.2D + 1.6W Normal Wind	420.17	0.00		1/2 A325	6
4	80	1.2D + 1.6W Normal Wind	305.14	0.00	0.0			1.2D + 1.6W Normal Wind	363.22	0.00		1/2 A325	6
5	100	1.2D + 1.6W Normal Wind	245.41	0.00	0.0			1.2D + 1.6W Normal Wind	305.14	0.00		1/2 A325	6
6	120	1.2D + 1.6W Normal Wind	184.54	0.00	0.0			1.2D + 1.6W Normal Wind	245.41	0.00		3/8 A325	6
7	140	1.2D + 1.6W Normal Wind	120.57	0.00	0.0			1.2D + 1.6W Normal Wind	184.54	0.00		3/8 A325	6
8	160	1.2D + 1.6W Normal Wind	57.74	0.00	0.0			1.2D + 1.6W Normal Wind	120.57	0.00		3/8 A325	6
9	180	1.2D + 1.6W Normal Wind	10.58	0.00	0.0			1.2D + 1.6W Normal Wind	57.74	0.00		3/8 A325	6
10	190	1.2D + 1.0Di + 1.0Wi 90° Wind	0.57	0.00	0.0			1.2D + 1.6W Normal Wind	10.58	0.00		3/8 A325	6

				Н	ORIZO	NTA	L ME	MBE	RS								
Sect	Top Elev	Member	Force (kips)		Len (ft)	Br X	acinç Y	у % Z	KL/R	Fy (ksi)		Num Bolts		Shear Cap (kips)	Сар	Use %	Controls
1	20										0.00	0	0				
2	40										0.00	0	0				
3	60										0.00	0	0				
4	80										0.00	0	0				
5	100										0.00	0	0				
6	120										0.00	0	0				
7	140										0.00	0	0				
8	160										0.00	0	0				
9	180										0.00	0	0				
10	190	SAE - 2X2X0.1875	-0.28	0.9D + 1.6W Normal Wind	5.41	100	100	100	164.65	36.00	5.92	1	1	12.43	9.79	5	Member Z

					DIAGO	NAL I	MEMI	3ER	S								
Sect	Top Elev	Member	Force (kips)	Load Case	Len (ft)	Br X	acing Y	յ % Ζ	KL/R	Fy (ksi)		Num Bolts	Num Holes	Shear Cap (kips)	Сар		Controls
1	20	SAE - 4X4X0.25	-14.9	1.2D + 1.6W 90° Wind	23.18	49	49	49	171.44	36.00	14.91	1	1	24.35	17.4	101	Member Z
2	40	SAE - 4X4X0.25	-15.2	1.2D + 1.6W 90° Wind	21.46	48	48	48	155.49	36.00	18.13	1	1	24.35	17.4	88	Bolt Bear
3	60	SAE - 4X4X0.25	-14.5	1.2D + 1.6W 90° Wind	19.76	48	48	48	143.17	36.00	21.38	1	1	24.35	17.4	84	Bolt Bear
4	80	SAE - 3.5X3.5X0.25	-13.6	1.2D + 1.6W 90° Wind	18.08	48	48	48	150.02	36.00	16.96	1	1	24.35	17.4	80	Member Z
5	100	SAE - 3.5X3.5X0.25	-12.8	1.2D + 1.6W 90° Wind	16.42	48	48	48	136.26	36.00	20.56	1	1	24.35	17.4	74	Bolt Bear
6	120	SAE - 3X3X0.1875	-11.3	1.2D + 1.6W 90° Wind	14.19	48	48	48	137.10	36.00	13.10	1	1	24.35	13.0	87	Bolt Bear

Force/Stress Compression Summary

Structure: MA12227-A-SBA **Code:** TIA-222-G 10/26/2023

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III



	•	0.00		Topography.	- Oti	ucı	Olas		""				ı ay	C. 14			
					DIAGO	IAL I	ИЕМІ	BER	S								
Sect	Top Elev	Member	Force (kips)	Load Case	Len (ft)	Br X	acing Y	ј % Z	KL/R	Fy (ksi)		Num Bolts		Shear Cap (kips)	Сар		Controls
7	140	SAE - 2.5X2.5X0.25	-10.6	1.2D + 1.6W 90° Wind	12.52	47	47	47	143.77	36.00	13.01	1	1	24.35	17.4	82	Member Z
8	160	SAE - 2.5X2.5X0.1875	-9.05	1.2D + 1.6W 90° Wind	10.89	48	48	48	126.74	36.00	12.55	1	1	24.35	13.0	72	Member Z
9	180	SAE - 2.5X2.5X0.1875	-7.68	1.2D + 1.6W 90° Wind	9.33	47	47	47	109.72	36.00	15.51	1	1	24.35	13.0	59	Bolt Bear
10	190	SAE - 2X2X0.1875	-2.43	0.9D + 1.6W 90° Wind	7.00	46	46	46	103.53	36.00	13.08	1	1	12.43	9.79	25	Bolt Bear


Force/Stress Tension Summary

Structure: MA12227-A-SBA **Code**: TIA-222-G 10/26/2023

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III



Page: 15

Tower Engineering Solutions

LEG MEMBERS

						Mem		
	Тор		Force		Fy	Cap	Leg	
Sect	Elev	Member	(kips)	Load Case	(ksi)	(kips)	Use %	Controls
1	20	SOL - 5 1/4" SOLID	446.93	0.9D + 1.6W 60° Wind	50	974.16	45.9	Member
2	40	SOL - 5 1/4" SOLID	402.36	0.9D + 1.6W 60° Wind	50	974.16	41.3	Member
3	60	SOL - 5" SOLID	355.79	0.9D + 1.6W 60° Wind	50	883.58	40.3	Member
4	80	SOL - 5" SOLID	307.53	0.9D + 1.6W 60° Wind	50	883.58	34.8	Member
5	100	SOL - 4 3/4" SOLID	257.42	0.9D + 1.6W 60° Wind	50	797.45	32.3	Member
6	120	SOL - 4 1/4" SOLID	207.55	0.9D + 1.6W 60° Wind	50	638.37	32.5	Member
7	140	SOL - 4" SOLID	152.90	0.9D + 1.6W 60° Wind	50	565.47	27.0	Member
8	160	SOL - 3 3/4" SOLID	95.30	0.9D + 1.6W 60° Wind	50	497.03	19.2	Member
9	180	SOL - 3 1/2" S0LID	38.96	0.9D + 1.6W 60° Wind	50	432.95	9.0	Member
10	190	SOL - 3" SOLID	5.42	0.9D + 1.6W 60° Wind	50	318.11	1.7	Member

Splices

			Top Splic	се					Bottom Sp	lice			
Sect	Top Elev	Load Case	Force (kips)	Cap (kips)	Use %	Bolt Type	Num Bolts	Load Case	Force (kips)	•	Use %	Bolt Type	Num Bolts
1	20	0.9D + 1.6W 60° Wind	408.68	0.00	0.0			0.9D + 1.6W 60° Wind	455.3	0.00			
2	40	0.9D + 1.6W 60° Wind	362.28	0.00	0.0			0.9D + 1.6W 60° Wind	408.6	663.98	61.6	1 1/2 A32	25 6
3	60	0.9D + 1.6W 60° Wind	314.39	0.00	0.0			0.9D + 1.6W 60° Wind	362.2	663.98	54.6	1 1/2 A32	25 6
4	80	0.9D + 1.6W 60° Wind	264.77	0.00	0.0			0.9D + 1.6W 60° Wind	314.3	663.98	47.3	1 1/2 A32	25 6
5	100	0.9D + 1.6W 60° Wind	212.87	0.00	0.0			0.9D + 1.6W 60° Wind	264.7	663.98	39.9	1 1/2 A32	25 6
6	120	0.9D + 1.6W 60° Wind	159.08	0.00	0.0			0.9D + 1.6W 60° Wind	212.8	545.68	39.0	1 3/8 A32	25 6
7	140	0.9D + 1.6W 60° Wind	100.95	0.00	0.0			0.9D + 1.6W 60° Wind	159.0	545.68	29.2	1 3/8 A32	25 6
8	160	0.9D + 1.6W 60° Wind	45.57	0.00	0.0			0.9D + 1.6W 60° Wind	100.9	545.68	18.5	1 3/8 A32	25 6
9	180	0.9D + 1.6W 60° Wind	6.87	0.00	0.0			0.9D + 1.6W 60° Wind	45.57	545.68	8.4	1 3/8 A32	25 6
10	190		0.00	0.00	0.0			0.9D + 1.6W 60° Wind	6.87	545.68	1.3	1 3/8 A32	25 6

			HORIZON	NTAL MEM	BERS						
Sect	Top Elev	Member	Force (kips) Load Case	Fy (ksi)	Mem Cap (kips)	Num Bolts	Num Holes	Shear Cap (kips)	Bear Cap (kips)	B.S. Cap (kips)	Use % Controls
1	20	-		36	0.00	0	0				
2	40	-		36	0.00	0	0				
3	60	-		36	0.00	0	0				
4	80	-		36	0.00	0	0				
5	100	-		36	0.00	0	0				
6	120	-		36	0.00	0	0				
7	140	-		36	0.00	0	0				
8	160	-		36	0.00	0	0				
9	180	-		36	0.00	0	0				
10	190	SAE - 2X2X0.1875	0.30 1.2D + 1.6W 60° W	ind 36	18.58	1	1	12.43	9.79	7.50	4.0 Blck Shear

				DIAGONAL	МЕМЕ	BERS							
Sect	Top Elev	Member	Force (kips)	Load Case	Fy (ksi)	Mem Cap (kips)	Num Bolts	Num Holes	Shear Cap (kips)	Bear Cap (kips)	B.S. Cap (kips)	Use %	Controls
1	20	SAE - 4X4X0.25	15.40 0.9[O + 1.6W 90° Wind	36	55.14	1	1	24.35	17.40	16.95	90.8	Blck Shear
2	40	SAE - 4X4X0.25	15.12 0.9[D + 1.6W 90° Wind	36	55.14	1	1	24.35	17.40	16.95	89.2	Blck Shear
3	60	SAE - 4X4X0.25	14.37 1.2[O + 1.6W 90° Wind	36	55.14	1	1	24.35	17.40	16.95	84.8	Blck Shear
4	80	SAE - 3.5X3.5X0.25	13.50 1.20	O + 1.6W 90° Wind	36	46.98	1	1	24.35	17.40	16.95	79.7	Blck Shear
5	100	SAE - 3.5X3.5X0.25	12.70 1.20	O + 1.6W 90° Wind	36	46.98	1	1	24.35	17.40	16.95	74.9	Blck Shear
6	120	SAE - 3X3X0.1875	11.18 1.20	D + 1.6W 90° Wind	36	29.44	1	1	24.35	13.05	10.67	104.8	Blck Shear
7	140	SAE - 2.5X2.5X0.25	10.56 1.20	O + 1.6W 90° Wind	36	30.67	1	1	24.35	17.40	12.87	82.0	Blck Shear


Force/Stress Tension Summary

Structure: MA12227-A-SBA Code: TIA-222-G 10/26/2023

Site Name: Truro Exposure: В Height: 190.00 (ft) Crest Height: 0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Topography: 1 Struct Class: III Gh: 0.85





				DIAGONAL	МЕМЕ	BERS							
Sect	Top Elev	Member	Force (kips)	Load Case	Fy (ksi)	Mem Cap (kips)	Num Bolts	Num Holes	Shear Cap (kips)	Bear Cap (kips)	B.S. Cap (kips)	Use %	Controls
8	160	SAE - 2.5X2.5X0.1875	8.98 1.2D	+ 1.6W 90° Wind	36	23.31	1	1	24.35	13.05	9.65	93.1	Blck Shear
9	180	SAE - 2.5X2.5X0.1875	7.60 1.2D	+ 1.6W 90° Wind	36	23.31	1	1	24.35	13.05	9.65	78.7	Blck Shear
10	190	SAE - 2X2X0.1875	2.47 1.2D	+ 1.6W 90° Wind	36	18.58	1	1	12.43	9.79	7.50	32.9	Blck Shear

Seismic Section Forces

Structure: MA12227-A-SBA Code: TIA-222-G

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III



10/26/2023



Load Case: 1.2D + 1.0E

Ke 0.0000 **Dead Load Factor** 1.20 **Sds** 0.175 **Ss** 0.1640 **Fa** 1.6000 **Seismic Load Factor** 1.00 **Sd1** 0.091 **S1** 0.0570 **Fv** 2.4000 **Kg** 0.0000 Seismic Importance Factor **Vs** 6.4200 **f1** 1.6730 1.50 **SA** 0.152 **R** 3.0000

						Lateral
Sect #	Elev (ft)	Wz (lb)	а	b	С	Fsz (lb)
1	10.00	8357.3	0.01	0.05	0.03	40.62
2	30.00	8153.8	0.05	0.07	0.04	85.04
3	50.00	7540.8	0.13	0.07	0.03	125.09
4	70.00	7089.3	0.26	0.05	0.02	175.44
5	90.00	6526.1	0.42	0.01	0.01	217.16
6	110.00	5353.4	0.63	-0.06	0.02	221.27
7	130.00	6963.3	0.88	-0.12	0.08	366.26
8	150.00	5778.8	1.18	-0.02	0.24	445.72
9	170.00	10223.	1.51	0.53	0.56	1312.33
10	185.00	4115.2	1.79	1.50	0.96	785.73

Load Case: 0.9D + 1.0E **Dead Load Factor** 0.90 **Sds** 0.175 **Fa** 1.6000 **Ke** 0.0000 **Ss** 0.1640 **Seismic Load Factor** 1.00 **Sd1** 0.091 **S1** 0.0570 **Fv** 2.4000 **Kg** 0.0000 Seismic Importance Factor **Vs** 6.4200 **f1** 1.6730 1.50 **SA** 0.152 **R** 3.0000

						Lateral
Sect #	Elev (ft)	Wz (lb)	а	b	С	Fsz (lb)
1	10.00	8357.3	0.01	0.05	0.03	40.62
2	30.00	8153.8	0.05	0.07	0.04	85.04
3	50.00	7540.8	0.13	0.07	0.03	125.09
4	70.00	7089.3	0.26	0.05	0.02	175.44
5	90.00	6526.1	0.42	0.01	0.01	217.16
6	110.00	5353.4	0.63	-0.06	0.02	221.27
7	130.00	6963.3	0.88	-0.12	0.08	366.26
8	150.00	5778.8	1.18	-0.02	0.24	445.72
9	170.00	10223.	1.51	0.53	0.56	1312.33
10	185.00	4115.2	1.79	1.50	0.96	785.73


Support Forces Summary

Structure: MA12227-A-SBA **Code**: TIA-222-G 10/26/2023

Site Name:TruroExposure:BHeight:190.00 (ft)Crest Height:0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III



Gn:	0.85	ropography:	3	truct Clas	55. III	Page: 18
Load	d Case	Node	FX (kips)	FY (kips)	FZ (kips)	(-) = Uplift (+) = Down
1.2D + 1.6	W Normal Wind	1	0.00	528.19	-51.05	
		1a	16.85	-222.03	-18.15	
		1b	-16.85	-222.03	-18.15	
1.2D + 1.6	W 60° Wind	1	-6.35	265.25	-24.78	
		1a	-24.64	265.25	6.90	
		1b	-39.62	-446.38	-22.88	
120 + 16		 1	-7.69	28.04	 -1.47	
1.20 + 1.0	VV 90 VVIIIU	1a	-38.56	444.47	18.03	
		1b	-36.73	-388.39	-16.56	
0.9D + 1.6	W Normal Wind	1	0.00	520.70	-50.67	
		1a	17.17	-228.80	-18.34	
		1b	-17.17	-228.80	-18.34	
0.9D + 1.6	W 60° Wind	1	-6.36	258.01	-24.40	
		1a	-24.31	258.01	6.70	
		1b	-39.94	-452.93	-23.06	
0.9D + 1.6	W 90° Wind	1	-7.70	21.03	-1.09	
		1a	-38.23	437.06	17.83	
		1b	-37.05	-395.00	-16.74	
120 + 10	Di + 1.0Wi Normal Wind	1	0.00	168.29	-9.43	
1.20 1 1.0	Di i 1.000 Normai villu	1a	3.95	20.03	-3.85	
		1b	-3.95	20.03	-3.85	
	D' . 4 0\4" 000 \4" . I					
1.2D + 1.0	Di + 1.0Wi 60° Wind	1	-1.30	117.82	-4.38	
		1a	-4.44	117.81	1.06	
		1b	-8.68	-27.29	-5.01 	
1.2D + 1.0	Di + 1.0Wi 90° Wind	1	-1.53	69.45	0.41	
		1a	-7.25	153.68	3.32	
		1b	-8.00	-14.79	-3.73	
1.2D + 1.0	E	1	0.00	56.55	5.27	
		1a	7.42	13.79	-4.50	
		1b	-7.42	13.79	-4.50	
0.9D + 1.0	 F	1	0.00	49.51	5.66	
0.00 1.0	_	1a	7.76	6.79	-4.70	
		1b	-7.76	6.79	-4.70	
4.00 . 4.0	NA/ N.L L.NAC					
1.00 + 1.0'	W Normal Wind	1	0.00	97.08	-8.67	
		1a 1b	1.59 -1.59	-13.49 -13.49	-2.14 -2.14	
			-1.59	-13.49	-2.14	
1.0D + 1.0	W 60° Wind	1	-0.97	58.32	-4.73	
		1a	-4.58	58.32	1.53	
		1b	-4.92	-46.54	-2.84	
1.0D + 1.0	W 90° Wind	1	-1.15	23.37	-1.26	
		1a	-6.67	84.73	3.19	
		1b	-4.49	-38.00	-1.93	

	Le	∍g		Ov	erturning		
Max	Uplift: -	452.93	(kips)	Moment:	9745.70	(ft-kips)	
Max [Down:	528.19	(kips)	Total Down:	84.12	(kips)	
Max S	Shear:	51.05	(kips)	Total Shear:	87.35	(kips)	

Analysis Summary

Structure: MA12227-A-SBA **Code:** TIA-222-G 10/26/2023

 Site Name:
 Truro
 Exposure:
 B

 Height:
 190.00 (ft)
 Crest Height:
 0.00

Base Elev: 0.000 (ft) Site Class: D - Stiff Soil

Gh: 0.85 Topography: 1 Struct Class: III Page: 20



Max Reactions

	Leg		Ove	erturning	
Max Uplift:	-452.93	(kips)	Moment:	9745.70	(ft-kips)
Max Down:	528.19	(kips)	Total Down:	84.12	(kips)
Max Shear:	51.05	(kips)	Total Shear:	87.35	(kips)

Anchor Bolts

Bolt Size (in.): 2.00 Number Bolts: 8

Yield Strength (Ksi): 50.00 Tensile Strength (Ksi): 65.00

Detail Type: D Length: 1.00

Interaction Ratio: 0.61

Max Usages

Max Leg: 70.1% (1.2D + 1.6W Normal Wind - Sect 1)
Max Diag: 104.8% (1.2D + 1.6W 90° Wind - Sect 6)
Max Horiz: 4.8% (0.9D + 1.6W Normal Wind - Sect 10)

Max Deflection, Twist and Sway

Load Case	(ft)	(ft)	Twist (deg)	Sway (deg)
0.9D + 1.0E - Normal To Face	140.00	0.0437	0.0016	0.0355
	155.00	0.0534	0.0018	0.0394
	165.00	0.0604	0.0018	0.0411
	175.00	0.0674	0.0018	0.0411
	186.67	0.0756	0.0018	0.0402
	190.00	0.0761	0.0000	0.0399
0.9D + 1.6W 115 mph Wind at 60° From Face	140.00	0.6489	-0.0217	0.4841
	155.00	0.7812	-0.0229	0.5191
	165.00	0.8728	-0.0234	0.5241
	175.00	0.9641	-0.0236	0.5258
	186.67	1.0697	-0.0230	0.5138
	190.00	1.0989	-0.0220	0.4947
0.9D + 1.6W 115 mph Wind at 90° From Face	140.00	0.6565	-0.0253	0.4894
	155.00	0.7903	-0.0267	0.5223
	165.00	0.8829	-0.0272	0.5286
	175.00	0.9750	-0.0275	0.5331
	186.67	1.0816	-0.0268	0.5188
	190.00	1.1109	-0.0255	0.4946
0.9D + 1.6W 115 mph Wind at Normal To Face	140.00	0.6795	0.0225	0.5032
	155.00	0.8172	0.0237	0.5392
	165.00	0.9122	0.0242	0.5440
	175.00	1.0071	0.0245	0.5460
	186.67	1.1168	0.0238	0.5336
	190.00	1.1470	0.0000	0.5287

1.0D + 1.0W 60 mph Wind at 60° From Face	140.00	0.0954	-0.0032	0.0709	
•	155.00	0.1149	-0.0034	0.0760	
	165.00	0.1283	-0.0034	0.0770	
	175.00	0.1417	-0.0035	0.0769	
	186.67	0.1572	-0.0034	0.0754	
	190.00	0.1615	-0.0032	0.0726	
1.0D + 1.0W 60 mph Wind at 90° From Face	140.00	0.0966	-0.0037	0.0718	
	155.00	0.1162	-0.0039	0.0767	
	165.00	0.1298	-0.0040	0.0776	
	175.00	0.1433	-0.0040	0.0782	
	186.67	0.1590	-0.0039	0.0761	
	190.00	0.1633	-0.0037	0.0725	
1.0D + 1.0W 60 mph Wind at Normal To Face	140.00	0.1000	0.0033	0.0739	
	155.00	0.1202	0.0035	0.0792	
	165.00	0.1342	0.0036	0.0797	
	175.00	0.1481	0.0036	0.0803	
	186.67	0.1642	0.0035	0.0783	
	190.00	0.1686	0.0000	0.0777	
1.2D + 1.0Di + 1.0Wi 50 mph Wind at 60° From Face	140.00	0.1324	-0.0043	0.0966	
	155.00	0.1586	-0.0046	0.1024	
	165.00	0.1766	-0.0046	0.1040	
	175.00	0.1946	-0.0047	0.1039	
	186.67	0.2154	-0.0046	0.1018	
	190.00	0.2204	-0.0044	0.0985	
1.2D + 1.0Di + 1.0Wi 50 mph Wind at 90° From Face	140.00	0.1329	-0.0050	0.0970	
1.25 · 1.051 · 1.071 00 mph 77md at 00 · 110m1 acc	155.00	0.1592	-0.0053	0.1032	
	165.00	0.1773	-0.0054	0.1043	
	175.00	0.1953	-0.0054	0.1046	
	186.67	0.2162	-0.0053	0.1021	
	190.00	0.2216	-0.0051	0.0978	
1.2D + 1.0Di + 1.0Wi 50 mph Wind at Normal From Face	140.00	0.1344	0.0044	0.0982	
	155.00	0.1611	0.0046	0.1048	
	165.00	0.1795	0.0047	0.1052	
	175.00	0.1978	0.0047	0.1060	
	186.67	0.2189	0.0046	0.1033	
	190.00	0.2239	0.0000	0.1028	
1.2D + 1.0E - Normal To Face	140.00	0.0437	0.0016	0.0356	
	155.00	0.0535	0.0018	0.0395	
	165.00	0.0604	0.0019	0.0412	
	175.00	0.0675	0.0019	0.0412	
	186.67	0.0757	0.0018	0.0403	
	190.00	0.0762	0.0000	0.0399	
1.2D + 1.6W 115 mph Wind at 60° From Face	140.00	0.6496	-0.0217	0.4847	
	155.00	0.7822	-0.0229	0.5198	
	165.00	0.8739	-0.0234	0.5249	
	175.00	0.9653	-0.0236	0.5265	
	186.67	1.0711	-0.0230	0.5146	
	190.00	1.1004	-0.0220	0.4954	
1.2D + 1.6W 115 mph Wind at 90° From Face	140.00	0.6572	-0.0253	0.4902	
·	155.00	0.7913	-0.0267	0.5231	
	165.00	0.8840	-0.0273	0.5294	
	175.00	0.9763	-0.0276	0.5339	
	186.67	1.0830	-0.0268	0.5196	
	190.00	1.1124	-0.0256	0.4954	
4.00 - 4.014(445					
1.2D + 1.6W 115 mph Wind at Normal To Face	140.00	0.6804	0.0226	0.5040	
	155.00	0.8182	0.0237	0.5401	
	165.00	0.9134	0.0242	0.5447	
	175.00	1.0083	0.0245	0.5468	
	186.67	1.1182	0.0238	0.5344	
	190.00	1.1485	0.0000	0.5295	



Mot Foundat	ion Docian for Solf Sunna	rting Tower	Date
Wat Foundat	ion Design for Self Suppo	rung rower	10/26/2023
Customer Name:	SBA Communications Corp	TIA Standard:	TIA-222-G
Site Name:		Structure Height (Ft.):	190
Site Nmber:	MA12227-A-SBA	Engineer Name:	S. Shrestha
Engr. Number:	143003	Engineer Login ID:	

Foundation Info Obtained from:

Analysis or Design?

Number of Tower Legs:

Base Reactions (Factored):

(1). Individual Leg:

Axial Load (Kips):

Shear Force (Kips):

(2). Tower Base:

Total Vertical Load (Kips):

Moment (Kips-ft):

84.1 9745.7

528.2

51.1

Leg distance (Center-to-Center ft.): Round Diameter of Pier (ft.):

Tower center to mat center (ft):

Length of Pad (ft.):

Thickness of Pad (ft):

Mapping Operation

Analysis

3 Legs

Uplift Force (Kips):

453.0

Total Shear Force (Kips):

87.4

Foundation Geometries:

22.5 14.0 0 38

4.50

Mods required -Yes/No ?: No Pier Height A. G. (ft.): 0.00 Depth of Base BG (ft.): 4.5 38

Width of Pad (ft.):

14' 0.00 #DIV/0! 0 24.5' 0 4.5' 10 10 4.5 # 66 # 66 10 10

6.495

0.00

12.990

19.486

38'

(L)

19.0

Mat Center

6.01

12.505

22.5

Material Properties and Reabr Info:

Concrete Strength (psi): 3000 Steel Elastic Modulus: Vertical bar yield (ksi) Tie steel yield (ksi): Vertical Rebar Size #: Tie / Stirrup Size #: Tie Spacing (in): Qty. of Vertical Rebars: Pad Rebar Yield (Ksi): 60 Pad Steel Rebar Size (#): Concrete Cover (in.): 3 Unit Weight of Concrete:

Rebar at the bottom of the concrete pad:

Rebar at the top of the concrete pad:

Qty. of Rebar in Pad (L):

Qty. of Rebar in Pad (L):

Qty. of Rebar in Pad (W):

66

Qty. of Rebar in Pad (W):

54

50.0

29000

10

150.0

ksi

pcf

(W)

38'



Soil Unit Weight (pcf): Water Table B.G.S. (ft): Ultimate Bearing Pressure (psf): Consider Soil Lateral Resistance? 125.0 24.5 4000

No

38.0


66

54

Soil Buoyant Weight: Unit Weight of Water:

62.4 Consider ties in concrete shear strength:

Pcf pcf No (W) 38



Angle from Top of Pad: Final Length of pad (ft)

0 Angle from Bottm of Pad:

Final width of pad (ft):

0 38.0

Angle from Bottm of Pad:

0

Allowable overstress %:		TES Engr. Number:	143003		Page 2/2 Date:	10/26/2023	3	
Apply 1.35 for e/w per G/H:	1.35							
Foundation Analysis and [Design:	Uplift Strength Reduction Factor:	0.75	Comp	ression Strength Reduction Factor:	0.75		
Total Dry Soil Volume ((cu. Ft.):		0.00	Total	Dry Soil Weight (Kips):	0.00		
Total Buoyant Soil Volu	ıme (cu.	Ft.):	0.00	Total	Buoyant Soil Weight (Kips):	0.00		
Total Effective Soil We	ight (Kips):	0.00	Weigh	nt from the Concrete Block at Top (K):	0.00		
Total Dry Concrete Vol	ume (cu.	Ft.):	6500.31	Total	Dry Concrete Weight (Kips):	975.05		
Total Buoyant Concret	e Volume	e (cu. Ft.):	0.00	Total	Buoyant Concrete Weight (Kips):	0.00		
Total Effective Concret	e Weight	(Kips):	975.05	Total	Vertical Load on Base (Kips):	1059.17		
Check Soil Capacities:							Load/ Capacity Ratio	
Calculated Maxium Net So	il Pressur	e under the base (psf):	2041.78	<	Allowable Factored Soil Bearing (psf):	3000	0.68	OK!
Allowable Foundation Ove	rturning	Resistance (kips-ft.):	18271.6	>	Design Factored Momont (kips-ft):	10139	0.55	OK!
Factor of Safety Against Ov	erturnin _i	g (O. R. Moment/Design Moment):	1.80	OK!				
Check the capacities of Re	inforcein	g Concrete:						
Strength reduction factor (Flexure a	nd axial tension):	0.90	Stren	gth reduction factor (Shear):	0.75		
Strength reduction factor (Axial con	npresion):	0.65	Wind	Load Factor on Concrete Design:	1.00		
							Load/	
(2).Concrete Pad:								
•	-	r Capacity (L or W Direction, Kips):	1887.3	>	One-Way Factored Shear (L/W-Dir Kip	•	0.15	OK!
•	-	r Capacity (Diagonal Dir., Kips):	947.5	>	One-Way Factored Shear (Dia. Dir, Kip		0.25	OK!
		orcement Ratio (L or W-Direct.):	0.0036		Lower Steel Reinf. Ratio (Dia. Dir.):	0.0040		
Lower Steel F	Pad Mom	ent Capacity (L or W-Dir. Kips-ft):	18185.3	>	Moment at Bottom (L-Direct. K-Ft):	1451.9	0.08	OK!
Lower Steel F	Pad Mom	ent Capacity (Dia. Direction,K-ft):	14992.1	>	Moment at Bottom (Dia. Dir. K-Ft):	1378.8	0.09	OK!
Upper Steel I	Pad Reinf	orcement Ratio (L or W -Direction):	0.0030		Upper Steel Reinf. Ratio (Dia. Dir.):	0.0033		
Upper Steel I	Pad Mom	ent Capacity (L or W-Dir., Kips-ft):	15000.2	>	Moment at the top (L-Dir Kips-Ft):	754.4	0.05	OK!
Upper Steel I	Pad Mom	ent Capacity (Dia. Direction, K-ft):	12376.1	>	Moment at the top (Dia. Dir., K-Ft):	500.4	0.04	OK!
Punching Fai	lure Capa	icity (Kips):	4230.0	>	Punch. Failure Factored Shear (K):	528.2	0.12	OK!
-1								

Rebar Info Assu

Concrete Strength (Psi): 3000 Vertical bar yield (ksi) 0 Pad Rebar Yield (Ksi):

Vertical Rebar Size #: 0 Vertical Rebar Area (sq. in./each): #N/A Min. Qty. of Vertical Rebars:

Pad Steel Rebar Size (#): 10 Vertical Rebar Area (sq. in./each): 1.27

Min. Qty. of Rebars in L-Direction: #DIV/0! Min. Qty. of Rebars in W-Direction: #DIV/0!

Reinforce Concrete Pad by enlarging the size of pier (Yes/No):

No

60

#N/A



November 7, 2023

Catherine Ware SBA Network Services, LLC. 101 Interchange Plaza, Suite 103 Cranbury, NJ 08512 (917) 868-8365 B+T Group 1717 S. Boulder, Suite 300 Tulsa, OK 74119 (918) 587-4630 btwo@btgrp.com

Subject: Appurtenance Mount Analysis Report

Carrier Designation: Dish Wireless Co-Locate

Site Number: BOBOS00593A

Site Name: N/A

SBA Network Services Designation: Site Number: MA12227-A

Site Name: Truro
Application Number: 163468, v1

Engineering Firm Designation: B+T Group Project Number: 149562.005.01.0001

Site Data: 5 Town Dump Road, Truro, MA, 02666, Barnstable County

Latitude 41.98578°, Longitude -70.04133°

Self-Support Tower (3) 8 ft. Sector Mount

Dear Catherine Ware,

B+T Group is pleased to submit this "**Appurtenance Mount Analysis Report**" to determine the structural integrity of the antenna mount on the above-mentioned structure.

The purpose of the analysis is to determine the acceptability of the mount's stress level. Based on our analysis we have determined the stress level for the mount under the following load case to be:

Proposed Equipment

Note: See Table 1 for the final loading configuration

Sufficient Capacity (Passing at 49.3%)

The analysis has been performed in accordance with the ANSI/TIA-222-G standard and 2015 IBC as amended by the Massachusetts State Building Code, Ninth Edition, based upon an ultimate 3-second gust wind speed of 149 mph converted to a nominal 3-second gust wind speed of 115 mph per section 1609.3.1 as required for use in the ANSI/TIA-222-G Standard per Exception #5 of Section 1609.1.1. Exposure Category B and Risk Category III were used in this analysis.

All the equipment proposed in this report shall be installed in accordance with the drawings for the determined available structural capacity to be effective.

We at *B+T Group* appreciate the opportunity of providing our continuing professional services to you and *SBA Network Services*, *LLC*. If you have any questions or need further assistance on this or any other projects, please give us a call.

Mount structural analysis prepared by: Joseph Variamparampil

Respectfully submitted by: B&T Engineering, Inc.




TABLE OF CONTENTS

1) INTRODUCTION

2) ANALYSIS CRITERIA

Table 1 - Proposed Equipment Information Table 2 - Documents Provided

3) ANALYSIS PROCEDURE

- 3.1) Analysis Method
- 3.2) Assumptions

4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity

5) RECOMMENDATIONS

6) APPENDIX A

RISA-3D Output

7) APPENDIX B

Additional Calculations

1) INTRODUCTION

The appurtenance mount consists of Commscope sector mount Part# MTC3975083 at 155 ft., attached to self-support tower at 5 Town Dump Road, Truro, MA, 02666, Barnstable County. The proposed antenna loading information was obtained from SBA Network Services, LLC. All information provided to B+T Group was assumed accurate and complete.

2) ANALYSIS CRITERIA

The structural analysis was performed for this mount in accordance with the ANSI/TIA-222-G-2-2005 Structural Standard for Antenna Supporting Structures and Antennas – Addendum 2 using a 3-second gust wind speed of 115 mph with no ice and 50 mph with 0.75 inch escalated ice thickness Exposure category B & Topographic Category 1 and Risk Category III were used in the analysis. In addition, the sector mount has been analyzed for various live loading conditions consisting of a 250-lb man live load applied individually at the midpoint and cantilevered ends of horizontal members as well as a 500-pound man live load applied individually at mount pipe locations using a 3-second gust of 30mph. The mount was analyzed under 30° increments in the wind direction. The analyzed loading is detailed in Table 1.

Table 1 – Proposed Equipment Information

Loading	RAD Center Elev. (ft.)	Position	Qty.	Description	Note
			3	JMA Wireless MX08FRO665-21	1
Dropood	155	1	3	Fujitsu TA08025-B605	2
Proposed	155		3	Fujitsu TA08025-B604	
		-	1	Raycap RDIDC-9181-PF-48	3

Note:

- 1) Proposed Antenna to be installed on the Proposed Mount Pipe.
- 2) Proposed Equipment to be installed directly behind the Antenna
- 3) Proposed Equipment to be installed on Mount.

Table 2 - Documents Provided

Documents	Remarks	Reference	Source
SBA Application	Dropood Loading	Date: 06/28/2021	SBA Network Services, LLC.
RFDS	Proposed Loading	Date: 05/27/2021	SBA Network Services, LLC.
Mount Analysis	B+T Group	Date: 07/23/2021	On File

3) ANALYSIS PROCEDURE

3.1) Analysis Method

RISA-3D (Version 21.0.1), a commercially available analysis software package, was used to create a three-dimensional model of the mount and calculate member stresses and deflections for various loading cases. Selected output from the analysis is included in Appendix A.

Manufacturer's drawings were used to create the model.

3.2) Assumptions

- 1. The mount was built in accordance with the manufacturer's specifications.
- 2. The mount has been maintained in accordance with the manufacturer's specifications and is free of damage.
- 3. The configuration of antennas and other appurtenances are as specified in Table 1.
- 4. All mount components have been assumed to be in sufficient condition to carry their full design capacity for the analysis.

- 5. Mount areas and weights are determined from field measurements, standard material properties, and/or manufacturer product data.
- 6. Serviceability with respect to antenna twist, tilt, roll or lateral translation is not checked and is left to the carrier or tower owner to ensure conformance.
- 7. All prior structural modifications, if any are assumed to be correctly installed and fully effective.
- 8. All member connections are assumed to have been designed to meet or exceed the load carrying capacity of the connected member unless otherwise specified in this report.
- 9. The following material grades were assumed (Unless Noted Otherwise):

a) Connection Bolts : ASTM A325

b) Steel Pipe : ASTM A53 (GR. 35) c) HSS (Round) : ASTM 500 (GR. B-42) d) HSS (Rectangular) : ASTM 500 (GR. B-46) e) Channel : ASTM A36 (GR. 36) : ASTM A36 (GR. 36) Steel Solid Rod g) Steel Plate : ASTM A36 (GR. 36) h) Steel Angle : ASTM A36 (GR. 36) UNISTRUT : ASTM A570 (GR. 33)

This analysis may be affected if any assumptions are not valid or have been made in error. B+T Group should be notified to determine the effect on the structural integrity of the antenna mounting system.

4) ANALYSIS RESULTS

Table 3 - Mount Component Stresses vs. Capacity

Notes	Component	Elevation (ft.)	% Capacity	Pass / Fail
-	Face Horizontals	155	26.1	Pass
-	Support Arms	155	30.7	Pass
-	Diagonals	155	49.3	Pass
-	Connection Plates	155	25.6	Pass
-	Verticals	155	47.7	Pass
-	Tiebacks	155	29.8	Pass
-	Mount Pipes	155	29.2	Pass


5) RECOMMENDATIONS

The Commscope sector mount Part# MTC3975083 has sufficient capacity to carry the proposed loads and is in compliance with the ANSI/TIA-222-G standard for the proposed loading. (Refer to the RISA output for the specific members).

APPENDIX A

(RISA-3D Output)





Envelope Only Solution


EDIC A
IIKISA
A NEMETSCHEK COMPANY

	B+T Group
Y	MSP
	149562.005.01.0001

MA12227-A - Truro

SK-1
Oct 27, 2023 at 05:13 PM
149562_005_01_0001_Truro






Envelope Only Solution

IIRISA	B+T Group	MA12227-A - Truro	SK-2
A NEMETSCHEK COMPANY	MSP		Oct 27, 2023 at 05:13 PM
	149562.005.01.0001		149562_005_01_0001_Truro






Envelope Only Solution

IIRISA	B+T Group	MA12227-A - Truro	SK-3
A NEMETSCHEK COMPANY	MSP		Oct 27, 2023 at 05:14 PM
	149562.005.01.0001		149562_005_01_0001_Truro





Loads: BLC 1, Dead Envelope Only Solution


IRISA
A NEMETSCHEK COMPANY

	B+T Group
Y	MSP
	149562.005.01.0001

MA12227-A - Truro

SK-4 Oct 27, 2023 at 05:14 PM 149562_005_01_0001_Truro...





Loads: BLC 2, 0 Wind - No Ice Envelope Only Solution


IRISA A NEMETSCHEK COMPANY

9	B+T Group	
NY.	MSP	
	149562.005.01.0001	

MA12227-A - Truro

SK-5
Oct 27, 2023 at 05:14 PM
149562_005_01_0001_Truro






Loads: BLC 3, 90 Wind - No Ice Envelope Only Solution


IRISA
A NEMETSCHEK COMPANY

	B+T Group
Y	MSP
	149562.005.01.0001

MA12227-A - Truro

SK-6
Oct 27, 2023 at 05:14 PM
149562_005_01_0001_Truro







Company : B+T Group Designer : MSP Job Number : 149562.005.01.0001 Model Name: MA12227-A - Truro

10/27/2023 5:15:23 PM Checked By : ___

Node Coordinates

		\ -5:-		7.00	B + 1 E - 5: :
	Label	X [ft]	Y [ft]	Z [ft]	Detach From Diaphragm
1	1	-4	-2.354167	2.796875	
2	2	4	-2.354167	2.796875	
3	3	-4	0.145833	2.796875	
4	4	4	0.145833	2.796875	
5	5	0.467947	0	0.771833	
6	6	0.385368	0	0.677994	
7	7	2.091999	0	2.61733	
8	8	2.00942	0	2.523491	
9	9	2.332579	0	2.890714	
10	10	2.25	0.145833	2.796875	
11	11	2.25	0	2.796875	
12	12	0	0	0.24008	
13	13	-0.467947	0	0.771833	
14	14	-0.385368	0	0.677994	
15	15	-2.091999	0	2.61733	
16	16	-2.00942	0	2.523491	
17	17	-2.332579	0 145933	2.890714	
18 19	<u>18</u> 19	-2.25 -2.25	0.145833	2.796875 2.796875	
20	20	0.467947	-2.5		
	20	0.467947	-2.5 -2.5	0.771833	
21 22				0.677994	
23	22 23	2.091999	-2.5	2.61733	
24	23 24	2.00942 2.332579	-2.5 -2.5	2.523491 2.890714	
25	25	2.332379	-2.354167	2.796875	
26	26	2.25		2.796875	
27	27	0	-2.5 -2.5	0.24008	
28	28	-0.467947	-2.5	0.24008	
29	29	-0.385368	-2.5	0.677994	
30	30	-2.091999	-2.5	2.61733	
31	31	-2.00942	-2.5	2.523491	
32	32	-2.332579	-2.5	2.890714	
33	33	-2.25	-2.354167	2.796875	
34	34	-2.25	-2.5	2.796875	
35	35	0.430236	0	0.72898	
36	36	2.047131	-2.5	2.566344	
37	37	2.047131	0	2.566344	
38	38	0.430236	-2.5	0.72898	
39	39	-0.430236	0	0.72898	
40	40	-2.047131	-2.5	2.566344	
41	41	-2.047131	0	2.566344	
42	42	-0.430236	-2.5	0.72898	
43	43	0	0.145833	2.796875	
44	44	0	0.145833	3.078125	
45	45	0	-2.354167	2.796875	
46	46	0	-2.354167	3.078125	
47	47	0	2.895833	3.078125	
48	48	0	-5.104167	3.078125	
49	49	3.666667	0.145833	2.796875	
50	50	3.666667	0.145833	3.078125	
51	51	3.666667	-2.354167	2.796875	
52	52	3.666667	-2.354167	3.078125	
53	53	3.666667	2.895833	3.078125	
54	54	3.666667	-5.104167	3.078125	
55	55	-3.666667	0.145833	2.796875	



Company : B+T Group Designer : MSP Job Number : 149562.005.01.0001 Model Name: MA12227-A - Truro

10/27/2023 5:15:23 PM Checked By : ___

Node Coordinates (Continued)

	Label	X [ft]	Y [ft]	Z [ft]	Detach From Diaphragm
56	56	-3.666667	0.145833	3.078125	
57	57	-3.666667	-2.354167	2.796875	
58	58	-3.666667	-2.354167	3.078125	
59	59	-3.666667	2.895833	3.078125	
60	60	-3.666667	-5.104167	3.078125	
61	61	0	0	0	
62	62	-2.75	0.145833	2.796875	
63	63	-4.275	0.145833	-7.404517	
64	64	4.275	0	-7.404517	
65	65	-4.275	0	-7.404517	

Node Boundary Conditions

	Node Label	X [k/in]	Y [k/in]	Z [k/in]	X Rot [k-ft/rad]	Z Rot [k-ft/rad]
1	12	Reaction	Reaction	Reaction	Reaction	Reaction
2	27	Reaction	Reaction	Reaction	Reaction	Reaction
3	63	Reaction	Reaction	Reaction		

Hot Rolled Steel Properties

	Label	E [ksi]	G [ksi]	Nu	Therm. Coeff. [1e⁵°F⁻¹]	Density [k/ft³]	Yield [ksi]	Ry	Fu [ksi]	Rt
1	A992	29000	11154	0.3	0.65	0.49	50	1.1	65	1.1
2	A36 Gr.36	29000	11154	0.3	0.65	0.49	36	1.5	58	1.2
3	A572 Gr.50	29000	11154	0.3	0.65	0.49	50	1.1	65	1.1
4	A500 Gr.B RND	29000	11154	0.3	0.65	0.527	42	1.4	58	1.3
5	A500 Gr.B Rect	29000	11154	0.3	0.65	0.527	46	1.4	58	1.3
6	A53 Gr.B	29000	11154	0.3	0.65	0.49	35	1.6	60	1.2
7	A1085	29000	11154	0.3	0.65	0.49	50	1.4	65	1.3
8	A529 Gr.50	29000	11154	0.3	0.65	0.49	50	1.1	65	1.1
9	A500 Gr.42	29000	11154	0.3	0.65	0.49	42	1.4	58	1.3
10	A500 Gr.46	29000	11154	0.3	0.65	0.49	46	1.4	58	1.3
11	A500 Gr.C	29000	11154	0.3	0.65	0.49	46	1.4	62	1.3

Hot Rolled Steel Section Sets

	Label	Shape	Туре	Design List	Material	Design Rule	Area [in²]	lyy [in⁴]	Izz [in⁴]	J [in⁴]
1	MF-H1	HSS2.875X0.203	Beam	HSS Pipe	A500 Gr.C	Typical	1.59	1.45	1.45	2.89
2	MF- SA1	1.9"ODX0.12"	Beam	Pipe	A500 Gr.B RND	Typical	0.671	0.267	0.267	0.534
3	MF-D1	SR 1/2"	VBrace	BAR	A529 Gr.50	Typical	0.196	0.003	0.003	0.006
4	MF-CP1	PL5/8X3.5	Beam	RECT	A572 Gr.50	Typical	2.205	0.073	2.251	0.259
5	MF-V1	0.63"SR	Column	BAR	A529 Gr.50	Typical	0.312	0.008	0.008	0.015
6	MF-CP2	PL5/8X4.25	Beam	RECT	A572 Gr.50	Typical	2.656	0.086	3.998	0.314
7	Tieback	PIPE2.38X0.12	Beam	Pipe	A500 Gr.C	Typical	0.852	0.545	0.545	1.091
8	MF-P1	PIPE2.875X0.12	Column	Pipe	A500 Gr.C	Typical	1.039	0.987	0.987	1.975

Member Primary Data

	Label	l Node	J Node	Rotate(deg)	Section/Shape	Type	Design List	Material	Design Rule
1	1	1	2		MF-H1	Beam	HSS Pipe	A500 Gr.C	Typical
2	2	3	4		MF-H1	Beam	HSS Pipe	A500 Gr.C	Typical
3	3	12	5	90	MF-CP1	Beam	RECT	A572 Gr.50	Typical
4	4	6	7		MF- SA1	Beam	Pipe	A500 Gr.B RND	Typical
5	5	8	9	90	MF-CP2	Beam	RECT	A572 Gr.50	Typical
6	6	10	11	90	RIGID	None	None	RIGID	Typical



Company : B+T Group Designer : MSP Job Number : 149562.005.01.0001 Model Name: MA12227-A - Truro

10/27/2023 5:15:23 PM

Checked By : ___

Member Primary Data (Continued)

	Label	I Node	J Node	Rotate(deg)	Section/Shape	Туре	Design List	Material	Design Rule
7	7	12	13	90	MF-CP1	Beam	RECT	A572 Gr.50	Typical
8	8	14	15		MF- SA1	Beam	Pipe	A500 Gr.B RND	Typical
9	9	16	17	90	MF-CP2	Beam	RECT	A572 Gr.50	Typical
10	10	18	19	90	RIGID	None	None	RIGID	Typical
11	11	27	20	90	MF-CP1	Beam	RECT	A572 Gr.50	Typical
12	12	21	22		MF- SA1	Beam	Pipe	A500 Gr.B RND	Typical
13	13	23	24	90	MF-CP2	Beam	RECT	A572 Gr.50	Typical
14	14	25	26	90	RIGID	None	None	RIGID	Typical
15	15	27	28	90	MF-CP1	Beam	RECT	A572 Gr.50	Typical
16	16	29	30		MF- SA1	Beam	Pipe	A500 Gr.B RND	Typical
17	17	31	32	90	MF-CP2	Beam	RECT	A572 Gr.50	Typical
18	18	33	34	90	RIGID	None	None	RIGID	Typical
19	19	37	36		MF-V1	Column	BAR	A529 Gr.50	Typical
20	20	35	38		MF-V1	Column	BAR	A529 Gr.50	Typical
21	21	35	36		MF-D1	VBrace	BAR	A529 Gr.50	Typical
22	22	37	38		MF-D1	VBrace	BAR	A529 Gr.50	Typical
23	23	41	40		MF-V1	Column	BAR	A529 Gr.50	Typical
24	24	39	42		MF-V1	Column	BAR	A529 Gr.50	Typical
25	25	39	40		MF-D1	VBrace	BAR	A529 Gr.50	Typical
26	26	41	42		MF-D1	VBrace	BAR	A529 Gr.50	Typical
27	27	43	44	90	RIGID	None	None	RIGID	Typical
28	28	45	46	90	RIGID	None	None	RIGID	Typical
29	29	47	48		MF-P1	Column	Pipe	A500 Gr.C	Typical
30	30	49	50	90	RIGID	None	None	RIGID	Typical
31	31	51	52	90	RIGID	None	None	RIGID	Typical
32	32	53	54		MF-P1	Column	Pipe	A500 Gr.C	Typical
33	33	55	56	90	RIGID	None	None	RIGID	Typical
34	34	57	58	90	RIGID	None	None	RIGID	Typical
35	35	59	60		MF-P1	Column	Pipe	A500 Gr.C	Typical
36	36	62	63		Tieback	Beam	Pipe	A500 Gr.C	Typical

Member Advanced Data

	IIIDCI Advanced D					
	Label	I Release	T/C Only	Physical	Deflection Ratio Options	Seismic DR
1	1			Yes	N/A	None
2	2			Yes	N/A	None
3	3			Yes	N/A	None
4	4			Yes	N/A	None
5	5			Yes	N/A	None
6	6	0000X0		Yes	** NA **	None
7	7			Yes	N/A	None
8	8			Yes	N/A	None
9	9			Yes	N/A	None
10	10	0000X0		Yes	** NA **	None
11	11			Yes	N/A	None
12	12			Yes	N/A	None
13	13			Yes	N/A	None
14	14	0000X0		Yes	** NA **	None
15	15			Yes	N/A	None
16	16			Yes	N/A	None
17	17			Yes	N/A	None
18	18	0000X0		Yes	** NA **	None
19	19			Yes	** NA **	None
20	20			Yes	** NA **	None
21 22	21			Yes	** NA **	None
22	22		Euler Buckling	Yes	** NA **	None



10/27/2023 5:15:23 PM Checked By : __

Member Advanced Data (Continued)

	Label	l Release	T/C Only	Physical	Deflection Ratio Options	Seismic DR
23	23			Yes	** NA **	None
24	24			Yes	** NA **	None
25	25			Yes	** NA **	None
26	26		Euler Buckling	Yes	** NA **	None
27	27			Yes	** NA **	None
28	28			Yes	** NA **	None
29	29			Yes	** NA **	None
30	30			Yes	** NA **	None
31	31			Yes	** NA **	None
32	32			Yes	** NA **	None
33	33			Yes	** NA **	None
34	34			Yes	** NA **	None
35	35			Yes	** NA **	None
36	36	BenPIN		Yes	Default	None

Hot Rolled Steel Design Parameters

<u> </u>	Hot Noned Oteci Design Furdineters						
	Label	Shape	Length [ft]	Lcomp top [ft]	Channel Conn.	a [ft]	Function
1	1	MF-H1	8	Lbyy	N/A	N/A	Lateral
2	2	MF-H1	8	Lbyy	N/A	N/A	Lateral
3	3	MF-CP1	0.708	Lbyy	N/A	N/A	Lateral
4	4	MF- SA1	2.583	Lbyy	N/A	N/A	Lateral
5	5	MF-CP2	0.489	Lbyy	N/A	N/A	Lateral
6	7	MF-CP1	0.708	Lbyy	N/A	N/A	Lateral
7	8	MF- SA1	2.583	Lbyy	N/A	N/A	Lateral
8	9	MF-CP2	0.489	Lbyy	N/A	N/A	Lateral
9	11	MF-CP1	0.708	Lbyy	N/A	N/A	Lateral
10	12	MF- SA1	2.583	Lbyy	N/A	N/A	Lateral
11	13	MF-CP2	0.489	Lbyy	N/A	N/A	Lateral
12	15	MF-CP1	0.708	Lbyy	N/A	N/A	Lateral
13	16	MF- SA1	2.583	Lbyy	N/A	N/A	Lateral
14	17	MF-CP2	0.489	Lbyy	N/A	N/A	Lateral
15	19	MF-V1	2.5	Lbyy	N/A	N/A	Lateral
16	20	MF-V1	2.5	Lbyy	N/A	N/A	Lateral
17	21	MF-D1	3.499	Lbyy	N/A	N/A	Lateral
18	22	MF-D1	3.499	Lbyy	N/A	N/A	Lateral
19	23	MF-V1	2.5	Lbyy	N/A	N/A	Lateral
20	24	MF-V1	2.5	Lbyy	N/A	N/A	Lateral
21	25	MF-D1	3.499	Lbyy	N/A	N/A	Lateral
22	26	MF-D1	3.499	Lbyy	N/A	N/A	Lateral
23	29	MF-P1	8	Lbyy	N/A	N/A	Lateral
24	32	MF-P1	8	Lbyy	N/A	N/A	Lateral
25	35	MF-P1	8	Lbyy	N/A	N/A	Lateral
26	36	Tieback	10.315	Lbyy	N/A	N/A	Lateral

Member Point Loads (BLC 1 : Dead)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	Y	-0.032	%15
2	32	Υ	-0.032	%85
3	32	Υ	-0.075	%20
4	32	Υ	-0.064	%50
5	32	Υ	0	0
6	8	Y	-0.022	%50
7	8	Υ	0	0



10/27/2023 5:15:23 PM Checked By: __

Member Point Loads (BLC 1 : Dead) (Continued)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
8	8	Υ	0	0
9	8	Y	0	0
10	8	Y	0	0

Member Point Loads (BLC 2 : 0 Wind - No Ice)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	Z	-0.259	%15
2	32	Z	-0.259	%85
3	32	Z	-0.081	%20
4	32	Z	-0.081	%50
5	32	Z	0	0
6	8	Z	-0.083	%50
7	8	Z	0	0
8	8	Z	0	0
9	8	Z	0	0
10	8	Z	0	0

Member Point Loads (BLC 3 : 90 Wind - No Ice)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	Χ	-0.103	%15
2	32	Χ	-0.103	%85
3	32	Χ	-0.049	%20
4	32	Χ	-0.043	%50
5	32	Χ	0	0
6	8	Χ	-0.047	%50
7	8	Χ	0	0
8	8	Χ	0	0
9	8	X	0	0
10	8	X	0	0

Member Point Loads (BLC 4 : 0 Wind - Ice)

	Member Label	Direction	Magnitude [k, k-ft] -0.055	Location [(ft, %)]
1	32	Z	-0.055	%15
2	32	Z	-0.055	%85
3	32	Z	-0.022	%20
4	32	Z	-0.022	%50
5	32	Z	0	0
6	8	Z	-0.022	%50
7	8	Z	0	0
8	8	Z	0	0
9	8	Z	0	0
10	8	Z	0	0

Member Point Loads (BLC 5 : 90 Wind - Ice)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	X	-0.028	%15
2	32	X	-0.028	%85
3	32	X	-0.015	%20
4	32	X	-0.014	%50
5	32	X	0	0



Company : B+T Group

Designer : MSP
Job Number : 149562.005.01.0001
Model Name : MA12227-A - Truro

10/27/2023 5:15:23 PM Checked By : __

Member Point Loads (BLC 5 : 90 Wind - Ice) (Continued)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
6	8	Χ	-0.015	%50
7	8	X	0	0
8	8	X	0	0
9	8	X	0	0
10	8	X	0	0

Member Point Loads (BLC 6 : 0 Wind - Service)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	Z	-0.018	%15
2	32	Z	-0.018	%85
3	32	Z	-0.005	%20
4	32	Z	-0.005	%50
5	32	Z	0	0
6	8	Z	-0.006	%50
7	8	Z	0	0
8	8	Z	0	0
9	8	Z	0	0
10	8	Z	0	0

Member Point Loads (BLC 7 : 90 Wind - Service)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	X	-0.007	%15
2	32	X	-0.007	%85
3	32	X	-0.003	%20
4	32	Χ	-0.003	%50
5	32	X	0	0
6	8	Χ	-0.003	%50
7	8	Χ	0	0
8	8	Χ	0	0
9	8	X	0	0
10	8	X	0	0

Member Point Loads (BLC 8 : Ice)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	32	Υ	-0.19	%15
2	32	Υ	-0.19	%85
3	32	Υ	-0.069	%20
4	32	Υ	-0.067	%50
5	32	Υ	0	0
6	8	Υ	-0.07	%50
7	8	Υ	0	0
8	8	Υ	0	0
9	8	Υ	0	0
10	8	Υ	0	0

Member Point Loads (BLC 13 : Maint LL 1)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	8	Υ	-0.25	%50



Company : B+T Group Designer : MSP

Job Number : 149562.005.01.0001 Model Name : MA12227-A - Truro 10/27/2023 5:15:23 PM Checked By : ____

Member Point Loads (BLC 14 : Maint LL 2)

Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1 16	Υ	-0.25	%50

Member Point Loads (BLC 15 : Maint LL 3)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	4	Υ	-0.25	%50

Member Point Loads (BLC 16 : Maint LL 4)

Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]	
1 12	Υ	-0.25	%50	

Member Point Loads (BLC 17 : Maint LL 5)

	Member Label	Direction	Magnitude [k, k-ft]	Location [(ft, %)]
1	2	Υ	-0.25	%95

Member Point Loads (BLC 18 : Maint LL 6)

Member Label		Direction	Magnitude [k, k-ft]	, k-ft] Location [(ft, %)]	
1	1	Y	-0.25	%95	

Member Distributed Loads (BLC 2 : 0 Wind - No Ice)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
1	1	Z	-0.012	-0.012	0	%100
2	2	Z	-0.012	-0.012	0	%100
3	3	Z	-0.003	-0.003	0	%100
4	4	Z	-0.007	-0.007	0	%100
5	5	Z	-0.003	-0.003	0	%100
6	7	Z	-0.003	-0.003	0	%100
7	8	Z	-0.007	-0.007	0	%100
8	9	Z	-0.003	-0.003	0	%100
9	11	Z	-0.003	-0.003	0	%100
10	12	Z	-0.007	-0.007	0	%100
11	13	Z	-0.003	-0.003	0	%100
12	15	Z	-0.003	-0.003	0	%100
13	16	Z	-0.007	-0.007	0	%100
14	17	Z	-0.003	-0.003	0	%100
15	19	Z	-0.003	-0.003	0	%100
16	20	Z	-0.003	-0.003	0	%100
17	21	Z	-0.002	-0.002	0	%100
18	22	Z	-0.002	-0.002	0	%100
19	23	Z	-0.003	-0.003	0	%100
20	24	Z	-0.003	-0.003	0	%100
21	25	Z	-0.002	-0.002	0	%100
22	26	Z	-0.002	-0.002	0	%100
23	29	Z	-0.012	-0.012	0	%100
24	32	Z	-0.012	-0.012	0	%100
25 26	35	Z	-0.012	-0.012	0	%100
26	36	Z	-0.01	-0.01	0	%100



10/27/2023 5:15:23 PM Checked By : ___

Member Distributed Loads (BLC 3 : 90 Wind - No Ice)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
1	1	Χ	-0.012	-0.012	0	%100
2	2	Χ	-0.012	-0.012	0	%100
3	3	Χ	-0.003	-0.003	0	%100
4	4	Χ	-0.007	-0.007	0	%100
5	5	Χ	-0.003	-0.003	0	%100
6	7	Χ	-0.003	-0.003	0	%100
7	8	Χ	-0.007	-0.007	0	%100
8	9	Х	-0.003	-0.003	0	%100
9	11	Χ	-0.003	-0.003	0	%100
10	12	Χ	-0.007	-0.007	0	%100
11	13	Χ	-0.003	-0.003	0	%100
12	15	Χ	-0.003	-0.003	0	%100
13	16	Χ	-0.007	-0.007	0	%100
14	17	Χ	-0.003	-0.003	0	%100
15	19	Χ	-0.003	-0.003	0	%100
16	20	Х	-0.003	-0.003	0	%100
17	21	Χ	-0.002	-0.002	0	%100
18	22	Х	-0.002	-0.002	0	%100
19	23	Χ	-0.003	-0.003	0	%100
20	24	Χ	-0.003	-0.003	0	%100
21	25	Χ	-0.002	-0.002	0	%100
22	26	Χ	-0.002	-0.002	0	%100
23	29	Χ	-0.012	-0.012	0	%100
24	32	Χ	-0.012	-0.012	0	%100
25	35	Χ	-0.012	-0.012	0	%100
26	36	Χ	-0.01	-0.01	0	%100

Member Distributed Loads (BLC 4 : 0 Wind - Ice)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
1	1	Z	-0.003	-0.003	0	%100
2	2	Z	-0.003	-0.003	0	%100
3	3	Z	-0.007	-0.007	0	%100
4	4	Z	-0.002	-0.002	0	%100
5	5	Z	-0.007	-0.007	0	%100
6	7	Z	-0.007	-0.007	0	%100
7	8	Z	-0.002	-0.002	0	%100
8	9	Z	-0.007	-0.007	0	%100
9	11	Z	-0.007	-0.007	0	%100
10	12	Z	-0.002	-0.002	0	%100
11	13	Z	-0.007	-0.007	0	%100
12	15	Z	-0.007	-0.007	0	%100
13	16	Z	-0.002	-0.002	0	%100
14	17	Z	-0.007	-0.007	0	%100
15	19	Z	-0.003	-0.003	0	%100
16	20	Z	-0.003	-0.003	0	%100
17	21	Z	-0.001	-0.001	0	%100
18	22	Z	-0.001	-0.001	0	%100
19	23	Z	-0.003	-0.003	0	%100
20	24	Z	-0.003	-0.003	0	%100
21	25	Z	-0.001	-0.001	0	%100
22 23	26	Z	-0.001	-0.001	0	%100
23	29	Z	-0.003	-0.003	0	%100
24	32	Z	-0.003	-0.003	0	%100
25	35	Z	-0.003	-0.003	0	%100



Company : B+T Group Designer : MSP Job Number : 149562.005.01.0001

Model Name: MA12227-A - Truro

10/27/2023 5:15:23 PM Checked By : ___

Member Distributed Loads (BLC 4: 0 Wind - Ice) (Continued)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
26	36	Z	-0.002	-0.002	0	%100

Member Distributed Loads (BLC 5 : 90 Wind - Ice)

	Member Label Direction Start Magnitude [k/ft, F, ksf, k-ft/ft] End Magnitude [k/ft, F, ksf, k-ft/ft] Start Location [(ft, %)] End Location [(ft, %)]							
1	1	X	-0.003	-0.003	0	%100		
2	2	X	-0.003	-0.003	0	%100		
3	3	X	-0.007	-0.007	0	%100		
4	4	X	-0.002	-0.002	0	%100		
5	5	Х	-0.007	-0.007	0	%100		
6	7	Х	-0.007	-0.007	0	%100		
7	8	Х	-0.002	-0.002	0	%100		
8	9	Χ	-0.007	-0.007	0	%100		
9	11	Χ	-0.007	-0.007	0	%100		
10	12	Х	-0.002	-0.002	0	%100		
11	13	Х	-0.007	-0.007	0	%100		
12	15	Χ	-0.007	-0.007	0	%100		
13	16	Х	-0.002	-0.002	0	%100		
14	17	Х	-0.007	-0.007	0	%100		
15	19	X	-0.003	-0.003	0	%100		
16	20	X	-0.003	-0.003	0	%100		
17	21	X	-0.001	-0.001	0	%100		
18	22	Х	-0.001	-0.001	0	%100		
19	23	X	-0.003	-0.003	0	%100		
20	24	Х	-0.003	-0.003	0	%100		
21	25	X	-0.001	-0.001	0	%100		
22 23	26	X	-0.001	-0.001	0	%100		
23	29	Х	-0.003	-0.003	0	%100		
24 25	32	X	-0.003	-0.003	0	%100		
25	35	Х	-0.003	-0.003	0	%100		
26	36	Х	-0.002	-0.002	0	%100		

Member Distributed Loads (BLC 6 : 0 Wind - Service)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
1	1	Z	-0.0004	-0.0004	0	%100
2	2	Z	-0.0004	-0.0004	0	%100
3	3	Z	-0.0002	-0.0002	0	%100
4	4	Z	-0.0003	-0.0003	0	%100
5	5	Z	-0.0002	-0.0002	0	%100
6	7	Z	-0.0002	-0.0002	0	%100
7	8	Z	-0.0003	-0.0003	0	%100
8	9	Z	-0.0002	-0.0002	0	%100
9	11	Z	-0.0002	-0.0002	0	%100
10	12	Z	-0.0003	-0.0003	0	%100
11	13	Z	-0.0002	-0.0002	0	%100
12	15	Z	-0.0002	-0.0002	0	%100
13	16	Z	-0.0003	-0.0003	0	%100
14		Z	-0.0002	-0.0002	0	%100
15	19	Z	-0.0001	-0.0001	0	%100
16	20	Z	-0.0001	-0.0001	0	%100
17	21	Z	-0.0001	-0.0001	0	%100
18	22	Z	-0.0001	-0.0001	0	%100
19	23	Z	-0.0001	-0.0001	0	%100
20	24	Z	-0.0001	-0.0001	0	%100



10/27/2023 5:15:23 PM Checked By: ___

Member Distributed Loads (BLC 6 : 0 Wind - Service) (Continued)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
21	25	Z	-0.0001	-0.0001	0	%100
22	26	Z	-0.0001	-0.0001	0	%100
23	29	Z	-0.0004	-0.0004	0	%100
24	32	Z	-0.0004	-0.0004	0	%100
25	35	Z	-0.0004	-0.0004	0	%100
26	36	Z	-0.0003	-0.0003	0	%100

Member Distributed Loads (BLC 7 : 90 Wind - Service)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
1	1	Х	-0.0004	-0.0004	0	%100
2	2	Х	-0.0004	-0.0004	0	%100
3	3	X	-0.0002	-0.0002	0	%100
4	4	Х	-0.0003	-0.0003	0	%100
5	5	Х	-0.0002	-0.0002	0	%100
6	7	X	-0.0002	-0.0002	0	%100
7	8	X	-0.0003	-0.0003	0	%100
8	9	X	-0.0002	-0.0002	0	%100
9	11	X	-0.0002	-0.0002	0	%100
10	12	Х	-0.0003	-0.0003	0	%100
11	13	X	-0.0002	-0.0002	0	%100
12	15	X	-0.0002	-0.0002	0	%100
13	16	X	-0.0003	-0.0003	0	%100
14	17	Х	-0.0002	-0.0002	0	%100
15	19	X	-0.0001	-0.0001	0	%100
16	20	X	-0.0001	-0.0001	0	%100
17	21	X	-0.0001	-0.0001	0	%100
18	22	X	-0.0001	-0.0001	0	%100
19	23	Х	-0.0001	-0.0001	0	%100
20	24	X	-0.0001	-0.0001	0	%100
21	25	X	-0.0001	-0.0001	0	%100
22	26	X	-0.0001	-0.0001	0	%100
23	29	X	-0.0004	-0.0004	0	%100
24	32	X	-0.0004	-0.0004	0	%100
25	35	Х	-0.0004	-0.0004	0	%100
26	36	Х	-0.0003	-0.0003	0	%100

Member Distributed Loads (BLC 8 : Ice)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
1	1	Υ	-0.014	-0.014	0	%100
2	2	Υ	-0.014	-0.014	0	%100
3	3	Υ	-0.015	-0.015	0	%100
4	4	Υ	-0.011	-0.011	0	%100
5	5	Υ	-0.017	-0.017	0	%100
6	7	Υ	-0.015	-0.015	0	%100
7	8	Υ	-0.011	-0.011	0	%100
8	9	Υ	-0.017	-0.017	0	%100
9	11	Υ	-0.015	-0.015	0	%100
10	12	Υ	-0.011	-0.011	0	%100
11	13	Υ	-0.017	-0.017	0	%100
12	15	Υ	-0.015	-0.015	0	%100
13	16	Υ	-0.011	-0.011	0	%100
14	17	Υ	-0.017	-0.017	0	%100
15	19	Υ	-0.008	-0.008	0	%100



10/27/2023 5:15:23 PM

Checked By: __

Member Distributed Loads (BLC 8 : Ice) (Continued)

	Member Label	Direction	Start Magnitude [k/ft, F, ksf, k-ft/ft]	End Magnitude [k/ft, F, ksf, k-ft/ft]	Start Location [(ft, %)]	End Location [(ft, %)]
16	20	Υ	-0.008	-0.008	0	%100
17	21	Υ	-0.007	-0.007	0	%100
18	22	Υ	-0.007	-0.007	0	%100
19	23	Υ	-0.008	-0.008	0	%100
20	24	Υ	-0.008	-0.008	0	%100
21	25	Υ	-0.007	-0.007	0	%100
22	26	Υ	-0.007	-0.007	0	%100
23	29	Υ	-0.014	-0.014	0	%100
24	32	Υ	-0.014	-0.014	0	%100
25	35	Υ	-0.014	-0.014	0	%100
26	36	Υ	-0.012	-0.012	0	%100

Member Area Loads

No Data to Print...

Node Loads and Enforced Displacements (BLC 9 : Live Load a)

	Node Label	L, D, M	Direction	Magnitude [(k, k-ft), (in, rad), (k*s²/ft, k*s²*ft)]
1	57	L	Υ	-0.5

Node Loads and Enforced Displacements (BLC 10 : Live Load b)

	Node Label	L, D, M	Direction	Magnitude [(k, k-ft), (in, rad), (k*s²/ft, k*s²*ft)]
1	45		Y	-0.5

Node Loads and Enforced Displacements (BLC 11 : Live Load c)

	Node Label	L, D, M	Direction	Magnitude [(k, k-ft), (in, rad), (k*s²/ft, k*s²*ft)]
1	51		Y	-0.5

Basic Load Cases

	BLC Description	Category	Y Gravity	Nodal	Point	Distributed
1	Dead	DL	-1		10	
2	0 Wind - No Ice	WLZ			10	26
3	90 Wind - No Ice	WLX			10	26
4	0 Wind - Ice	WLZ			10	26
5	90 Wind - Ice	WLX			10	26
6	0 Wind - Service	WLZ			10	26
7	90 Wind - Service	WLX			10	26
8	Ice	OL1			10	26
9	Live Load a	LL		1		
10	Live Load b	LL		1		
11	Live Load c	LL		1		
12	Live Load d	LL				
13	Maint LL 1	LL			1	
14	Maint LL 2	LL			1	
15	Maint LL 3	LL			1	
16	Maint LL 4	LL			1	
17	Maint LL 5	LL			1	
18	Maint LL 6	LL			1	



10/27/2023 5:15:23 PM Checked By : ___

Load Combinations

Description Solve P-Delta BLC Factor BLC Fac											
Description Solve P-Delta BLC Factor BLC Factor BLC											
1	1.4 Dead	Yes	Υ	1	1.4						
2	0.9 D + 1.6 - 0 W	Yes	Y	1	0.9	2	1.6				
3	0.9 D + 1.6 - 30 W	Yes	Y	1	0.9	2	1.386	3	0.8		
4	0.9 D + 1.6 - 60 W	Yes	Ý	- i	0.9	3	1.386	2	0.8		
5	0.9 D + 1.6 - 90 W	Yes	Y	1	0.9	3	1.6		0.0		
6	0.9 D + 1.6 - 120 W	Yes	Y	1	0.9	3	1.386	2	-0.8		
7	0.9 D + 1.6 - 150 W	Yes	Y	1	0.9	2	-1.386	3	0.8		
8	0.9 D + 1.6 - 180 W	Yes	Y	1	0.9		-1.6	<u> </u>	0.0		
9	0.9 D + 1.6 - 180 W	Yes	Y	1	0.9	2	-1.386	3	-0.8		
10	0.9 D + 1.6 - 210 W	Yes	Y	1	0.9		-1.386	2	-0.8		
						3			-0.0		
11	0.9 D + 1.6 - 270 W	Yes	Y	1	0.9	3	-1.6	0	0.0		
12	0.9 D + 1.6 - 300 W	Yes	Y	1	0.9	3	-1.386	2	0.8		
13	0.9 D + 1.6 - 330 W	Yes	Y	1	0.9	2	1.386	3	-0.8		
14	1.2 D + 1.6 - 0 W	Yes	Y	1	1.2	2	1.6				
15	1.2 D + 1.6 - 30 W	Yes	Υ	1	1.2	2	1.386	3	0.8		
16	1.2 D + 1.6 - 60 W	Yes	Υ	1	1.2	3	1.386	2	0.8		
17	1.2 D + 1.6 - 90 W	Yes	Y	1	1.2	3	1.6				
18	1.2 D + 1.6 - 120 W	Yes	Υ	1	1.2	3	1.386	2	-0.8		
19	1.2 D + 1.6 - 150 W	Yes	Y	1	1.2	2	-1.386	3	0.8		
20	1.2 D + 1.6 - 180 W	Yes	Y	1	1.2	2	-1.6				
21	1.2 D + 1.6 - 210 W	Yes	Υ	1	1.2	2	-1.386	3	-0.8		
22	1.2 D + 1.6 - 240 W	Yes	Υ	1	1.2	3	-1.386	2	-0.8		
23	1.2 D + 1.6 - 270 W	Yes	Υ	1	1.2	3	-1.6				
24	1.2 D + 1.6 - 300 W	Yes	Y	1	1.2	3	-1.386	2	0.8		
25	1.2 D + 1.6 - 330 W	Yes	Υ	1	1.2	2	1.386	3	-0.8		
26	0.9 D + 1.6 - 0 W/Ice	Yes	Y	1	0.9	4	1.6			8	1
27	0.9 D + 1.6 - 30 W/Ice	Yes	Y	1	0.9	4	1.386	5	0.8	8	1
28	0.9 D + 1.6 - 60 W/Ice	Yes	Ý	. 1	0.9	5	1.386	4	0.8	8	1
29	0.9 D + 1.6 - 90 W/Ice	Yes	Y	1	0.9	5	1.6		0.0	8	1
30	0.9 D + 1.6 - 120 W/Ice	Yes	Y	1	0.9	5	1.386	4	-0.8	8	1
31	0.9 D + 1.6 - 150 W/Ice	Yes	Y	1	0.9	4	-1.386	5	0.8	8	1
32	0.9 D + 1.6 - 180 W/Ice	Yes	Y	1	0.9	4	-1.6	<u> </u>	0.0	8	1
33			Y	1				E	0.0		1
	0.9 D + 1.6 - 210 W/lce	Yes	Y		0.9	4	-1.386	5	-0.8	8	-
34	0.9 D + 1.6 - 240 W/Ice	Yes		1	0.9	5	-1.386	4	-0.8	8	1
35	0.9 D + 1.6 - 270 W/Ice	Yes	Y	1	0.9	5	-1.6	4	0.0	8	1
36	0.9 D + 1.6 - 300 W/Ice	Yes	Y	1	0.9	5	-1.386	4	0.8	8	1
37	0.9 D + 1.6 - 330 W/Ice	Yes	Y	1	0.9	4	1.386	5	-0.8	8	1
38	1.2 D + 1.0 - 0 W/Ice	Yes	Y	1	1.2	4	1			8	1
39	1.2 D + 1.0 - 30 W/Ice	Yes	Y	1	1.2	4	0.866	5	0.5	8	1
40	1.2 D + 1.0 - 60 W/Ice	Yes	Y	1	1.2	5	0.866	4	0.5	8	1
41	1.2 D + 1.0 - 90 W/Ice	Yes	Υ	1	1.2	5	1			8	1
42	1.2 D + 1.0 - 120 W/Ice	Yes	Y	1	1.2	5	0.866	4	-0.5	8	1
43	1.2 D + 1.0 - 150 W/Ice	Yes	Y	1	1.2	4	-0.866	5	0.5	8	1
44	1.2 D + 1.0 - 180 W/Ice	Yes	Y	11	1.2	4	-1			8	1
45	1.2 D + 1.0 - 210 W/Ice	Yes	Υ	1	1.2	4	-0.866	5	-0.5	8	1
46	1.2 D + 1.0 - 240 W/Ice	Yes	Υ	1	1.2	5	-0.866	4	-0.5	8	1
47	1.2 D + 1.0 - 270 W/Ice	Yes	Υ	1	1.2	5	-1			8	1
48	1.2 D + 1.0 - 300 W/lce	Yes	Y	1	1.2	5	-0.866	4	0.5	8	1
49	1.2 D + 1.0 - 330 W/Ice	Yes	Y	1	1.2	4	0.866	5	-0.5	8	1
50	1.2 D + 1.5 LL a + Service - 0 W	Yes	Ý		1.2	6	1		J.0	9	1.5
51	1.2 D + 1.5 LL a + Service - 30 W	Yes	Y	1	1.2	6	0.866	7	0.5	9	1.5
52	1.2 D + 1.5 LL a + Service - 60 W	Yes	Y	1	1.2	7	0.866	6	0.5	9	1.5
53	1.2 D + 1.5 LL a + Service - 90 W	Yes	Y	1	1.2	7	1	J	0.0	9	1.5
54	1.2 D + 1.5 LL a + Service - 90 W	Yes	Y	1	1.2	7	0.866	6	-0.5	9	1.5
55			Y	1				7			
55	1.2 D + 1.5 LL a + Service - 150 W	Yes	Y		1.2	6	-0.866	/	0.5	9	1.5



10/27/2023 5:15:23 PM

Checked By : ___

Load Combinations (Continued)

	Description	Solve	P-Delta	BLC	Factor	BLC	Factor	BLC	Factor	BLC	Factor
56	1.2 D + 1.5 LL a + Service - 180 W	Yes	Y	1	1.2	6	-1	DLO	1 dotoi	9	1.5
57	1.2 D + 1.5 LL a + Service - 210 W	Yes	Y	1	1.2	6	-0.866	7	-0.5	9	1.5
58	1.2 D + 1.5 LL a + Service - 240 W	Yes	Ý	1	1.2	7	-0.866	6	-0.5	9	1.5
59	1.2 D + 1.5 LL a + Service - 270 W	Yes	Y	1	1.2	7	-1		-0.0	9	1.5
60	1.2 D + 1.5 LL a + Service - 300 W	Yes	Y	1	1.2	7	-0.866	6	0.5	9	1.5
61	1.2 D + 1.5 LL a + Service - 330 W	Yes	Y	1	1.2	6	0.866	7	-0.5	9	1.5
62	1.2 D + 1.5 LL b + Service - 0 W	Yes	Y	1	1.2	6	1	- I	-0.0	10	1.5
63	1.2 D + 1.5 LL b + Service - 30 W	Yes	Y	1	1.2	6	0.866	7	0.5	10	1.5
64	1.2 D + 1.5 LL b + Service - 60 W	Yes	Ý	1	1.2	7	0.866	6	0.5	10	1.5
65	1.2 D + 1.5 LL b + Service - 90 W	Yes	Ϋ́	1	1.2	7	1		0.0	10	1.5
66	1.2 D + 1.5 LL b + Service - 120 W	Yes	Ý	1	1.2	7	0.866	6	-0.5	10	1.5
67	1.2 D + 1.5 LL b + Service - 150 W	Yes	Ϋ́	1	1.2	6	-0.866	7	0.5	10	1.5
68	1.2 D + 1.5 LL b + Service - 180 W	Yes	Ý	1	1.2	6	-1		0.0	10	1.5
69	1.2 D + 1.5 LL b + Service - 210 W	Yes	Ϋ́	1	1.2	6	-0.866	7	-0.5	10	1.5
70	1.2 D + 1.5 LL b + Service - 240 W	Yes	Y	1	1.2	7	-0.866	6	-0.5	10	1.5
71	1.2 D + 1.5 LL b + Service - 270 W	Yes	Y	1	1.2	7	-1		-0.0	10	1.5
72	1.2 D + 1.5 LL b + Service - 300 W	Yes	Ý	1	1.2	7	-0.866	6	0.5	10	1.5
73	1.2 D + 1.5 LL b + Service - 330 W	Yes	Y	1	1.2	6	0.866	7	-0.5	10	1.5
74	1.2 D + 1.5 LL c + Service - 0 W	Yes	Ý	1	1.2	6	1		-0.0	11	1.5
75	1.2 D + 1.5 LL c + Service - 30 W	Yes	Y	1	1.2	6	0.866	7	0.5	11	1.5
76	1.2 D + 1.5 LL c + Service - 60 W	Yes	Ý	1	1.2	7	0.866	6	0.5	11	1.5
77	1.2 D + 1.5 LL c + Service - 90 W	Yes	Y	1	1.2	7	1		0.0	11	1.5
78	1.2 D + 1.5 LL c + Service - 120 W	Yes	Ý	1	1.2	7	0.866	6	-0.5	11	1.5
79	1.2 D + 1.5 LL c + Service - 150 W	Yes	Y	1	1.2	6	-0.866	7	0.5	11	1.5
80	1.2 D + 1.5 LL c + Service - 180 W	Yes	Ý	1	1.2	6	-1	•	0.0	11	1.5
81	1.2 D + 1.5 LL c + Service - 210 W	Yes	Y	1	1.2	6	-0.866	7	-0.5	11	1.5
82	1.2 D + 1.5 LL c + Service - 240 W	Yes	Ý	1	1.2	7	-0.866	6	-0.5	11	1.5
83	1.2 D + 1.5 LL c + Service - 270 W	Yes	Y	1	1.2	7	-1		0.0	11	1.5
84	1.2 D + 1.5 LL c + Service - 300 W	Yes	Ý	1	1.2	7	-0.866	6	0.5	11	1.5
85	1.2 D + 1.5 LL c + Service - 330 W	Yes	Y	1	1.2	6	0.866	7	-0.5	11	1.5
86	1.2 D + 1.5 LL d + Service - 0 W	Yes	Y	1	1.2	6	1	•	0.0	12	1.5
87	1.2 D + 1.5 LL d + Service - 30 W	Yes	Y	1	1.2	6	0.866	7	0.5	12	1.5
88	1.2 D + 1.5 LL d + Service - 60 W	Yes	Y	1	1.2	7	0.866	6	0.5	12	1.5
89	1.2 D + 1.5 LL d + Service - 90 W	Yes	Y	1	1.2	7	1		0.0	12	1.5
90	1.2 D + 1.5 LL d + Service - 120 W	Yes	Y	1	1.2	7	0.866	6	-0.5	12	1.5
91	1.2 D + 1.5 LL d + Service - 150 W	Yes	Y	1	1.2	6	-0.866	7	0.5	12	1.5
92	1.2 D + 1.5 LL d + Service - 180 W	Yes	Y	1	1.2	6	-1	•	0.0	12	1.5
93	1.2 D + 1.5 LL d + Service - 210 W	Yes	Y	1	1.2	6	-0.866	7	-0.5	12	1.5
94	1.2 D + 1.5 LL d + Service - 240 W	Yes	Y	1	1.2	7	-0.866	6	-0.5	12	1.5
95	1.2 D + 1.5 LL d + Service - 270 W	Yes	Y	1	1.2	7	-1			12	1.5
96	1.2 D + 1.5 LL d + Service - 300 W	Yes	Ý	1	1.2	7	-0.866	6	0.5	12	1.5
97	1.2 D + 1.5 LL d + Service - 330 W	Yes	Y	1	1.2	6	0.866	7	-0.5	12	1.5
98	1.2 D + 1.5 LL Maint (1)	Yes	Ý	1	1.2		2.200			13	1.5
99	1.2 D + 1.5 LL Maint (1)	Yes	Y	1	1.2					14	1.5
100	1.2 D + 1.5 LL Maint (3)	Yes	Y	1	1.2					15	1.5
101	1.2 D + 1.5 LL Maint (4)	Yes	Y	1	1.2					16	1.5
102	1.2 D + 1.5 LL Maint (5)	Yes	Ý	1	1.2					17	1.5
103	1.2 D + 1.5 LL Maint (6)	Yes	Y	1	1.2					18	1.5

Envelope Node Reactions

١	Node Label		X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
0	12	max	0.706	53	1.145	42	2.702	13	-0.002	7	0	103	0.218	78
1		min	-1.291	83	0.171	12	-3.602	19	-0.333	49	0	1	-0.128	61
2	27	max	1.279	77	1.05	48	1.966	38	0.026	8	0	103	0.191	79
3		min	-0.694	59	0.152	6	-0.287	8	-0.308	38	0	1	-0.117	61



Company : B+T Group Designer : MSP Job Number : 149562.005.01.0001

Model Name: MA12227-A - Truro

10/27/2023 5:15:23 PM Checked By : ___

Envelope Node Reactions (Continued)

1	lode Label		X [k]	LC	Y [k]	LC	Z [k]	LC	MX [k-ft]	LC	MY [k-ft]	LC	MZ [k-ft]	LC
4	63	max	0.324	18	0.08	48	1.654	18	0	103	0	103	0	103
5		min	-0.325	24	0.013	7	-1.656	24	0	1	0	1	0	1
6	Totals:	max	1.701	17	2.251	48	2.369	2						
7		min	-1.701	11	0.46	6	-2.369	20						

Envelope AISC 13TH (360-05): LRFD Member Steel Code Checks

	Membe	r Shape C	Code Chec	kLoc[ft] LC S	Shear Che	ckLoc[ft][DirLC	phi*Pnc [k]	phi*Pnt [k]	phi*Mn y-y [k-ft]	phi*Mn z-z [k-f	t] Cb	Eqn
0	1	HSS2.875X0.203	0.172	6.25 20	0.096	6.25	20	33.355	65.826	4.727	4.727	1	H1-1b
1	2	HSS2.875X0.203	0.261	6.25 20	0.13	1.75	18	33.355	65.826	4.727	4.727	1	H1-1b
2	3	PL5/8X3.5	0.256	0 42	0.05	0.583	y 19	84.578	99.225	1.302	7.235	1.231	H1-1b
3	4	1.9"ODX0.12"	0.307	2.449 19	0.068	2.449	19	21.867	25.364	1.2	1.2	1	H1-1b
4	5	PL5/8X4.25	0.185	0.362 14	0.044	0.362	y 19	110.629	119.531	1.556	10.583	1.423	H1-1b
5	7	PL5/8X3.5	0.176	0 61	0.051	0.583	y 25	84.578	99.225	1.302	7.235	1.16	H1-1b
6	8	1.9"ODX0.12"	0.303	2.449 13	0.07	2.449	25	21.867	25.364	1.2	1.2	1	H1-1b
7	9	PL5/8X4.25	0.24	0.362 25	0.06	0.362	y 25	110.629	119.531	1.556	10.583	_	H1-1b
8	11	PL5/8X3.5	0.228	0 41	0.092	0.583	y 20	84.578	99.225	1.302	7.235	2.353	H1-1b
9	12	1.9"ODX0.12"	0.226	2.449 20	0.107	2.449	20	21.867	25.364	1.2	1.2	1	H1-1b
10	13	PL5/8X4.25	0.131	0.127 20	0.099	0.362	y 20	110.629	119.531	1.556	10.583	1.44	H1-1b
11	15	PL5/8X3.5	0.161	0 61	0.03	0	y 58	84.578	99.225	1.302	7.235	1.254	H1-1b
12	16	1.9"ODX0.12"	0.171	1.292 99	0.043	2.449	99	21.867	25.364	1.2	1.2	1	H1-1b
13	17	PL5/8X4.25	0.075	0.127 19	0.031	0.362	y 56	110.629	119.531	1.556	10.583	1.445	H1-1b
14	19	0.63"SR	0.466	2.5 41	0.004	2.5	18	1.941	14.028	0.147	0.147	1	H1-1a
15	20	0.63"SR	0.477	2.5 42	0.011	2.5	19	1.941	14.028	0.147	0.147	1	H1-1a
16	21	SR 1/2"	0.493	3.499 13	0.004	0	10	0.393	8.836	0.074	0.074	1	H1-1a
17	22	SR 1/2"	0	3.499 103	0.007	0	13	0.393	8.836	0.074	0.074	1	H1-1a
18	23	0.63"SR	0.329	0 25	0.017	0	18	1.941	14.028	0.147	0.147	1	H1-1a
19	24	0.63"SR	0.346	2.5 61	0.011	2.5	19	1.941	14.028	0.147	0.147	1	H1-1a
20	25	SR_1/2"	0.192	0 61	0.005	3.499	36	0.393	8.836	0.074	0.074	1	H1-1b*
21	26	SR 1/2"	0.024	3.499 6	0.017	0	19	0.393	8.836	0.074	0.074	1	H1-1b*
22	29	PIPE2.875X0.12	0.154	2.75 19	0.059	2.75	19	22.398	42.998	3.144	3.144	1	H1-1b
23	32	PIPE2.875X0.12	0.292	2.75 14	0.067	2.75	2	22.398	42.998	3.144	3.144	1	H1-1b
24	35	PIPE2.875X0.12	0.122	5.25 55	0.049	2.75	18	22.398	42.998	3.144	3.144	1	H1-1b
25	36	PIPE2.38X0.12	0.298	5.05 18	0.008	10.315	23	8.036	35.273	2.115	2.115	1	H1-1a

APPENDIX B

(Additional Calculations)



ASCE 7 Hazards Report


Address:


No Address at This Location

Standard: ASCE/SEI 7-10 Latitude: 41.985783
Risk Category: III Longitude: -70.041333

Soil Class: D - Stiff Soil **Elevation:** 29.375566586343556 ft

(NAVD 88)







Seismic


D - Stiff Soil

Site Soil Class:

Results:

S _S :	0.163	S _{D1} :	0.091
S ₁ :	0.057	T_L :	6
F _a :	1.6	PGA:	0.084
F _v :	2.4	PGA _M :	0.134
S _{MS} :	0.26	F _{PGA} :	1.6
S _{M1} :	0.137	l _e :	1.25
S _{DS} :	0.173		

Seismic Design Category: B



Data Accessed: Fri Oct 27 2023

Date Source:

USGS Seismic Design Maps based on ASCE/SEI 7-10, incorporating Supplement 1 and errata of March 31, 2013, and ASCE/SEI 7-10 Table 1.5-2. Additional data for site-specific ground motion procedures in accordance with ASCE/SEI 7-10 Ch. 21 are available from USGS.



lce

Results:

Ice Thickness: 0.75 in.

Concurrent Temperature: 15 F

Gust Speed 50 mph

Data Source: Standard ASCE/SEI 7-10, Figs. 10-2 through 10-8

Date Accessed: Fri Oct 27 2023

Ice thicknesses on structures in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

Values provided are equivalent radial ice thicknesses due to freezing rain with concurrent 3-second gust speeds, for a 50-year mean recurrence interval, and temperatures concurrent with ice thicknesses due to freezing rain. Thicknesses for ice accretions caused by other sources shall be obtained from local meteorological studies. Ice thicknesses in exposed locations at elevations higher than the surrounding terrain and in valleys and gorges may exceed the mapped values.

The ASCE 7 Hazard Tool is provided for your convenience, for informational purposes only, and is provided "as is" and without warranties of any kind. The location data included herein has been obtained from information developed, produced, and maintained by third party providers; or has been extrapolated from maps incorporated in the ASCE 7 standard. While ASCE has made every effort to use data obtained from reliable sources or methodologies, ASCE does not make any representations or warranties as to the accuracy, completeness, reliability, currency, or quality of any data provided herein. Any third-party links provided by this Tool should not be construed as an endorsement, affiliation, relationship, or sponsorship of such third-party content by or from ASCE.

ASCE does not intend, nor should anyone interpret, the results provided by this Tool to replace the sound judgment of a competent professional, having knowledge and experience in the appropriate field(s) of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the contents of this Tool or the ASCE 7 standard.

In using this Tool, you expressly assume all risks associated with your use. Under no circumstances shall ASCE or its officers, directors, employees, members, affiliates, or agents be liable to you or any other person for any direct, indirect, special, incidental, or consequential damages arising from or related to your use of, or reliance on, the Tool or any information obtained therein. To the fullest extent permitted by law, you agree to release and hold harmless ASCE from any and all liability of any nature arising out of or resulting from any use of data provided by the ASCE 7 Hazard Tool.

PROJECT	149562.00	5.01.0001 - Tru	ıro, M	A	KSC
SUBJECT	Sector- Mou	unt Analysis			
DATE	11/07/23	PAGE	1	OF	5



INPUT [REF: ANSI/TIA-222-G2005]

Tower Type : SST
Tower Height : 190 ft

Mount Elevation : 155 ft

Antenna Elevation : 155 ft

Crest Height : 0 ft

III Structure Class [Table 2-1] Exposure Category В [Sec. 2.6.5] Topography Category 1 [Sec. 2.6.6.2] Wind Velocity 115 [Annex B] mph Ice wind Velocity 50 mph [Annex B] Service Velocity 30 mph [Annex B] Base Ice thickness t_i : 0.75 in [Annex B]

ANTENNAS

	Manufacturer	Model	Height	Front	Side Width	Weight	Shape	Quantity	Locatio
			(in)	Width (in)	(in)	(lbs)			(%)
1ount	Pipe 32		•	•			•		
	JMA WIRELESS	MX08FRO665-21	72.00	20.00	8.00	64.50	Flat	0.5	15
	JMA WIRELESS	MX08FRO665-21	72.00	20.00	8.00	64.50	Flat	0.5	85
	Fujitsu	TA08025-B605	15.75	14.96	9.05	74.95	Flat	1	20
	Fujitsu	TA08025-B604	15.75	14.96	7.87	63.93	Flat	1	50
Mount									
	RAYCAP	RDIDC-9181-PF-48	16.57	14.57	8.15	21.85	Flat	1	50
1ount	Pipe								
				+					
Marint.	Diag								
Mount	Pipe								
Mount	Pipe								
Mount	Pipe								
Mount	Pipe								
Mount	Pipe								
Mount	Pipe								
Mount									
Mount	Pipe								
	Pipe								
Mount	Pipe								
Mount	Pipe								
Mount	Pipe								
Mount	Pipe								

dish wireless...

DISH Wireless L.L.C. SITE ID:

BOBOS00593A

DISH Wireless L.L.C. SITE ADDRESS:

5 TOWN DUMP ROAD TRURO, MA 02666

MASSACHUSETTS CODE COMPLIANCE

ALL WORK SHALL BE PERFORMED AND MATERIALS INSTALLED IN ACCORDANCE WITH THE CURRENT EDITIONS OF THE FOLLOWING CODES AS ADOPTED BY THE LOCAL GOVERNING AUTHORITIES. NOTHING IN THESE PLANS IS TO BE CONSTRUED TO PERMIT WORK NOT CONFORMING TO THESE CODES:

MECHANICAL

MA STATE BUILDING CODE, 9TH EDITION (780 CMR)/2015 IBC W/ AMENDMENTS MA STATE BUILDING CODE, 9TH EDITION (780 CMR)/2015 IMC W/ AMENDMENTS MA ELECTRICAL CODE/2020 NEC W/ AMENDMENTS

	SHEET INDEX
SHEET NO.	SHEET TITLE
T-1	TITLE SHEET
LS1	SITE SURVEY
A-1	OVERALL AND ENLARGED SITE PLAN
A-2	ELEVATION, ANTENNA LAYOUT AND SCHEDULE
A-3	EQUIPMENT PAD AND H-FRAME DETAILS
A-4	EQUIPMENT DETAILS
A-5	EQUIPMENT DETAILS
A-6	EQUIPMENT DETAILS
E-1	ELECTRICAL/FIBER ROUTE PLAN AND NOTES
E-2	ELECTRICAL DETAILS
E-3	ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE
G-1	GROUNDING PLANS AND NOTES
G-2	GROUNDING DETAILS
G-3	GROUNDING DETAILS
RF-1	RF CABLE COLOR CODE
GN-1	LEGEND AND ABBREVIATIONS
GN-2	GENERAL NOTES
GN-3	GENERAL NOTES
GN-4	GENERAL NOTES

SCOPE OF WORK

THIS IS NOT AN ALL INCLUSIVE LIST. CONTRACTOR SHALL UTILIZE SPECIFIED EQUIPMENT PART OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL VERIFY ALL NEEDED EQUIPMENT TO PROVIDE A FUNCTIONAL SITE. THE PROJECT GENERALLY CONSISTS OF THE FOLLOWING:

TOWER SCOPE OF WORK:

- INSTALL (3) PROPOSED PANEL ANTENNAS (1 PER SECTOR)
 INSTALL (3) PROPOSED ANTENNA MOUNTS (1 PER SECTOR)

- INSTALL (6) PROPOSED RRUS (2 PER SECTOR)
- INSTALL (1) PROPOSED OVER VOLTAGE PROTECTION DEVICE (OVP) INSTALL (1) PROPOSED HYBRID CABLE

- GROUND SCOPE OF WORK:

 INSTALL (1) PROPOSED CONCRETE PAD

 INSTALL (1) PROPOSED ICE BRIDGE
- PROPOSED PPC CABINET
-) PROPOSED FOUIPMENT CARINET INSTALL
- INSTALL (1) PROPOSED TELCO CONDUIT
- INSTALL (1) PROPOSED TELCO-FIBER BOX
- INSTALL (1) PROPOSED GPS UNIT INSTALL (1) PROPOSED FIBER NID (IF REQUIRED)

SITE PHOTO





UNDERGROUND SERVICE ALERT - 811 DIG SAFE UTILITY NOTIFICATION CENTER OF MASSACHUSETTS (888) 344-7233 WWW.DIGSAFE.COM

CALL 3 WORKING DAYS UTILITY NOTIFICATION PRIOR TO CONSTRUCTION

GENERAL NOTES

THE FACILITY IS UNMANNED AND NOT FOR HUMAN HABITATION. A TECHNICIAN WILL VISIT THE SITE AS REQUIRED FOR ROUTINE MAINTENANCE. THE PROJECT WILL NOT RESULT IN ANY SIGNIFICANT DISTURBANCE OR EFFECT ON DRAINAGE. NO SANITARY SEWER SERVICE, POTABLE WATER, OR TRASH DISPOSAL IS REQUIRED AND NO COMMERCIAL SIGNAGE IS PROPOSED.

11"x17" PLOT WILL BE HALF SCALE UNLESS OTHERWISE NOTED

CONTRACTOR SHALL VERIFY ALL PLANS, EXISTING DIMENSIONS, AND CONDITIONS ON THE JOB SITE, AND SHALL IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BEFORE PROCFEDING WITH THE WORK.


SITE INFORMATION PROJECT DIRECTORY PROPERTY OWNER: S B A TOWERS II LLC DISH Wireless L.L.C. TAX DEPT MA122227-A 5701 SOUTH SANTA FE DRIVE 8051 CONGRESS AVE LITTLETON, CO 80120 BOCA RATON, FL 33487 TOWER TYPE: SELF-SUPPORT TOWER TOWER OWNER: SBA COMMUNICATAIONS CORP. TOWER CO SITE ID: MA12227-A 8051 CONGRESS AVENUE BOCA RATON, FL 33487 TOWER APP NUMBER: 163468 (800) 487-7483 COUNTY: BARNSTABLE SITE DESIGNER: B+T GROUP 1717 S. BOULDER AVE, SUITE 300 LATITUDE (NAD 83): TULSA, OK 74119 41° 59' 8.82" N 41.985783 N (918) 587-4630 LONGITUDE (NAD 83): 70° 2' 28.8" W 70.041332 W SITE ACQUISITION: DAVID CAMPBELL ZONING JURISDICTION: TOWN OF TRURO DAVID.CAMPBELL@DISH.COM ZONING DISTRICT: SFO CONSTRUCTION MANAGER: AARON CHANDLER PARCEL NUMBER: 55-2-A AARON, CHANDLER ODISH, COM OCCUPANCY GROUP: RF ENGINEER: ARVIN SEBASTIAN ARVIN.SEBASTIAN@DISH.COM CONSTRUCTION TYPE: II-B POWER COMPANY:

DIRECTIONS

DIRECTIONS FROM PROVINCETOWN MUNICIPAL AIRPORT:

TELEPHONE COMPANY: COMCAST

HEAD EAST TOWARD PROVINCE LANDS BIKE TRAIL. TURN RIGHT ONTO RACE POINT RD. TURN LEFT ONTO US-6 W. TURN LEFT ONTO ACCESS RD AND ARRIVE AT BOBOSO0593A.





5701 SOUTH SANTA FF DRIVE LITTLETON, CO 80120



BOCA RATON, FL 33487





B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN	BY:	CHECKED	BY:	APPROVED	BY:
RMC		BLJ		MDW	

RFDS REV #:

PRELIMINARY DOCUMENTS

	SUBMITTALS					
REV	DATE	DESCRIPTION				
Α	7/28/21	ISSUED FOR REVIEW				
0	8/10/21	ISSUED FOR CONSTRUCTION				
	A&E F	PROJECT NUMBER				


149562.001.01


BOBOSO0593A 5 TOWN DUMP ROAD TRURO, MA 02666

> SHEET TITLE TITLE SHEET

SHEET NUMBER

T-1





I HEREBY CERIFY TO SBA TOWERS II, LLC, A FLORIDA LIMITED LIABILITY COMPANY AND FIRST AMERICAN TITLE INSURANCE COMPANY THE FOLLOWING:

I HAVE RECEIVED AND REVIEWED THAT CERTAIN TITLE COMMITMENT NO. 590012514-RJO ISSUED BY FIRST AMERICAN TITLE INSURANCE COMPANY WITH AN EFFECTIVE DATE OF NOVEMBER 11, 2009, WHICH PROFOSES TO INSURE THE LANDS DESCRIBED UNDER ITS SCHEDULE A.

TO THE BEST OF MY KNOWLEDGE AND BELIEF THE LANDS DESCRIBED UNDER SAID SCHEDULE A OF THE TITLE COMMITMENT CONTAIN OR INCLUDE THE LANDS DESCRIBED IN AND DEPICTED ON THIS SURVEY.

TO THE BEST OF MY KNOWLEDGE AND BELLIEF THE VISABLE BASEMENTS OF RECORD AND IDENTIFIED UNDER SCHEDULE B-2 OF SAID COMMITMENT ENCUMBER THE LANDS DESCRIBED ON THIS SURVEY, BUT SAID BASEMENTS WILL NOT INTERFERE WITH THE LOCATION OF THE PROFOSED ISSURED LANDS, INCLUDING THE LEASED AREA AND ANY AND ALL ACCESS, UTILITY AND GUY WIRE EASEMENT PARCELS.

TIMOTHY J. WININGS, MAPLS #45099

EXISTING CONDITIONS PLAN

ASSESSOR'S MAP 55, LOTS 2 & 3 & LEASEHOLD IMPROVEMENTS 5 TOWN DUMP ROAD TRURO, MA

DRAWN FOR
SBA TOWERS II, LLC
OWNER OF RECORD
TOWN OF TRURO

DATE: 22 DECEMBER 2009 SCALE 1 INCH = 50 FEET TJW SURVEY
TIMOTHY I. WINNEGE PLEPSS PAS
15 KESTRES DRIVE
LONGOHERSEY, HE 1883-4808
603-422-428



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

П	DRAWN	BY:	CHECKED	BY:	APPROVED	BY:
П	RMC		BLJ		MDW	

RFDS REV #:

PRELIMINARY DOCUMENTS

		SUBMITTALS				
REV	DATE	DESCRIPTION				
A	7/28/21	ISSUED FOR REVIEW				
0	8/10/21	ISSUED FOR CONSTRUCTION				
	A&E PROJECT NUMBER					

149562.001.01


DISH Wireless L.L. PROJECT INFORMATI


BOBOSO0593A 5 TOWN DUMP ROAD TRURO, MA 02666


SHEET TITLE
SURVEY SHEET

SHEET NUMBER

LS-1







ANTENNA TRANSMISSION CABLE SECTOR FEED LINE TYPE AND LENGTH EXISTING OR PROPOSED MANUFACTURER - MODEL RAD CENTER TECHNOLOGY SIZE (HxW) AZIMUTH ALPHA A1 PROPOSED JMA WIRELESS-MX08FR0665-21 5G 72.0" x 20.0" 0° 155'-0 1) HIGH-CAPACITY HYBRID CABLE (200' LONG) BETA B1 JMA WIRELESS-MX08FR0665-21 5G 72.0" x 20.0" 120° 155'-0" 72.0" × 20.0" 240° 155'-0" GAMMA C1 PROPOSED JMA WIRELESS-MX08FR0665-21 5G

		RRH		N
SECTOR	POSITION	MANUFACTURER — MODEL NUMBER	TECHNOLOGY	1
ALPHA	A1	FUJITSU - TA08025-B605	5G	١,
ALPHA	A1	FUJITSU - TA08025-B604	5G	1
BETA	B1	FUJITSU - TA08025-B605	5G	
BEIA	B1	FUJITSU - TA08025-B604	5G	
GAMMA	C1	FUJITSU - TA08025-B605	5G	
GAMMA	C1	FUJITSU - TA08025-B604	5G	

ANTENNA LAYOUT

NOTES

- CONTRACTOR TO REFER TO FINAL CONSTRUCTION RFDS FOR ALL RF DETAILS.
- ANTENNA AND RRH MODELS MAY CHANGE DUE TO EQUIPMENT AVAILABILITY. ALL EQUIPMENT CHANGES MUST BE APPROVED AND REMAIN IN COMPLIANCE WITH THE PROPOSED DESIGN AND STRUCTURAL ANALYSES.



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

	1	DRAWN BY:	CHECKED BY:	APPROVED BY
RMC BLJ MDW	ı	RMC	BLJ	MDW

RFDS REV #:

PRELIMINARY DOCUMENTS

		SUBMITTALS
REV	DATE	DESCRIPTION
Α	7/28/21	ISSUED FOR REVIEW
0	8/10/21	ISSUED FOR CONSTRUCTION
	Δ&F I	PROJECT NUMBER

149562.001.01

DISH Wireless L.L.C. PROJECT INFORMATION

BOBOS00593A 5 TOWN DUMP ROAD TRURO, MA 02666

SHEET TITLE

ELEVATION, ANTENNA LAYOUT AND SCHEDULE


SHEET NUMBER


A-2


ANTENNA SCHEDULE


NO SCALE

3/4"=1'-0









FINAL POWER OR FIBER DESIGN NOT AVAILABLE AT TIME OF ISSUE

<u>NOTES</u>

- CONTRACTOR SHALL FIELD VERIFY ALL PROPOSED UNDERGROUND UTILITY CONDUIT ROUTE.
- ANTENNAS AND MOUNTS OMITTED FOR CLARITY.

DC POWER WIRING SHALL BE COLOR CODED AT EACH END FOR IDENTIFYING ± 24 V and ± 48 V conductors. RED MARKINGS SHALL IDENTIFY ± 24 V and blue markings shall identify ± 48 V.

- CONTRACTOR SHALL INSPECT THE EXISTING CONDITIONS PRIOR TO SUBMITTING A BID. ANY QUESTIONS ARISING DURING THE BID PERIOD IN REGARDS TO THE CONTRACTOR'S FUNCTIONS, THE SCOPE OF WORK, OR ANY OTHER ISSUE RELATED TO THIS PROJECT SHALL BE BROUGHT UP DURING THE BID PERIOD WITH THE PROJECT MANAGER FOR CLARIFICATION, NOT AFTER THE CONTRACT HAS BEEN AWARDED.
- ALL ELECTRICAL WORK SHALL BE DONE IN ACCORDANCE WITH CURRENT NATIONAL ELECTRICAL CODES AND ALL STATE AND LOCAL CODES, LAWS, AND ORDINANCES. PROVIDE ALL COMPONENTS AND WIRING SIZES AS REQUIRED TO MEET NEC STANDARDS.
- 3. LOCATION OF EQUIPMENT, CONDUIT AND DEVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE AND SHALL BE COORDINATED WITH FIELD CONDITIONS PRIOR TO CONSTRUCTION.
- CONDUIT ROUGH—IN SHALL BE COORDINATED WITH THE MECHANICAL EQUIPMENT TO AVOID LOCATION CONFLICTS.
 VERIFY WITH THE MECHANICAL EQUIPMENT CONTRACTOR AND COMPLY AS REQUIRED.
- 5. CONTRACTOR SHALL PROVIDE ALL BREAKERS, CONDUITS AND CIRCUITS AS REQUIRED FOR A COMPLETE SYSTEM.
- 6. CONTRACTOR SHALL PROVIDE PULL BOXES AND JUNCTION BOXES AS REQUIRED BY THE NEC ARTICLE 314.
- 7. CONTRACTOR SHALL PROVIDE ALL STRAIN RELIEF AND CABLE SUPPORTS FOR ALL CABLE ASSEMBLIES. INSTALLATION SHALL BE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
- 8. ALL DISCONNECTS AND CONTROLLING DEVICES SHALL BE PROVIDED WITH ENGRAVED PHENOLIC NAMEPLATES INDICATING EQUIPMENT CONTROLLED, BRANCH CIRCUITS INSTALLED ON, AND PANEL FIELD LOCATIONS FED FROM.
- INSTALL AN EQUIPMENT GROUNDING CONDUCTOR IN ALL CONDUITS PER THE SPECIFICATIONS AND NEC 250.
 THE EQUIPMENT GROUNDING CONDUCTORS SHALL BE BONDED AT ALL JUNCTION BOXES, PULL BOXES, AND ALL
 DISCONNECT SWITCHES, AND EQUIPMENT CABINETS.
- 10. ALL NEW MATERIAL SHALL HAVE A U.L. LABEL.
- 11. PANEL SCHEDULE LOADING AND CIRCUIT ARRANGEMENTS REFLECT POST-CONSTRUCTION EQUIPMENT.
- 12. CONTRACTOR SHALL BE RESPONSIBLE FOR AS-BUILT PANEL SCHEDULE AND SITE DRAWINGS.
- 13. ALL TRENCHES IN COMPOUND TO BE HAND DUG



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



BOCA RATON, FL 33487





B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN	BY:	CHECKED	BY:	APPROVED	BY:
RMC		BLJ		MDW	

RFDS REV #:

PRELIMINARY DOCUMENTS

		SUBMITTALS
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	8/10/21	ISSUED FOR CONSTRUCTION
	∧ &cE	PROJECT NUMBER

149562.001.01

DISH Wireless L.L.C. PROJECT INFORMATION


BOBOSO0593A 5 TOWN DUMP ROAD TRURO, MA 02666

SHEET TITLE

ELECTRICAL/FIBER ROUTE PLAN AND NOTES

SHEET NUMBER


E-1




UTILITY ROUTE PLAN

ELECTRICAL NOTES

NO SCALE





NOTES

THE (2) CONDUITS WITH (4) CURRENT CARRYING CONDUCTORS EACH, SHALL APPLY THE ADJUSTMENT FACTOR OF 80% PER 2014/17 NEC TABLE 310.15(B)(3)(α) OR 2020 NEC TABLE 310.15(C)(1) FOR UL1015 WIRE.

> #12 FOR 15A-20A/1P BREAKER: 0.8 x 30A = 24.0A #10 FOR 25A-30A/2P BREAKER: 0.8 x 40A = 32.0A #8 FOR 35A-40A/2P BREAKER: 0.8 x 55A = 44.0A #6 FOR 45A-60A/2P BREAKER: 0.8 x 75A = 60.0A

CONDUIT SIZING: AT 40% FILL PER NEC CHAPTER 9, TABLE 4, ARTICLE 358. 0.5" CONDUIT - 0.122 SQ. IN AREA

0.75" CONDUIT - 0.213 SQ. IN AREA 2.0" CONDUIT - 1.316 SQ. IN AREA 3.0" CONDUIT - 2.907 SQ. IN AREA

CABINET CONVENIENCE OUTLET CONDUCTORS (1 CONDUIT): USING THWN-2, CU.

#10 - 0.0211 SQ. IN X 2 = 0.0422 SQ. IN #10 - 0.0211 SQ. IN X 1 = 0.0211 SQ. IN <GROUND = 0.0633 SQ. IN

O.5" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (3) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

RECTIFIER CONDUCTORS (2 CONDUITS): USING UL1015, CU.

#10 - 0.0266 SQ. IN X 4 = 0.1064 SQ. IN #10 - 0.0082 SQ. IN X 1 = 0.0082 SQ. IN <BARE GROUND TOTAL = 0.1146 SQ. IN

0.75" EMT CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (5) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

PPC FEED CONDUCTORS (1 CONDUIT): USING THWN, CU.

TOTAL

3/0 - 0.2679 SQ. IN X 3 = 0.8037 SQ. IN #6 - 0.0507 SQ. IN X 1 = 0.0507 SQ. IN <GROUND

NO SCALE

= 0.8544 SQ. IN 3.0" SCH 40 PVC CONDUIT IS ADEQUATE TO HANDLE THE TOTAL OF (4) WIRES, INCLUDING GROUND WIRE, AS INDICATED ABOVE.

B&T ENGINEERING, INC.

5701 SOUTH SANTA FE DRIVE

LITTLETON, CO 80120

BOCA RATON, FL 33487

B+T GRP

1717 S. BOULDER SUITE 300 TULSA, OK 74119 PH: (918) 587-4630 www.btgrp.com

SBA

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY: CHECKED BY: APPROVED BY MDW

RFDS REV #:

PRELIMINARY DOCUMENTS

		SUBMITTALS		
REV	DATE	DESCRIPTION		
Α	7/28/21	ISSUED FOR REVIEW		
0	8/10/21	ISSUED FOR CONSTRUCTION		

A&E PROJECT NUMBER

149562.001.01

BOBOSO0593A 5 TOWN DUMP ROAD TRURO, MA 02666

SHEET TITLE

ELECTRICAL ONE-LINE, FAULT CALCS & PANEL SCHEDULE

SHEET NUMBER

E-3

PPC ONE-LINE DIAGRAM

BREAKERS REQUIRED: (4) 30A, 2P BREAKER — SQUARE D P/N:QO230 (1) 15A, 1P BREAKER - SQUARE D P/N:Q0115


PROPOSED CHARLES PANEL SCHEDULE (WATTS) (WATTS) LOAD SERVED ABB/GE INFINITY RECTIFIER 1 30A ABB/GE INFINITY RECTIFIER 2 30A ABB/GE INFINITY 30A ABB/GE INFINIT 30A RECTIFIER 4
-SPACE-SPACE-VOLTAGE AMPS | 180 | 180 200A MCB, 16, 24 SPACE, 120/240V MB RATING: 65,000 AIC 11700 11700 VOLTAGE AMPS 98 98 AMPS

PANEL SCHEDULE

NO SCALE

NOT USED

NO SCALE



TYPICAL EQUIPMENT GROUNDING PLAN

DISH Wireless L.L.C. TEMPLATE VERSION 37 - 07/09/2021

<u>NOTES</u>

ANTENNAS AND OVP SHOWN ARE GENERIC AND NOT REFERENCING TO A SPECIFIC

MANUFACTURER. THIS LAYOUT IS FOR REFERENCE

EXOTHERMIC CONNECTION MECHANICAL CONNECTION

GROUND BUS BAR

GROUND ROD

(•)

TEST GROUND ROD WITH INSPECTION SLEEVE

---- #6 AWG STRANDED & INSULATED

— · — · — #2 AWG SOLID COPPER TINNED

▲ BUSS BAR INSULATOR

GROUNDING LEGEND

- 1. GROUNDING IS SHOWN DIAGRAMMATICALLY ONLY.
- CONTRACTOR SHALL GROUND ALL EQUIPMENT AS A COMPLETE SYSTEM. GROUNDING SHALL BE IN COMPLIANCE WITH NEC SECTION 250 AND DISH Wireless L.L.C. GROUNDING AND BONDING REQUIREMENTS AND MANUFACTURER'S SPECIFICATIONS.
- 3. ALL GROUND CONDUCTORS SHALL BE COPPER; NO ALUMINUM CONDUCTORS SHALL BE USED.

GROUNDING KEY NOTES

- (A) EXTERIOR GROUND RING: #2 AWG SOLID COPPER, BURIED AT A DEPTH OF AT LEAST 30 INCHES BELOW GRADE, OR 6 INCHES BELOW THE FROST LINE AND APPROXIMATELY 24 INCHES FROM THE EXTERIOR WALL OR FOOTING.
- B TOWER GROUND RING: THE GROUND RING SYSTEM SHALL BE INSTALLED AROUND AN ANTENNA TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN BROWNERS FOR THE TOWER'S LEGS, AND/OR GUY ANCHORS. WHERE SEPARATE SYSTEMS HAVE BEEN PROVIDED FOR THE TOWER AND THE BUILDING, AT LEAST TWO BONDS SHALL BE MADE BETWEEN THE TOWER RING GROUND SYSTEM AND THE BUILDING RING GROUND SYSTEM USING MINIMUM #2 AWG SOLID COPPER CONDUCTORS.
- © INTERIOR GROUND RING: #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTOR EXTENDED AROUND THE PERIMETER OF THE EQUIPMENT AREA. ALL NON-TELECOMMUNICATIONS RELATED METALLIC OBJECTS FOUND WITHIN A SITE SHALL BE GROUNDED TO THE INTERIOR GROUND RING WITH #6 AWG STRANDED GREEN
- D BOND TO INTERIOR GROUND RING: #2 AWG SOLID TINNED COPPER WIRE PRIMARY BONDS SHALL BE PROVIDED AT LEAST AT FOUR POINTS ON THE INTERIOR GROUND RING, LOCATED AT THE CORNERS OF THE
- F CELL REFERENCE GROUND BAR: POINT OF GROUND REFERENCE FOR ALL COMMUNICATIONS EQUIPMENT FRAMES. ALL BONDS ARE MADE WITH #2 AWG UNLESS NOTED OTHERWISE STRANDED GREEN INSULATED COPPER CONDUCTORS. BOND TO GROUND RING WITH (2) #2 SOLID TINNED COPPER CONDUCTORS.
- G HATCH PLATE GROUND BAR: BOND TO THE INTERIOR GROUND RING WITH TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS. WHEN A HATCH-PLATE AND A CELL REFERENCE GROUND BAR ARE BOTH PRESENT, THE CRGB MUST BE CONNECTED TO THE HATCH-PLATE AND TO THE INTERIOR GROUND RING USING (2) TWO #2 AWG STRANDED GREEN INSULATED COPPER CONDUCTORS EACH.
- (H) EXTERIOR CABLE ENTRY PORT GROUND BARS; LOCATED AT THE ENTRANCE TO THE CELL SITE BUILDING, BOND TO GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTORS WITH AN EXOTHERMIC WELD AND INSPECTION SLEEVE.
- () TELCO GROUND BAR: BOND TO BOTH CELL REFERENCE GROUND BAR OR EXTERIOR GROUND RING.
- J FRAME BONDING: THE BONDING POINT FOR TELECOM EQUIPMENT FRAMES SHALL BE THE GROUND BUS THAT IS NOT ISOLATED FROM THE EQUIPMENTS METAL FRAMEWORK.
- K INTERIOR UNIT BONDS: METAL FRAMES, CABINETS AND INDIVIDUAL METALLIC UNITS LOCATED WITH THE AREA OF THE INTERIOR GROUND RING REQUIRE A #6 AWG STRANDED GREEN INSULATED COPPER BOND TO THE
- L FENCE AND GATE GROUNDING: METAL FENCES WITHIN 7 FEET OF THE EXTERIOR GROUND RING OR OBJECTS BONDED TO THE EXTERIOR GROUND RING SHALL BE BONDED TO THE GROUND RING WITH A #2 AWG SOLID TINNED COPPER CONDUCTOR AT AN INTERVAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH CAST BOST AND ACCROSS CAST OFFENTIAL NOT EXCEEDING 25 FEET. BONDS SHALL BE MADE AT EACH
- (M) <u>Exterior unit bonds</u>: Metallic objects, external to or mounted to the building, shall be bonded to the exterior ground ring. Using #2 tinned solid copper wire
- N ICE BRIDGE SUPPORTS: EACH ICE BRIDGE LEG SHALL BE BONDED TO THE GROUND RING WITH #2 AWG BARE TINNED COPPER CONDUCTOR. PROVIDE EXOTHERMIC WELDS AT BOTH THE ICE BRIDGE LEG AND BURIED
- DURING ALL DC POWER SYSTEM CHANGES INCLUDING DC SYSTEM CHANGE OUTS, RECTIFIER REPLACEMENTS OR ADDITIONS, BREAKER DISTRIBUTION CHANGES, BATTERY ADDITIONS, BATTERY REPLACEMENTS AND INSTALLATIONS OR CHANGES TO DC CONVETTER SYSTEMS IT SHALL BE REQUIRED THAT SERVICE CONTRACTORS VERIFY ALL DC POWER SYSTEMS ARE EQUIPPED WITH A MASTER DC SYSTEM RETURN GROUND CONDUCTOR FROM THE DC POWER SYSTEM COMMON RETURN BUS DIRECTLY CONNECTED TO THE CELL SITE PEFERENCE CROUND BAR REFERENCE GROUND BAR
- (P) TOWER TOP COLLECTOR BUSS BAR IS TO BE MECHANICALLY BONDED TO TOWER STEEL.

REFER TO DISH Wireless L.L.C. GROUNDING NOTES.



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



BOCA RATON, FL 33487





B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

ı	DRAWN BY:		CHECKED	BY:	APPROVED	BY:
	RMC		BLJ		MDW	

PRELIMINARY DOCUMENTS

		SUBMITTALS
REV	DATE	DESCRIPTION
Α	7/28/21	ISSUED FOR REVIEW
0	8/10/21	ISSUED FOR CONSTRUCTION
	A&E F	PROJECT NUMBER

149562.001.01

DISH Wireless L.L.C. PROJECT INFORMATION

BOBOSO0593A 5 TOWN DUMP ROAD TRURO, MA 02666

SHEET TITLE

GROUNDING PLANS AND NOTES

SHEET NUMBER

NO SCALE

G-1

TYPICAL ANTENNA GROUNDING PLAN NO SCALE **GROUNDING KEY NOTES**


PROPOSED BUSS BAR INSULATORS (TYP)


PROPOSED 4"x6"x1/4"
TINNED COPPER SECTOR


GROUND BUSSBAR (TYP


PROPOSED #2 AWG STRANDED COPPER GREEN INSULATED (TYP)

PROPOSED UPPER TOWER GROUND BAR









NOT USED



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

П	DRAWN	BY:	CHECKED	BY:	APPROVED	BY:
П	RMC		BLJ		MDW	

RFDS REV #:

PRELIMINARY DOCUMENTS

		SUBMITTALS
REV	DATE	DESCRIPTION
Α.	7/28/21	ISSUED FOR REVIEW
0	8/10/21	ISSUED FOR CONSTRUCTION
$\overline{}$	∧ &cE = E	DRO IECT NILIMBER

149562.001.01

DISH Wireless L.L.C. PROJECT INFORMATION

BOBOS00593A 5 TOWN DUMP ROAD TRURO, MA 02666

SHEET TITLE


RF

CABLE COLOR CODE

SHEET NUMBER

NO SCALE

RF-1





5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN	BY:	CHECKED	BY:	APPROVED	BY:
RMC)	BLJ		MDW	

RFDS REV #:

PRELIMINARY DOCUMENTS

		SUBMITTALS
REV	DATE	DESCRIPTION
A	7/28/21	ISSUED FOR REVIEW
0	8/10/21	ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

149562.001.01

PROJECT INFORMATIO

BOBOSO0593A 5 TOWN DUMP ROAD TRURO, MA 02666

SHEET TITLE

LEGEND AND ABBREVIATIONS

SHEET NUMBER

SITE ACTIVITY REQUIREMENTS:

- 1. NOTICE TO PROCEED NO WORK SHALL COMMENCE PRIOR TO CONTRACTOR RECEIVING A WRITTEN NOTICE TO PROCEED (NTP) AND THE ISSUANCE OF A PURCHASE ORDER. PRIOR TO ACCESSING/ENTERING THE SITE YOU MUST CONTACT THE DISH Wireless L.L.C. AND TOWER OWNER NOC & THE DISH Wireless L.L.C. AND TOWER CONSTRUCTION MANAGER.
- 2. "LOOK UP" DISH Wireless L.L.C. AND TOWER OWNER SAFETY CLIMB REQUIREMENT:

THE INTEGRITY OF THE SAFETY CLIMB AND ALL COMPONENTS OF THE CLIMBING FACILITY SHALL BE CONSIDERED DURING ALL STAGES OF DESIGN, INSTALLATION, AND INSPECTION. TOWER MODIFICATION, MOUNT REINFORCEMENTS, AND/OR EQUIPMENT INSTALLATIONS SHALL NOT COMPROMISE THE INTEGRITY OR FUNCTIONAL USE OF THE SAFETY CLIMB OR ANY COMPONENTS OF THE CLIMBING FACILITY ON THE STRUCTURE. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO: PINCHING OF THE WIRE ROPE, BENDING OF THE WIRE ROPE FROM ITS SUPPORTS, DIRECT CONTACT OR CLOSE PROXIMITY TO THE WIRE ROPE WHICH MAY CAUSE FRICTIONAL WEAR, IMPACT TO THE ANCHORAGE POINTS IN ANY WAY, OR TO IMPEDE/BLOCK ITS INTENDED USE. ANY COMPROMISED SAFETY CLIMB, INCLUDING EXISTING CONDITIONS MUST BE TAGGED OUT AND REPORTED TO YOUR DISH WIReless L.L.C. AND DISH WIReless L.L.C. AND TOWER OWNER POC OR CALL THE NOC TO GENERATE A SAFETY CLIMB MAINTENANCE AND CONTRACTOR NOTICE TICKET.

- 3. PRIOR TO THE START OF CONSTRUCTION, ALL REQUIRED JURISDICTIONAL PERMITS SHALL BE OBTAINED. THIS INCLUDES, BUT IS NOT LIMITED TO, BUILDING, ELECTRICAL, MECHANICAL, FIRE, FLOOD ZONE, ENVIRONMENTAL, AND ZONING. AFTER ONSITE ACTIVITIES AND CONSTRUCTION ARE COMPLETED, ALL REQUIRED PERMITS SHALL BE SATISFIED AND CLOSED OUT ACCORDING TO LOCAL JURISDICTIONAL REQUIREMENTS.
- 4. ALL CONSTRUCTION MEANS AND METHODS; INCLUDING BUT NOT LIMITED TO, ERECTION PLANS, RIGGING PLANS, CLIMBING PLANS, AND RESCUE PLANS SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR RESPONSIBLE FOR THE EXECUTION OF THE WORK CONTAINED HEREIN, AND SHALL MEET ANSI/ASSE A10.48 (LATEST EDITION); FEDERAL, STATE, AND LOCAL REGULATIONS; AND ANY APPLICABLE INDUSTRY CONSENSUS STANDARDS RELATED TO THE CONSTRUCTION ACTIVITIES BEING PERFORMED. ALL RIGGING PLANS SHALL ADHERE TO ANSI/ASSE A10.48 (LATEST EDITION) AND DISH WIRELESS L.L.C. AND TOWER OWNER STANDARDS, INCLUDING THE REQUIRED INVOLVEMENT OF A QUALIFIED ENGINEER FOR CLASS IV CONSTRUCTION, TO CERTIFY THE SUPPORTING STRUCTURE(S) IN ACCORDANCE WITH ANSI/TIA-322 (LATEST EDITION).
- 5. ALL SITE WORK TO COMPLY WITH DISH Wireless L.L.C. AND TOWER OWNER INSTALLATION STANDARDS FOR CONSTRUCTION ACTIVITIES ON DISH Wireless L.L.C. AND TOWER OWNER TOWER SITE AND LATEST VERSION OF ANSI/TIA-1019-A-2012 "STANDARD FOR INSTALLATION, ALTERATION, AND MAINTENANCE OF ANTENNA SUPPORTING STRUCTURES AND ANTENNAS."
- 6. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY DISH Wireless L.L.C. AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION.
- 7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- 8. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- 9. THE CONTRACTOR SHALL CONTACT UTILITY LOCATING SERVICES INCLUDING PRIVATE LOCATES SERVICES PRIOR TO THE START OF CONSTRUCTION.
- 10. ALL EXISTING ACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES WHERE ENCOUNTERED IN THE WORK, SHALL BE PROTECTED AT ALL TIMES AND WHERE REQUIRED FOR THE PROPER EXECUTION OF THE WORK, SHALL BE RELOCATED AS DIRECTED BY CONTRACTOR. EXTREME CAUTION SHOULD BE USED BY THE CONTRACTOR WHEN EXCAVATING OR DRILLING PIERS AROUND OR NEAR UTILITIES. CONTRACTOR SHALL PROVIDE SAFETY TRAINING FOR THE WORKING CREW. THIS WILL INCLUDE BUT NOT BE LIMITED TO A) FALL PROTECTION B) CONFINED SPACE C) ELECTRICAL SAFETY D) TRENCHING AND EXCAVATION E) CONSTRUCTION SAFETY PROCEDURES.
- 11. ALL SITE WORK SHALL BE AS INDICATED ON THE STAMPED CONSTRUCTION DRAWINGS AND DISH PROJECT SPECIFICATIONS, LATEST APPROVED REVISION.
- 12. CONTRACTOR SHALL KEEP THE SITE FREE FROM ACCUMULATING WASTE MATERIAL, DEBRIS, AND TRASH AT THE COMPLETION OF THE WORK. IF NECESSARY, RUBBISH, STUMPS, DEBRIS, STICKS, STONES AND OTHER REFUSE SHALL BE REMOVED FROM THE SITE AND DISPOSED OF LEGALLY.
- 13. ALL EXISTING INACTIVE SEWER, WATER, GAS, ELECTRIC AND OTHER UTILITIES, WHICH INTERFERE WITH THE EXECUTION OF THE WORK, SHALL BE REMOVED AND/OR CAPPED, PLUGGED OR OTHERWISE DISCONTINUED AT POINTS WHICH WILL NOT INTERFERE WITH THE EXECUTION OF THE WORK, SUBJECT TO THE APPROVAL OF DISH WIReless L.L.C. AND TOWER OWNER, AND/OR LOCAL UTILITIES.
- 14. THE CONTRACTOR SHALL PROVIDE SITE SIGNAGE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION FOR SITE SIGNAGE REQUIRED BY LOCAL JURISDICTION AND SIGNAGE REQUIRED ON INDIVIDUAL PIECES OF EQUIPMENT, ROOMS, AND SHELTERS.
- 15. THE SITE SHALL BE GRADED TO CAUSE SURFACE WATER TO FLOW AWAY FROM THE CARRIER'S EQUIPMENT AND TOWER AREAS.
- 16. THE SUB GRADE SHALL BE COMPACTED AND BROUGHT TO A SMOOTH UNIFORM GRADE PRIOR TO FINISHED SURFACE APPLICATION.
- 17. THE AREAS OF THE OWNERS PROPERTY DISTURBED BY THE WORK AND NOT COVERED BY THE TOWER, EQUIPMENT OR DRIVEWAY, SHALL BE GRADED TO A UNIFORM SLOPE, AND STABILIZED TO PREVENT EROSION AS SPECIFIED ON THE CONSTRUCTION DRAWINGS AND/OR PROJECT SPECIFICATIONS.
- 18. CONTRACTOR SHALL MINIMIZE DISTURBANCE TO EXISTING SITE DURING CONSTRUCTION. EROSION CONTROL MEASURES, IF REQUIRED DURING CONSTRUCTION, SHALL BE IN CONFORMANCE WITH THE LOCAL GUIDELINES FOR EROSION AND SEDIMENT CONTROL.
- 19. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF OWNER.
- 20. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS AND RADIOS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- 21. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION, TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.
- 22. NO FILL OR EMBANKMENT MATERIAL SHALL BE PLACED ON FROZEN GROUND. FROZEN MATERIALS, SNOW OR ICE SHALL NOT BE PLACED IN ANY FILL OR EMBANKMENT.

GENERAL NOTES:

1.FOR THE PURPOSE OF CONSTRUCTION DRAWING, THE FOLLOWING DEFINITIONS SHALL APPLY:

CONTRACTOR:GENERAL CONTRACTOR RESPONSIBLE FOR CONSTRUCTION

CARRIER:DISH Wireless L.L.C.

TOWER OWNER:TOWER OWNER

- 2. THESE DRAWINGS HAVE BEEN PREPARED USING STANDARDS OF PROFESSIONAL CARE AND COMPLETENESS NORMALLY EXERCISED UNDER SIMILAR CIRCUMSTANCES BY REPUTABLE ENGINEERS IN THIS OR SIMILAR LOCALITIES. IT IS ASSUMED THAT THE WORK DEPICTED WILL BE PERFORMED BY AN EXPERIENCED CONTRACTOR AND/OR WORKPEOPLE WHO HAVE A WORKING KNOWLEDGE OF THE APPLICABLE CODE STANDARDS AND REQUIREMENTS AND OF INDUSTRY ACCEPTED STANDARD GOOD PRACTICE. AS NOT EVERY CONDITION OR ELEMENT IS (OR CAN BE) EXPLICITLY SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARD GOOD PRACTICE FOR MISCELLANEOUS WORK NOT EXPLICITLY SHOWN.
- 3. THESE DRAWINGS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE MEANS OR METHODS OF CONSTRUCTION. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY FOR PROTECTION OF LIFE AND PROPERTY DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, FORMWORK, SHORING, ETC. SITE VISITS BY THE ENGINEER OR HIS REPRESENTATIVE WILL NOT INCLUDE INSPECTION OF THESE ITEMS AND IS FOR STRUCTURAL OBSERVATION OF THE FINISHED STRUCTURE ONLY.
- 4. NOTES AND DETAILS IN THE CONSTRUCTION DRAWINGS SHALL TAKE PRECEDENCE OVER GENERAL NOTES AND TYPICAL DETAILS. WHERE NO DETAILS ARE SHOWN, CONSTRUCTION SHALL CONFORM TO SIMILAR WORK ON THE PROJECT, AND/OR AS PROVIDED FOR IN THE CONTRACT DOCUMENTS. WHERE DISCREPANCIES OCCUR BETWEEN PLANS, DETAILS, GENERAL NOTES, AND SPECIFICATIONS, THE GREATER, MORE STRICT REQUIREMENTS, SHALL GOVERN. IF FURTHER CLARIFICATION IS REQUIRED CONTACT THE ENGINEER OF RECORD.
- 5. SUBSTANTIAL EFFORT HAS BEEN MADE TO PROVIDE ACCURATE DIMENSIONS AND MEASUREMENTS ON THE DRAWINGS TO ASSIST IN THE FABRICATION AND/OR PLACEMENT OF CONSTRUCTION ELEMENTS BUT IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO FIELD VERIFY THE DIMENSIONS, MEASUREMENTS, AND/OR CLEARANCES SHOWN IN THE CONSTRUCTION DRAWINGS PRIOR TO FABRICATION OR CUTTING OF ANY NEW OR EXISTING CONSTRUCTION ELEMENTS. IF IT IS DETERMINED THAT THERE ARE DISCREPANCIES AND/OR CONFLICTS WITH THE CONSTRUCTION DRAWINGS THE ENGINEER OF RECORD IS TO BE NOTIFIED AS SOON AS POSSIBLE.
- 6. PRIOR TO THE SUBMISSION OF BIDS, THE BIDDING CONTRACTOR SHALL VISIT THE CELL SITE TO FAMILIARIZE WITH THE EXISTING CONDITIONS AND TO CONFIRM THAT THE WORK CAN BE ACCOMPLISHED AS SHOWN ON THE CONSTRUCTION DRAWINGS. ANY DISCREPANCY FOUND SHALL BE BROUGHT TO THE ATTENTION OF CARRIER POC AND TOWER OWNER.
- 7. ALL MATERIALS FURNISHED AND INSTALLED SHALL BE IN STRICT ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND ORDINANCES. CONTRACTOR SHALL ISSUE ALL APPROPRIATE NOTICES AND COMPLY WITH ALL LAWS, ORDINANCES, RULES, REGULATIONS AND LAWFUL ORDERS OF ANY PUBLIC AUTHORITY REGARDING THE PERFORMANCE OF THE WORK. ALL WORK CARRIED OUT SHALL COMPLY WITH ALL APPLICABLE MUNICIPAL AND UTILITY COMPANY SPECIFICATIONS AND LOCAL JURISDICTIONAL CODES, ORDINANCES AND APPLICABLE REGULATIONS.
- 8. UNLESS NOTED OTHERWISE, THE WORK SHALL INCLUDE FURNISHING MATERIALS, EQUIPMENT, APPURTENANCES AND LABOR NECESSARY TO COMPLETE ALL INSTALLATIONS AS INDICATED ON THE DRAWINGS.
- 9. THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT AND MATERIALS IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS UNLESS SPECIFICALLY STATED OTHERWISE.
- 10. IF THE SPECIFIED EQUIPMENT CAN NOT BE INSTALLED AS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL PROPOSE AN ALTERNATIVE INSTALLATION FOR APPROVAL BY THE CARRIER AND TOWER OWNER PRIOR TO PROCEEDING WITH ANY SUCH CHANGE OF INSTALLATION
- 11. CONTRACTOR IS TO PERFORM A SITE INVESTIGATION, BEFORE SUBMITTING BIDS, TO DETERMINE THE BEST ROUTING OF ALL CONDUITS FOR POWER, AND TELCO AND FOR GROUNDING CABLES AS SHOWN IN THE POWER, TELCO, AND GROUNDING PLAN DRAWINGS.
- 12. THE CONTRACTOR SHALL PROTECT EXISTING IMPROVEMENTS, PAVEMENTS, CURBS, LANDSCAPING AND STRUCTURES. ANY DAMAGED PART SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE TO THE SATISFACTION OF DISH Wireless L.L.C. AND TOWER OWNER
- 13. CONTRACTOR SHALL LEGALLY AND PROPERLY DISPOSE OF ALL SCRAP MATERIALS SUCH AS COAXIAL CABLES AND OTHER ITEMS REMOVED FROM THE EXISTING FACILITY. ANTENNAS REMOVED SHALL BE RETURNED TO THE OWNER'S DESIGNATED LOCATION.
- 14. CONTRACTOR SHALL LEAVE PREMISES IN CLEAN CONDITION. TRASH AND DEBRIS SHOULD BE REMOVED FROM SITE ON A DAILY BASIS.



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

	DRAWN BY:		CHECKED	BY:	APPROVED	BY:
П	RMC		BLJ		MDW	

RFDS REV #

PRELIMINARY DOCUMENTS

SUBMITTALS

REV DATE DESCRIPTION

A 7/28/21 ISSUED FOR REVIEW

0 8/10/21 ISSUED FOR CONSTRUCTION

A&E PROJECT NUMBER

DISH Wireless L.L.C. PROJECT INFORMATION

149562.001.01

BOBOSO0593A 5 TOWN DUMP ROAD TRURO, MA 02666

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

CONCRETE, FOUNDATIONS, AND REINFORCING STEEL:

- 1. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH THE ACI 301, ACI 318, ACI 336, ASTM A184, ASTM A185 AND THE DESIGN AND CONSTRUCTION SPECIFICATION FOR CAST—IN—PLACE CONCRETE.
- 2. UNLESS NOTED OTHERWISE, SOIL BEARING PRESSURE USED FOR DESIGN OF SLABS AND FOUNDATIONS IS ASSUMED TO BE 1000 psf.
- 3. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH (f'c) OF 3000 psi AT 28 DAYS, UNLESS NOTED OTHERWISE. NO MORE THAN 90 MINUTES SHALL ELAPSE FROM BATCH TIME TO TIME OF PLACEMENT UNLESS APPROVED BY THE ENGINEER OF RECORD. TEMPERATURE OF CONCRETE SHALL NOT EXCEED 90'F AT TIME OF PLACEMENT.
- 4. CONCRETE EXPOSED TO FREEZE-THAW CYCLES SHALL CONTAIN AIR ENTRAINING ADMIXTURES, AMOUNT OF AIR ENTRAINMENT TO BE BASED ON SIZE OF AGGREGATE AND F3 CLASS EXPOSURE (VERY SEVERE). CEMENT USED TO BE TYPE II PORTLAND CEMENT WITH A MAXIMUM WATER-TO-CEMENT RATIO (W/C) OF 0.45.
- 5. ALL STEEL REINFORCING SHALL CONFORM TO ASTM A615. ALL WELDED WIRE FABRIC (WWF) SHALL CONFORM TO ASTM A185. ALL SPLICES SHALL BE CLASS "B" TENSION SPLICES, UNLESS NOTED OTHERWISE. ALL HOOKS SHALL BE STANDARD 90 DEGREE HOOKS, UNLESS NOTED OTHERWISE. YIELD STRENGTH (Fy) OF STANDARD DEFORMED BARS ARE AS FOLLOWS:

#4 BARS AND SMALLER 40 ksi

#5 BARS AND LARGER 60 ksi

- 6. THE FOLLOWING MINIMUM CONCRETE COVER SHALL BE PROVIDED FOR REINFORCING STEEL UNLESS SHOWN OTHERWISE ON DRAWINGS:
- CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH 3"
- CONCRETE EXPOSED TO EARTH OR WEATHER:
- #6 BARS AND LARGER 2"
- #5 BARS AND SMALLER 1-1/2"
- . CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
- SLAB AND WALLS 3/4"
- BEAMS AND COLUMNS 1-1/2*
- 7. A TOOLED EDGE OR A 3/4" CHAMFER SHALL BE PROVIDED AT ALL EXPOSED EDGES OF CONCRETE, UNLESS NOTED OTHERWISE, IN ACCORDANCE WITH ACI 301 SECTION 4.2.4.

ELECTRICAL INSTALLATION NOTES:

- 1. ALL ELECTRICAL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS, NEC AND ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES/ORDINANCES.
- 2. CONDUIT ROUTINGS ARE SCHEMATIC. CONTRACTOR SHALL INSTALL CONDUITS SO THAT ACCESS TO EQUIPMENT IS NOT BLOCKED AND TRIP HAZARDS ARE ELIMINATED.
- 3. WIRING, RACEWAY AND SUPPORT METHODS AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE NEC.
- 4. ALL CIRCUITS SHALL BE SEGREGATED AND MAINTAIN MINIMUM CABLE SEPARATION AS REQUIRED BY THE NEC.
- 4.1. ALL EQUIPMENT SHALL BEAR THE UNDERWRITERS LABORATORIES LABEL OF APPROVAL, AND SHALL CONFORM TO REQUIREMENT OF THE NATIONAL ELECTRICAL CODE.
- 4.2. ALL OVERCURRENT DEVICES SHALL HAVE AN INTERRUPTING CURRENT RATING THAT SHALL BE GREATER THAN THE SHORT CIRCUIT CURRENT TO WHICH THEY ARE SUBJECTED, 22,000 AIC MINIMUM. VERIFY AVAILABLE SHORT CIRCUIT CURRENT DOES NOT EXCEED THE RATING OF ELECTRICAL EQUIPMENT IN ACCORDANCE WITH ARTICLE 110.24 NEC OR THE MOST CURRENT ADOPTED CODE PRE THE GOVERNING JURISDICTION.
- 5. EACH END OF EVERY POWER PHASE CONDUCTOR, GROUNDING CONDUCTOR, AND TELCO CONDUCTOR OR CABLE SHALL BE LABELED WITH COLOR—CODED INSULATION OR ELECTRICAL TAPE (3M BRAND, 1/2" PLASTIC ELECTRICAL TAPE WITH UV PROTECTION, OR EQUAL). THE IDENTIFICATION METHOD SHALL CONFORM WITH NEC AND OSHA.
- 6. ALL ELECTRICAL COMPONENTS SHALL BE CLEARLY LABELED WITH LAMICOID TAGS SHOWING THEIR RATED VOLTAGE, PHASE CONFIGURATION, WIRE CONFIGURATION, POWER OR AMPACITY RATING AND BRANCH CIRCUIT ID NUMBERS (i.e. PANEL BOARD AND CIRCUIT ID'S).
- 7. PANEL BOARDS (ID NUMBERS) SHALL BE CLEARLY LABELED WITH PLASTIC LABELS.
- 8. TIE WRAPS ARE NOT ALLOWED.
- 9. ALL POWER AND EQUIPMENT GROUND WIRING IN TUBING OR CONDUIT SHALL BE SINGLE COPPER CONDUCTOR (#14 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- 10. SUPPLEMENTAL EQUIPMENT GROUND WIRING LOCATED INDOORS SHALL BE SINGLE COPPER CONDUCTOR (#6 OR LARGER) WITH TYPE THHW, THWN, THWN-2, XHHW, XHHW-2, THW, THW-2, RHW, OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- 11. POWER AND CONTROL WIRING IN FLEXIBLE CORD SHALL BE MULTI-CONDUCTOR, TYPE SOOW CORD (#14 OR LARGER) UNLESS OTHERWISE SPECIFIED.
- 12. POWER AND CONTROL WIRING FOR USE IN CABLE TRAY SHALL BE MULTI-CONDUCTOR, TYPE TC CABLE (#14 OR LARGER), WITH TYPE THHW. THWN. THWN-2. XHHW. XHHW-2. THW. THW-2. RHW. OR RHW-2 INSULATION UNLESS OTHERWISE SPECIFIED.
- 13. ALL POWER AND GROUNDING CONNECTIONS SHALL BE CRIMP-STYLE, COMPRESSION WIRE LUGS AND WIRE NUTS BY THOMAS AND BETTS (OR EQUAL). LUGS AND WIRE NUTS SHALL BE RATED FOR OPERATION NOT LESS THAN 75° C (90° C IF AVAILABLE).
- 14. RACEWAY AND CABLE TRAY SHALL BE LISTED OR LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND NEC.
- 15. ELECTRICAL METALLIC TUBING (EMT), INTERMEDIATE METAL CONDUIT (IMC), OR RIGID METAL CONDUIT (RMC) SHALL BE USED FOR EXPOSED INDOOR LOCATIONS.

- 6. ELECTRICAL METALLIC TUBING (EMT) OR METAL—CLAD CABLE (MC) SHALL BE USED FOR CONCEALED INDOOR LOCATIONS.
- 17. SCHEDULE 40 PVC UNDERGROUND ON STRAIGHTS AND SCHEDULE 80 PVC FOR ALL ELBOWS/90s AND ALL APPROVED ABOVE GRADE PVC CONDUIT.
- 18. LIQUID-TIGHT FLEXIBLE METALLIC CONDUIT (LIQUID-TITE FLEX) SHALL BE USED INDOORS AND OUTDOORS, WHERE VIBRATION OCCURS OR FLEXIBILITY IS NEEDED.
- 19. CONDUIT AND TUBING FITTINGS SHALL BE THREADED OR COMPRESSION—TYPE AND APPROVED FOR THE LOCATION USED. SET SCREW FITTINGS ARE NOT ACCEPTABLE.
- 20. CABINETS, BOXES AND WIRE WAYS SHALL BE LABELED FOR ELECTRICAL USE IN ACCORDANCE WITH NEMA, UL, ANSI/IEEE AND THE NEC.
- 21. WIREWAYS SHALL BE METAL WITH AN ENAMEL FINISH AND INCLUDE A HINGED COVER, DESIGNED TO SWING OPEN DOWNWARDS (WIREMOLD SPECMATE WIREWAY).
- 22. SLOTTED WIRING DUCT SHALL BE PVC AND INCLUDE COVER (PANDUIT TYPE E OR EQUAL).
- 23. CONDUITS SHALL BE FASTENED SECURELY IN PLACE WITH APPROVED NON-PERFORATED STRAPS AND HANGERS. EXPLOSIVE DEVICES (i.e. POWDER-ACTUATED) FOR ATTACHING HANGERS TO STRUCTURE WILL NOT BE PERMITTED. CLOSELY FOLLOW THE LINES OF THE STRUCTURE, MAINTAIN CLOSE PROXIMITY TO THE STRUCTURE AND KEEP CONDUITS IN TIGHT ENVELOPES. CHANGES IN DIRECTION TO ROUTE AROUND OBSTACLES SHALL BE MADE WITH CONDUIT OUTLET BODIES. CONDUIT SHALL BE INSTALLED IN A NEAT AND WORKMANLIKE MANNER. PARALLEL AND PERPENDICULAR TO STRUCTURE WALL AND CEILING LINES. ALL CONDUIT SHALL BE FISHED TO CLEAR OBSTRUCTIONS. ENDS OF CONDUITS SHALL BE TEMPORARILY CAPPED FLUSH TO FINISH GRADE TO PREVENT CONCRETE, PLASTER OR DIRT FROM ENTERING. CONDUITS SHALL BE RIGIDLY CLAMPED TO BOXES BY GALVANIZED MALLEABLE IRON BUSHING ON INSIDE AND GALVANIZED MALLEABLE IRON LOCKNUT ON OUTSIDE AND INSIDE.
- 24. EQUIPMENT CABINETS, TERMINAL BOXES, JUNCTION BOXES AND PULL BOXES SHALL BE GALVANIZED OR EPOXY-COATED SHEET STEEL. SHALL MEET OR EXCEED UL 50 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND NEMA 3 (OR BETTER) FOR EXTERIOR LOCATIONS.
- 25. METAL RECEPTACLE, SWITCH AND DEVICE BOXES SHALL BE GALVANIZED, EPOXY—COATED OR NON—CORRODING; SHALL MEET OR EXCEED UL 514A AND NEMA OS 1 AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
- 26. NONMETALLIC RECEPTACLE, SWITCH AND DEVICE BOXES SHALL MEET OR EXCEED NEMA OS 2 (NEWEST REVISION) AND BE RATED NEMA 1 (OR BETTER) FOR INTERIOR LOCATIONS AND WEATHER PROTECTED (WP OR BETTER) FOR EXTERIOR LOCATIONS.
- 27. THE CONTRACTOR SHALL NOTIFY AND OBTAIN NECESSARY AUTHORIZATION FROM THE CARRIER AND/OR DISH Wireless L.L.C. AND TOWER OWNER BEFORE COMMENCING WORK ON THE AC POWER DISTRIBUTION PANELS.
- 28. THE CONTRACTOR SHALL PROVIDE NECESSARY TAGGING ON THE BREAKERS, CABLES AND DISTRIBUTION PANELS IN ACCORDANCE WITH THE APPLICABLE CODES AND STANDARDS TO SAFEGUARD LIFE AND PROPERTY.
- 29. INSTALL LAMICOID LABEL ON THE METER CENTER TO SHOW "DISH Wireless L.L.C.".
- 30. ALL EMPTY/SPARE CONDUITS THAT ARE INSTALLED ARE TO HAVE A METERED MULE TAPE PULL CORD INSTALLED.



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

RMC BLJ I	MDW

RFDS REV #

PRELIMINARY DOCUMENTS

	SUBMITTALS				
REV	DATE	DESCRIPTION			
Α	7/28/21	ISSUED FOR REVIEW			
0	8/10/21	ISSUED FOR CONSTRUCTION			
	A&E F	PROJECT NUMBER			

149562.001.01

BOBOSO0593A 5 TOWN DUMP ROAD TRURO, MA 02666

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

GROUNDING NOTES:

- 1. ALL GROUND ELECTRODE SYSTEMS (INCLUDING TELECOMMUNICATION, RADIO, LIGHTNING PROTECTION AND AC POWER GES'S) SHALL BE BONDED TOGETHER AT OR BELOW GRADE, BY TWO OR MORE COPPER BONDING CONDUCTORS IN ACCORDANCE WITH THE NEC.
- 2. THE CONTRACTOR SHALL PERFORM IEEE FALL—OF—POTENTIAL RESISTANCE TO EARTH TESTING (PER IEEE 1100 AND 81) FOR GROUND ELECTRODE SYSTEMS, THE CONTRACTOR SHALL FURNISH AND INSTALL SUPPLEMENTAL GROUND ELECTRODES AS NEEDED TO ACHIEVE A TEST RESULT OF 5 OHMS OR LESS.
- 3. THE CONTRACTOR IS RESPONSIBLE FOR PROPERLY SEQUENCING GROUNDING AND UNDERGROUND CONDUIT INSTALLATION AS TO PREVENT ANY LOSS OF CONTINUITY IN THE GROUNDING SYSTEM OR DAMAGE TO THE CONDUIT AND PROVIDE TESTING RESULTS.
- 4. METAL CONDUIT AND TRAY SHALL BE GROUNDED AND MADE ELECTRICALLY CONTINUOUS WITH LISTED BONDING FITTINGS OR BY BONDING ACROSS THE DISCONTINUITY WITH #6 COPPER WIRE UL APPROVED GROUNDING TYPE CONDUIT CLAMPS.
- 5. METAL RACEWAY SHALL NOT BE USED AS THE NEC REQUIRED EQUIPMENT GROUND CONDUCTOR. STRANDED COPPER CONDUCTORS WITH GREEN INSULATION, SIZED IN ACCORDANCE WITH THE NEC, SHALL BE FURNISHED AND INSTALLED WITH THE POWER CIRCUITS TO BTS EQUIPMENT.
- 6. EACH CABINET FRAME SHALL BE DIRECTLY CONNECTED TO THE MASTER GROUND BAR WITH GREEN INSULATED SUPPLEMENTAL EQUIPMENT GROUND WIRES, #6 STRANDED COPPER OR LARGER FOR INDOOR BTS; #2 BARE SOLID TINNED COPPER FOR OUTDOOR BTS.
- 7. CONNECTIONS TO THE GROUND BUS SHALL NOT BE DOUBLED UP OR STACKED BACK TO BACK CONNECTIONS ON OPPOSITE SIDE OF THE GROUND BUS ARE PERMITTED.
- 8. ALL EXTERIOR GROUND CONDUCTORS BETWEEN EQUIPMENT/GROUND BARS AND THE GROUND RING SHALL BE #2 SOLID TINNED COPPER UNLESS OTHERWISE INDICATED.
- 9. ALUMINUM CONDUCTOR OR COPPER CLAD STEEL CONDUCTOR SHALL NOT BE USED FOR GROUNDING CONNECTIONS.
- 10. USE OF 90° BENDS IN THE PROTECTION GROUNDING CONDUCTORS SHALL BE AVOIDED WHEN 45° BENDS CAN BE ADEQUATELY SUPPORTED.
- 11. EXOTHERMIC WELDS SHALL BE USED FOR ALL GROUNDING CONNECTIONS BELOW GRADE.
- 12. ALL GROUND CONNECTIONS ABOVE GRADE (INTERIOR AND EXTERIOR) SHALL BE FORMED USING HIGH PRESS CRIMPS.
- COMPRESSION GROUND CONNECTIONS MAY BE REPLACED BY EXOTHERMIC WELD CONNECTIONS.
- 14. ICE BRIDGE BONDING CONDUCTORS SHALL BE EXOTHERMICALLY BONDED OR BOLTED TO THE BRIDGE AND THE TOWER GROUND BAR.
- 15. APPROVED ANTIOXIDANT COATINGS (i.e. CONDUCTIVE GEL OR PASTE) SHALL BE USED ON ALL COMPRESSION AND BOLTED GROUND CONNECTIONS.
- 16. ALL EXTERIOR GROUND CONNECTIONS SHALL BE COATED WITH A CORROSION RESISTANT MATERIAL.
- 17. MISCELLANEOUS ELECTRICAL AND NON-ELECTRICAL METAL BOXES, FRAMES AND SUPPORTS SHALL BE BONDED TO THE GROUND RING, IN ACCORDANCE WITH THE NEC.
- 18. BOND ALL METALLIC OBJECTS WITHIN 6 ft OF MAIN GROUND RING WITH (1) #2 BARE SOLID TINNED COPPER GROUND CONDUCTOR.
- 19. GROUND CONDUCTORS USED FOR THE FACILITY GROUNDING AND LIGHTNING PROTECTION SYSTEMS SHALL NOT BE ROUTED THROUGH METALLIC OBJECTS THAT FORM A RING AROUND THE CONDUCTOR, SUCH AS METALLIC CONDUITS, METAL SUPPORT CLIPS OR SLEEVES THROUGH WALLS OR FLOORS. WHEN IT IS REQUIRED TO BE HOUSED IN CONDUIT TO MEET CODE REQUIREMENTS OR LOCAL CONDITIONS, NON-METALLIC MATERIAL SUCH AS PVC CONDUIT SHALL BE USED. WHERE USE OF METAL CONDUIT IS UNAVOIDABLE (i.e., NONMETALLIC CONDUIT PROHIBITED BY LOCAL CODE) THE GROUND CONDUCTOR SHALL BE BONDED TO EACH END OF THE METAL CONDUIT.
- 20. ALL GROUNDS THAT TRANSITION FROM BELOW GRADE TO ABOVE GRADE MUST BE #2 BARE SOLID TINNED COPPER IN 3/4" NON-METALLIC, FLEXIBLE CONDUIT FROM 24" BELOW GRADE TO WITHIN 3" TO 6" OF CAD-WELD TERMINATION POINT. THE EXPOSED END OF THE CONDUIT MUST BE SEALED WITH SILICONE CAULK. (ADD TRANSITIONING GROUND STANDARD DETAIL AS WELL).
- 21. BUILDINGS WHERE THE MAIN GROUNDING CONDUCTORS ARE REQUIRED TO BE ROUTED TO GRADE, THE CONTRACTOR SHALL ROUTE TWO GROUNDING CONDUCTORS FROM THE ROOFTOP, TOWERS, AND WATER TOWERS GROUNDING RING, TO THE EXISTING GROUNDING SYSTEM, THE GROUNDING CONDUCTORS SHALL NOT BE SMALLER THAN 2/O COPPER. ROOFTOP GROUNDING RING SHALL BE BONDED TO THE EXISTING GROUNDING SYSTEM, THE BUILDING STEEL COLUMNS, LIGHTNING PROTECTION SYSTEM, AND BUILDING MAIN WATER LINE (FERROUS OR NONFERROUS METAL PIPING ONLY). DO NOT ATTACH GROUNDING TO FIRE SPRINKLER SYSTEM PIPES.



5701 SOUTH SANTA FE DRIVE LITTLETON, CO 80120



8051 CONGRESS AVENUE BOCA RATON, FL 33487





B&T ENGINEERING, INC.

IT IS A VIOLATION OF LAW FOR ANY PERSON, UNLESS THEY ARE ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT.

DRAWN BY:		CHECKED BY:		APPROVED	BY:
RMC		BLJ		MDW	

RFDS REV #:

PRELIMINARY DOCUMENTS

	SUBMITTALS					
REV	DATE	DESCRIPTION				
A	7/28/21	ISSUED FOR REVIEW				
0	8/10/21	ISSUED FOR CONSTRUCTION				
	405.5	DDO JEGT NUMBER				

A&E PROJECT NUMBER

149562.001.01

DISH Wireless L.L PROJECT INFORMAT

BOBOSO0593A 5 TOWN DUMP ROAD TRURO, MA 02666

SHEET TITLE

GENERAL NOTES

SHEET NUMBER



Radio Frequency Emissions Analysis Report



Site ID: BOBOS00593A

SBA - Town Dump Road 5 Town Dump Road Truro, MA 02666

April 27, 2023

Fox Hill Telecom Project Number: 230389

Site Compliance Summary				
Compliance Status:	COMPLIANT			
Site total MPE% of FCC general population allowable limit:	11.94 %			



April 27, 2023

Dish Wireless 5701 South Santa Fe Drive Littleton, CO 80120

Emissions Analysis for Site: BOBOS00593A – SBA - Town Dump Road

Fox Hill Telecom, Inc ("Fox Hill") was directed to analyze the proposed radio installation for Dish Wireless, LLC (Dish) facility located at **5 Town Dump Road, Truro, MA**, for the purpose of determining whether the emissions from the Proposed Dish radio and antenna installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter (μ W/cm²). The number of μ W/cm² calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) - (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general population may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general population would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Population exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter (μ W/cm²). The general population exposure limit for the 600 MHz band is approximately 400 μ W/cm². The general population exposure limit for the 1900 MHz (PCS) and 2100 MHz (AWS / AWS-4) bands is 1000 μ W/cm². Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report the percentage of MPE rather than power density.



Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.



CALCULATIONS

Calculations were performed for the proposed upgrades to the Dish Wireless antenna facility located at **5 Town Dump Road, Truro, MA**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65 for far field modeling calculations.

In OET-65, plane wave power densities in the Far Field of an antenna are calculated by considering antenna gain and reflective waves that would contribute to exposure.

Since the radiation pattern of an antenna has developed in the **Far Field** region the power gain in specific directions needs to be considered in exposure predictions to yield an Effective Radiated Power (ERP) in each specific direction from the antenna. Also, since the vertical radiation pattern of the antenna is considered, the exposure calculations would most likely be reduced significantly at ground level, resulting in a more realistic estimate of the actual exposure levels. To determine a worst-case scenario at each point along the calculation radials, each point was calculated using the antenna gain value at each angle of incident and compared against the result using an isotropic radiator at the antenna height with the greater of the two used to yield the more pessimistic far field value for each point along the calculation radial.

Additionally, to model a truly "worst case" prediction of exposure levels at or near a surface, such as at ground-level or on a rooftop, reflection off the surface of antenna radiation power can be assumed, resulting in a potential 1.6 times increase in power density in calculating far field power density values.

With these factors Considered, the worst case **Far Field prediction model** utilized in this analysis is determined by the following equation:

Equation 9 per FCC OET65 for Far Field Modeling

$$S = \frac{33.4 \ ERP}{R^2}$$

S = Power Density (in μ w/cm²)

ERP = Effective Radiated Power from antenna (watts)

R = Distance from the antenna (meters)

Predicted far field power density values for all carriers identified in this report were calculated 6 feet above the ground level and are displayed as a percentage of the applicable FCC standards. All emissions values for other carriers were calculated using the same Far Field model outlined above, using industry standard radio configurations and frequency band selection based upon available licenses in this geographic area for emissions contribution estimates.



For each Dish sector the following channel counts, frequency bands and power levels were utilized as shown in *Table 1*:

Technology	Frequency Band	Channel Count	Transmit Power per Channel (W)
5G	n71 (600 MHz)	4	61.5
5G	n70 (AWS-4 / 1995-2020)	4	40
5G	n66 (AWS-4 / 2180-2200)	4	40

Table 1: Channel Data Table



The following **Dish** antennas listed in *Table 2* were used in the modeling for transmission in the 600 MHz (n71) frequency band and the 2100 MHz (AWS 4) frequency bands at 1995-2020 MHz (n70) and 2180-2200 MHz (n66). This is based on feedback from Dish regarding anticipated antenna selection. Maximum gain values for all antennas are listed in the Inventory and Power Data table below.

			Antenna
	Antenna		Centerline
Sector	Number	Antenna Make / Model	(ft)
A	1	JMA MX08FRO665-21	155
В	1	JMA MX08FRO665-21	155
С	1	JMA MX08FRO665-21	155

Table 2: Antenna Data

All calculations were done with respect to uncontrolled / general population threshold limits.



RESULTS

Per the calculations completed for the proposed **Dish** configurations *Table 3* shows resulting emissions power levels and percentages of the FCC's allowable general population limit.

Antenna	Antenna Make /		Antenna Gain	Channel	Total TX		1.000.4
ID	Model	Frequency Bands	(dBd)	Count	Power (W)	ERP (W)	MPE %
		n71 (600 MHz)/					
Antenna	JMA	n70 (AWS-4 / 1995-2020) /	11.45 / 16.15 /				
A1	MX08FRO665-21	n66 (AWS-4 / 2180-2200)	16.65	12	566	17,426.72	3.59
				Ç	Sector A Comp	osite MPE%	3.59
		n71 (600 MHz)/					
Antenna	JMA	n70 (AWS-4 / 1995-2020) /	11.45 / 16.15 /				
B1	MX08FRO665-21	n66 (AWS-4 / 2180-2200)	16.65	12	566	17,426.72	3.59
				Š	Sector B Comp	osite MPE%	3.59
		n71 (600 MHz)/					
Antenna	JMA	n70 (AWS-4 / 1995-2020) /	11.45 / 16.15 /				
C1	MX08FRO665-21	n66 (AWS-4 / 2180-2200)	16.65	12	566	17,426.72	3.59
Sector C Composite MPE%							3.59

Table 3: Dish Emissions Levels



The Following table (*Table 4*) shows all additional carriers on site and their emissions contribution estimates, along with the newly calculated **Dish** far field emissions contributions per this report. FCC OET 65 specifies that for carriers utilizing directional antennas the highest recorded sector value be used for composite site emissions values due to their greatly reduced emissions contributions in the directions of the adjacent sectors. For this site, all three sectors have the same configuration yielding the same results for all three sectors. *Table 5* below shows a summary for each **Dish** Sector as well as the composite emissions value for the site.

Site Composite MPE%				
Carrier	MPE%			
Dish – Max Per Sector Value	3.59 %			
AT&T	2.76 %			
T-Mobile	1.58 %			
Verizon Wireless	3.04 %			
Sprint	0.97 %			
Site Total MPE %:	11.94 %			

Table 4: All Carrier MPE Contributions

Dish Sector A Total:	3.59 %			
Dish Sector B Total:	3.59 %			
Dish Sector C Total:	3.59 %			
Site Total:	11.94 %			

Table 5: Site MPE Summary



Table 6 below details a breakdown by frequency band and technology for the MPE power values for the maximum calculated **Dish** sector(s). For this site, all three sectors have the same configuration yielding the same results for all three sectors.

Dish _ Frequency Band / Technology Max Power Values (Per Sector)	# Channels	Watts ERP (Per Channel)	Height (feet)	Total Power Density (µW/cm²)	Frequency (MHz)	Allowable MPE (µW/cm²)	Calculated % MPE
Dish n71 (600 MHz) 5G	4	858.77	155	3.52	n71 (600 MHz)	400	0.88%
Dish n70 (AWS-4 / 1995-2020) 5G	4	1,648.39	155	8.80	n70 (AWS-4 / 1995-2020)	1000	0.88%
Dish n66 (AWS-4 / 2180-2200) 5G	4	1,849.52	155	18.30	n66 (AWS-4 / 2180-2200)	1000	1.83%
						Total:	3.59 %

Table 6: Dish Maximum Sector MPE Power Values



Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general population exposure to RF Emissions.

The anticipated maximum composite contributions from the Dish facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general population exposure to RF Emissions are shown here:

Dish Sector	Power Density Value (%)	
Sector A:	3.59 %	
Sector B:	3.59 %	
Sector C:	3.59 %	
Dish Maximum Total	3.59 %	
(per sector):	3.39 %	
Site Total:	11.94 %	
Site Compliance Status:	COMPLIANT	

The anticipated composite emissions value for this site, assuming all carriers present, is 11.94 % of the allowable FCC established general population limit sampled at the ground level. This is based upon the far field calculations performed for all carriers identified in this report.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Scott Heffernan Principal RF Engineer

Fox Hill Telecom, Inc Worcester, MA 01609

(978)660-3998